

8" Interior CMU

Class	Material ID	Description	Quantity	Amount	Lay Rate	Hand-written notes
CMU	MW08B	8" Mediumweight CMU-Bull	11 Pieces	9.778 SF	135.0 Pieces/Day	
CMU	MW08BB	8" MW CMU Bond Beam	4 Pieces	3.111 SF	120.0 Pieces/Day	
CMU	MW08BH	8"Lt Wt CMU-1/2 Bullnose	11 Pieces	4.889 SF	130.0 Pieces/Day	
CMU	MW08INT	Interior 8" MW CMU	389 Pieces	345.778 SF	150.0 Pieces/Day	
DF	DF3-4X7-4	Door Frame 3'-4"x7'-4"	1 Each	1.000 Ea	8.0 Each/Day	
GRO	3000PSI	3000 PSI Grout in Cu.Ft.	1 CbcFt	1.099 CF	175.0 CbcFt/Day	
MOR	MORTARDF	Door Frame Mortar	2 CbcFt	1.778 CF	120.0 CbcFt/Day	
MOR	MORTARJ	Fill for Jamb Cell/Mortar	3 CbcFt	2.815 CF	120.0 CbcFt/Day	
MOR	Type N Port/Lime	1:1:6 Mix	22 CbcFt	22.309 CF	0.0 CbcFt/Day	
REB	#4 56"BAR	#4 Bond Beam 56" Pcs	2 Pieces	9.333 LF	385.7 Pieces/Day	
WIR	MGT9GA08"	Mill-Gal./Truss 9ga-- 8"	270 LinFt	270.222 LF	0.0 LinFt/Day	

14" Exterior-Vert Rebar

Class	Material ID	Description	Quantity	Amount	Lay Rate	Hand-written notes
BOL	BOLTS8-IN	100 CNT BOXES OF 8" BOLTS	40 Each	40.000 Ea	1200.0 Each/Day	
BRI	M	Modular Brick	9,852 Pieces	1,459.259 SF	450.0 Pieces/Day	
BRI	MS	Modular Brick Soldier	1,212 Pieces	179.556 SF	300.0 Pieces/Day	
BRI	MW	Modular Pier Brick-White	1,296 Pieces	192.000 SF	400.0 Pieces/Day	
CMU	CMU SILL	8"Lt Wt CMU-1/2 Bullnose	10 Pieces	4.444 SF	130.0 Pieces/Day	
CMU	MW08	8" Mediumweight CMU	1,538 Pieces	1,367.111 SF	170.0 Pieces/Day	
CMU	MW08B	8" Mediumweight CMU-Bull	100 Pieces	88.889 SF	135.0 Pieces/Day	
CMU	MW08BB	8" MW CMU Bond Beam	151 Pieces	134.222 SF	120.0 Pieces/Day	
CMU	MW08BH	8"Lt Wt CMU-1/2 Bullnose	100 Pieces	44.444 SF	130.0 Pieces/Day	
CMU	MW08PIER	8" Mediumweight CMU	324 Pieces	288.000 SF	140.0 Pieces/Day	
CMU	MW08S	8"Lt Wt CMU-Sash Full	120 Pieces	106.667 SF	160.0 Pieces/Day	
CMU	MW08SH	8"Lt Wt CMU-Sash Half	120 Pieces	53.333 SF	160.0 Pieces/Day	
CMU	PIER4CMU	4"CMU-Fill@back of brick	108 Pieces	96.000 SF	185.0 Pieces/Day	
CON	CJ	Control Joint Material	84 LinFt	84.000 LF	2000.0 LinFt/Day	
DF	DF3-4X7-4	Door Frame 3'-4"x7'-4"	8 Each	8.000 Ea	8.0 Each/Day	
DRI	COPPERDRI	Copper Drip Edge	135 LinFt	134.667 LF	2000.0 LinFt/Day	
FLA	IPCO18"	IPCO 18" Flashing	135 LinFt	134.667 LF	3000.0 LinFt/Day	
GRO	3000PSI	3000 PSI Grout in Cu.Ft.	135 CbcFt	134.744 CF	175.0 CbcFt/Day	
INR	BLUE2"	Blue 2" Rigid Insulation	1,990 SqFt	1,989.778 SF	1500.0 SqFt/Day	
LIL	2X5SILLR	2-1/4 x 5 Sills	2 Pieces	7.333 LF	67.2 Pieces/Day	
LIL	COPING	Limestone Coping - LF	39 Pieces	156.667 LF	12.5 Pieces/Day	
LIL	PILASTCAP	4"x4"x24" Pilaster Cap	6 Pieces	12.000 LF	50.0 Pieces/Day	
MOR	MORTARDF	Door Frame Mortar	14 CbcFt	14.222 CF	120.0 CbcFt/Day	
MOR	MORTARJ	Fill for Jamb Cell/Mortar	28 CbcFt	28.152 CF	120.0 CbcFt/Day	
MOR	Type N Port/Lime	1:1:6 Mix	423 CbcFt	422.854 CF	0.0 CbcFt/Day	
MOR	Type S Port/Lime	1:1/2:4-1/2 Mix	31 CbcFt	31.112 CF	0.0 CbcFt/Day	
MOR	Type N White Port/Lime--Silica Sand		10 CbcFt	9.675 CF	0.0 CbcFt/Day	
REB	#4 14'-0"	#4 Vt Rebar14'-0"Long Pcs	39 Pieces	546.000 LF	128.6 Pieces/Day	
REB	#4 56"BAR	#4 Bond Beam 56" Pcs	20 Pieces	93.333 LF	385.7 Pieces/Day	
REB	#4BB 20-0	#4 Bond Beam 20'-0" Pcs	17 Pieces	336.000 LF	90.0 Pieces/Day	
SPL	SF04	4" Splitface	258 Pieces	229.333 SF	145.0 Pieces/Day	
WEE	WEEPPLAS	Plastic Weep Holes	67 Each	67.333 Ea	3000.0 Each/Day	
WIR	HDT9GA14"	Hot-Dipp./Truss 9ga--14"	1,608 LinFt	1,607.877 LF	0.0 LinFt/Day	