

Wall

Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
----------	--------------------	----------	--------	--------	--------	-----	-----	-----	-----	-------

Classification **AIR**

Air Deduction

T	MW10AIR	10" Mediumweight CMU	Lay	125.0	Pieces/Day	\$1.170/ Piece	SqFt	3.00% waste	1.125	Pieces per SqFt		
B	Arch on Piers @ Ent for Mark?		33	Pieces		\$38.07	\$195.09	28.083	3' 0"	17' 0"	1 Opn	Rect
T	SQ FT-AIR	Air deduction for any mat	Lay	0.0	Pieces/Day	\$0.000/ Piece	SqFt	1.125	Pieces per SqFt			
B	(8 CMU) Splitface Top Radius		154	Pieces		\$0.00	\$0.00	136.953	6' 0"	41' 4"	1 Opn	Rect
B	North wall of Cafetorium SGT		116	Pieces		\$0.00	\$0.00	102.667	26' 0"	22' 0"	1 Opn Odd	Rect
B	Arch on Piers @ Ent for Mark?		32	Pieces		\$0.00	\$0.00	28.083	3' 0"	17' 0"	1 Opn	Rect
A	West wall Gym		1,654	Pieces		\$0.00	\$0.00	1,470.198	33' 8"	89' 8"	1 Opn Odd	Rect
B	8 CMU Top Radius@ Band		154	Pieces		\$0.00	\$0.00	136.950	6' 0"	41' 4"	1 Opn	Rect
CA#1	Alt#1 North Brick&CMU		1,470	Pieces		\$0.00	\$0.00	1,306.667	40' 0"	57' 0"	1 Opn Odd	Rect
C	Col 23 F.5 to N 3 story Classr		6,177	Pieces		\$0.00	\$0.00	5,490.889	40' 0"	290' 2"	1 Opn Odd	Rect
B	Alt#2 (part out)33-8 N Band Rm		665	Pieces		\$0.00	\$0.00	590.792	33' 8"	54' 3"	1 Opn Odd	Rect
B	E6 between 12.3 & 17 South Wal		827	Pieces		\$0.00	\$0.00	735.111	26' 0"	94' 0"	1 Opn Odd	Rect
A	18" Ext @ Cafetorium		766	Pieces		\$0.00	\$0.00	680.996	22' 8"	114' 0"	1 Opn Odd Adj	Rect
B	North wall of Cafetorium		416	Pieces		\$0.00	\$0.00	370.222	26' 0"	79' 4"	1 Opn Odd Adj	Rect
B	West Wall Vest B123 NO Insul		72	Pieces		\$0.00	\$0.00	64.000	28' 8"	26' 0"	1 Opn Odd	Rect
A	(8 CMU) Top Radius		98	Pieces		\$0.00	\$0.00	86.762	5' 1"	50' 4"	1 Opn	Rect
Material [SQ FT-AIR] Totals			12,600	Pieces		\$0.00	\$0.00	11,200.289	Mat. Lay Rate 0.0 Pieces/Day			
Class Totals Air Deduction			12,633	Pieces		\$38.07	\$195.09	11,228.372	Avg. Lay Rate 49,978.7 Pieces/Day			

Classification **ANC**

WALL ANCHORS

	2PCSSCREW	2 pcs screw on Veneer anc	Lay	200.0	Each/Day	\$1.000/ Each	Each	Show as Each				
	Brick Piers in Learning Center		27	Each		\$26.54	\$102.43	26.541	3' 4"	20' 8"	1	Rect
	Brick Piers in Learning Center		40	Each		\$40.00	\$154.38	40.000	3' 4"	8' 0"	4	Pier
Material [2PCSSCREW] Totals			67	Each		\$66.54	\$256.81	66.541	Mat. Lay Rate 200.0 Each/Day			

Classification **BOL**

ANCHOR BOLTS

	BOLTS8-IN	100 CNT BOXES OF 8" BOLTS	Lay	1,200.0	Each/Day	\$0.400/ Each	Each	Show as Each				
A	Ext Col A		70	Each		\$28.00	\$45.03	70.000	16' 8"	279' 3"	1 Opn Odd	Rect
B	(8 CMU) Splitface Top Radius		11	Each		\$4.40	\$7.08	11.000	6' 0"	41' 4"	1 Opn	Rect
B	North wall of Cafetorium SGT		6	Each		\$2.40	\$3.86	6.000	26' 0"	22' 0"	1 Opn Odd	Rect
CA#1	Alt#1 42-8 N & S Full Brick		9	Each		\$3.60	\$5.79	9.000	42' 8"	36' 0"	1 Opn Odd Adj	Rect
A	West wall Gym		23	Each		\$9.20	\$14.79	23.000	33' 8"	89' 8"	1 Opn Odd	Rect
B	8 CMU Top Radius@ Band		11	Each		\$4.40	\$7.08	11.000	6' 0"	41' 4"	1 Opn	Rect
C	42-8 N & S Full Brick		9	Each		\$3.60	\$5.79	9.000	42' 8"	36' 0"	1 Opn Odd	Rect
CA#1	Alt#1 North Brick&CMU		15	Each		\$6.00	\$9.65	15.000	40' 0"	57' 0"	1 Opn Odd	Rect
C	Col 23 F.5 to N 3 story Classr		73	Each		\$29.20	\$46.96	73.000	40' 0"	290' 2"	1 Opn Odd	Rect
CA#1	Alt#1 Returns 1-2" E.5		2	Each		\$0.80	\$1.29	2.000	8' 8"	1' 2"	2	Odd Gable
CA#1	Alt#1 Cor Ent ReturnsCol E.5		2	Each		\$0.80	\$1.29	2.000	8' 8"	6' 8"	1	Odd Rect
C	Cor Ent ReturnsCol E.5		2	Each		\$0.80	\$1.29	2.000	8' 8"	6' 8"	1	Odd Rect
C	Returns 1-2" E.5		2	Each		\$0.80	\$1.29	2.000	8' 8"	1' 2"	2	Odd Gable
C	Col 17 between E.5 & H.9		22	Each		\$8.80	\$14.15	22.000	40' 0"	85' 7"	1 Opn Odd	Rect
B	Alcove B127a N Band Rm		15	Each		\$6.00	\$9.65	15.000	19' 8"	58' 4"	1 Opn Odd	Rect
B	N Mech Rm 33-8		38	Each		\$15.20	\$24.44	38.000	20' 4"	149' 8"	1 Opn Odd	Rect
B	Alt#2 (part out)33-8 N Band Rm		14	Each		\$5.60	\$9.01	14.000	33' 8"	54' 3"	1 Opn Odd	Rect

Sample Reports
Quantity/Bid Price Report

BOL Continued

						Wall						
		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
B	E6 between 12.3 & 17 South Wal	24	Each	\$9.60	\$15.44	24.000	26' 0"	94' 0"	1	Opn	Odd	Rect
B	W Wall (12 CMU) Band B127	15	Each	\$6.00	\$9.65	15.000	20' 0"	57' 0"	1	Opn	Odd	Rect
B2	(12 CMU) IDF D226	3	Each	\$1.20	\$1.93	3.000	15' 0"	12' 0"	1		Odd	Rect
B	Alcove B127a N Band Rm @26-0	11	Each	\$4.40	\$7.08	11.000	10' 8"	41' 4"	1		Odd	Rect
B	Alt2(out)Cor Ent ReturnsCol #3	2	Each	\$0.80	\$1.29	2.000	8' 8"	6' 4"	1		Odd	Rect
B	Alt2 (out) Returns 1-2" Col #3	2	Each	\$0.80	\$1.29	2.000	8' 8"	1' 2"	2		Odd	Gable
A	Returns 1-2"	2	Each	\$0.80	\$1.29	2.000	8' 8"	1' 2"	2		Odd	Gable
B	Alt#2 (part out)22-8 N Band Rm	21	Each	\$8.40	\$13.51	21.000	22' 8"	82' 4"	1	Opn	Odd	Rect
A	Corr Ent Returns	2	Each	\$0.80	\$1.29	2.000	8' 8"	6' 8"	1		Odd	Rect
B	E Wall (12 CMU) Band B127	9	Each	\$3.60	\$5.79	9.000	22' 8"	35' 0"	1		Odd	Rect
A	N Wall (12 CMU) Serving #119	12	Each	\$4.80	\$7.72	12.000	22' 8"	45' 0"	1	Opn	Odd	Rect
A	18" Ext @ Cafetorium	29	Each	\$11.60	\$18.65	29.000	22' 8"	114' 0"	1	Opn	Odd	Adj
A	Alt2 12CMU Col 4.3 @ C&D (Out)	12	Each	\$4.80	\$7.72	12.000	33' 8"	48' 0"	1	Opn	Odd	Rect
B	H7 between 6 & 6.8 N Ext Wall	13	Each	\$5.20	\$8.36	13.000	16' 0"	50' 8"	1	Opn	Odd	Rect
B	West Wall Vest B123 with Insul	3	Each	\$1.20	\$1.93	3.000	28' 8"	9' 8"	1	Opn	Odd	Rect
B	North wall of Cafetorium	20	Each	\$8.00	\$12.86	20.000	26' 0"	79' 4"	1	Opn	Odd	Adj
B	West Wall Vest B123 NO Insul	7	Each	\$2.80	\$4.50	7.000	28' 8"	26' 0"	1	Opn	Odd	Rect
B	East Wall Vest B123 NO Insul	7	Each	\$2.80	\$4.50	7.000	13' 4"	26' 8"	1	Opn	Odd	Rect
B	8" CMUf @ roof Col 10.1&10.9	41	Each	\$16.40	\$26.37	41.000	7' 4"	161' 4"	1		Odd	Rect
B	8" CMU Fill in @ roof	1	Each	\$0.40	\$0.64	1.000	4' 8"	1' 8"	1		Odd	Rect
B	N Wall Top of Main ent.	18	Each	\$7.20	\$11.58	18.000	22' 8"	69' 8"	1	Opn	Odd	Rect
B	N Wall Top of Main ent.	14	Each	\$5.60	\$9.01	14.000	18' 8"	55' 4"	1	Opn	Odd	Rect
B	N Wall Office B13 & 140	6	Each	\$2.40	\$3.86	6.000	13' 4"	24' 0"	1	Opn	Odd	Rect
B	N Wall Confere B138 with Insul	13	Each	\$5.20	\$8.36	13.000	13' 4"	49' 8"	1	Opn	Odd	Rect
B	H10 between 6.9 & 9	5	Each	\$2.00	\$3.22	5.000	19' 0"	18' 4"	1	Opn	Odd	Rect
B	East Wall Vest B123 with Insul	4	Each	\$1.60	\$2.57	4.000	13' 4"	12' 8"	1	Opn	Odd	Rect
B	E6 between 12???????????	10	Each	\$4.00	\$6.43	10.000	28' 8"	39' 0"	1	Opn	Odd	Rect
B	E&W Walls Office B136 & 140	7	Each	\$2.80	\$4.50	7.000	10' 0"	25' 1"	1			Rect
B	Below barrel parapet	11	Each	\$4.40	\$7.08	11.000	10' 8"	41' 4"	1		Odd	Rect
A	(8 CMU) Top Radius	13	Each	\$5.20	\$8.36	13.000	5' 1"	50' 4"	1	Opn		Rect
A	(12 CMU) So Gym A108 "no" SGT	25	Each	\$10.00	\$16.08	25.000	33' 8"	99' 4"	1	Opn	Odd	Rect
A	(12 CMU) No Gym A108 "no" SGT	25	Each	\$10.00	\$16.08	25.000	33' 8"	98' 4"	1	Opn	Odd	Rect
A	(12 CMU) Gym A108 SGT	32	Each	\$12.80	\$20.58	32.000	33' 8"	125' 0"	1	Opn	Odd	Rect
Material [BOLTS8-IN] Totals		743	Each	\$297.20	\$477.93	743.000	Mat. Lay Rate	1,200.0	Each/Day			

Classification **BRI**

BRICKS

U325A		Utility Brick A Color	Lay	390.0 Pieces/Day	\$1.000/ Piece	SqFt	3.00% waste	3.000	Pieces per SqFt			
A	Ext Col A	12,398	Pieces	\$12,397.77	\$23,822.89	4,012.225	16' 8"	279' 3"	1	Opn	Odd	Rect
B	Arch on Piers @ Ent for Mark?	215	Pieces	\$215.39	\$413.88	69.706	4' 4"	20' 0"	1	Opn	Odd	Rect
A	West wall Gym	3,508	Pieces	\$3,508.34	\$6,741.44	1,135.386	33' 8"	89' 8"	1	Opn	Odd	Rect
CA#1	Alt#1 North Brick&CMU	2,031	Pieces	\$2,030.82	\$3,902.31	657.222	40' 0"	57' 0"	1	Opn	Odd	Rect
C	Col 23 F.5 to N 3 story Classr	8,707	Pieces	\$8,707.11	\$16,731.10	2,817.833	40' 0"	290' 2"	1	Opn	Odd	Rect
CA#1	Alt#1 Returns 1-2" E.5	5	Pieces	\$4.81	\$9.24	1.556	8' 8"	1' 2"	2		Odd	Gable
CA#1	Alt#1 Cor Ent ReturnsCol E.5	14	Pieces	\$13.73	\$26.39	4.444	8' 8"	6' 8"	1		Odd	Rect
C	Cor Ent ReturnsCol E.5	14	Pieces	\$13.73	\$26.39	4.444	8' 8"	6' 8"	1		Odd	Rect
C	Returns 1-2" E.5	5	Pieces	\$4.81	\$9.24	1.556	8' 8"	1' 2"	2		Odd	Gable
B	Alcove B127a N Band Rm	123	Pieces	\$122.54	\$235.46	39.655	19' 8"	58' 4"	1	Opn	Odd	Rect
B	Alt#2 (part out)33-8 N Band Rm	136	Pieces	\$135.57	\$260.51	43.875	33' 8"	54' 3"	1	Opn	Odd	Rect
B	E6 between 12.3 & 17 South Wal	2,960	Pieces	\$2,960.22	\$5,688.20	958.000	26' 0"	94' 0"	1	Opn	Odd	Rect
	Dumpster Privacy Wall	1,932	Pieces	\$1,932.28	\$3,712.96	625.333	8' 0"	28' 2"	1		Odd	Rect
	Dumpster Privacy Wall Ends	297	Pieces	\$296.64	\$570.01	96.000	8' 0"	6' 0"	2			Pier

Sample Reports
Quantity/Bid Price Report

BRI Continued

Wall

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
B	Alt2(out)Cor Ent ReturnsCol #3	13	Pieces \$13.05	\$25.07	4.222	8' 8"	6' 4"	1		Odd		Rect
B	Alt2 (out) Returns 1-2" Col #3	5	Pieces \$4.81	\$9.24	1.556	8' 8"	1' 2"	2		Odd		Gable
A	Returns 1-2"	58	Pieces \$57.68	\$110.83	18.667	8' 8"	1' 2"	2		Odd		Gable
B	Alt#2 (part out)22-8 N Band Rm	233	Pieces \$232.78	\$447.30	75.333	22' 8"	82' 4"	1	Opn	Odd		Rect
A	Corr Ent Returns	165	Pieces \$164.80	\$316.67	53.333	8' 8"	6' 8"	1		Odd		Rect
B	E Wall (12 CMU) Band B127	72	Pieces \$72.10	\$138.54	23.333	22' 8"	35' 0"	1		Odd		Rect
A	N Wall (12 CMU) Serving #119	93	Pieces \$92.70	\$178.13	30.000	22' 8"	45' 0"	1	Opn	Odd		Rect
A	18" Ext @ Cafetorium	263	Pieces \$262.65	\$504.69	85.000	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
B	H7 between 6 & 6.8 N Ext Wall	1,497	Pieces \$1,496.93	\$2,876.43	484.444	16' 0"	50' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 with Insul	522	Pieces \$521.52	\$1,002.13	168.778	28' 8"	9' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 NO Insul	1,371	Pieces \$1,371.27	\$2,634.96	443.777	28' 8"	26' 0"	1	Opn	Odd		Rect
B	East Wall Vest B123 NO Insul	397	Pieces \$397.24	\$763.31	128.556	13' 4"	26' 8"	1	Opn	Odd		Rect
B	Top of Piers @ Ent	1,066	Pieces \$1,066.07	\$2,048.50	345.006	4' 4"	55' 2"	1	Opn	Odd		Rect
B	N Wall Top of Main ent.	1,523	Pieces \$1,523.01	\$2,926.54	492.884	18' 8"	55' 4"	1	Opn	Odd		Rect
B	N Wall Confere B138 with Insul	930	Pieces \$930.28	\$1,787.57	301.061	13' 4"	49' 8"	1	Opn	Odd		Rect
B	H10 between 6.9 & 9	809	Pieces \$808.93	\$1,554.39	261.789	19' 0"	18' 4"	1	Opn	Odd		Rect
B	East Wall Vest B123 with Insul	290	Pieces \$289.76	\$556.80	93.775	13' 4"	12' 8"	1	Opn	Odd		Rect
B	E6 between 12???????????	2,082	Pieces \$2,082.18	\$4,001.00	673.843	28' 8"	39' 0"	1	Opn	Odd		Rect
A	(12 CMU) So Gym A108 "no" SGT	34	Pieces \$34.33	\$65.97	11.111	33' 8"	99' 4"	1	Opn	Odd		Rect
Material [U325A] Totals		43,766	Pieces \$43,765.85	\$84,098.08	14,163.704	Mat. Lay Rate	390.0	Pieces/Day				

U325ACLOS Closer Brick A Color		Lay	400.0 Pieces/Day	\$0.850/ Piece	SqFt	3.00% waste	4.500	Pieces per SqFt				
A	Ext Col A	23	Pieces	\$19.26	\$42.45	4.889	16' 8"	279' 3"	1	Opn	Odd	Rect
A	(8 CMU) Corr A106 SGT	45	Pieces	\$38.52	\$84.91	9.778	21' 4"	22' 4"	1	Opn	Odd	Adj Rect
CA#1	Alt#1 42-8 N & S Full Brick	117	Pieces	\$99.81	\$219.99	25.333	42' 8"	36' 0"	1	Opn	Odd	Adj Rect
A	West wall Gym	68	Pieces	\$57.78	\$127.36	14.667	33' 8"	89' 8"	1	Opn	Odd	Rect
C	42-8 N & S Full Brick	142	Pieces	\$120.82	\$266.30	30.667	42' 8"	36' 0"	1	Opn	Odd	Rect
C	Col 23 F.5 to N 3 story Classr	445	Pieces	\$378.22	\$833.64	96.000	40' 0"	290' 2"	1	Opn	Odd	Rect
B	8" CMU Corr with SGT base	60	Pieces	\$50.78	\$111.92	12.889	13' 4"	497' 4"	1	Opn	Odd	Rect
C	Col 17 between E.5 & H.9	45	Pieces	\$38.52	\$84.91	9.778	40' 0"	85' 7"	1	Opn	Odd	Rect
B	Alcove B127a N Band Rm	55	Pieces	\$46.84	\$103.24	11.889	19' 8"	58' 4"	1	Opn	Odd	Rect
B	E6 between 12.3 & 17 South Wal	124	Pieces	\$105.06	\$231.57	26.667	26' 0"	94' 0"	1	Opn	Odd	Rect
B	Alt#2 (part out)22-8 N Band Rm	16	Pieces	\$14.01	\$30.88	3.556	22' 8"	82' 4"	1	Opn	Odd	Rect
A	18" Ext @ Cafetorium	237	Pieces	\$201.37	\$443.83	51.111	22' 8"	114' 0"	1	Opn	Odd	Adj Rect
B	H7 between 6 & 6.8 N Ext Wall	74	Pieces	\$63.04	\$138.94	16.000	16' 0"	50' 8"	1	Opn	Odd	Rect
B	West Wall Vest B123 with Insul	9	Pieces	\$7.88	\$17.37	2.000	28' 8"	9' 8"	1	Opn	Odd	Rect
B	8"CMU Corr SGT13-0 FireS	23	Pieces	\$19.26	\$42.45	4.889	13' 0"	83' 7"	1	Opn	Odd	Rect
B	North wall of Cafetorium	23	Pieces	\$19.26	\$42.45	4.889	26' 0"	79' 4"	1	Opn	Odd	Adj Rect
B	West Wall Vest B123 NO Insul	19	Pieces	\$15.76	\$34.73	4.000	28' 8"	26' 0"	1	Opn	Odd	Rect
B	East Wall Vest B123 NO Insul	33	Pieces	\$28.02	\$61.75	7.111	13' 4"	26' 8"	1	Opn	Odd	Rect
B	N Wall Top of Main ent.	109	Pieces	\$92.80	\$204.55	23.556	22' 8"	69' 8"	1	Opn	Odd	Rect
B	N Wall Top of Main ent.	144	Pieces	\$122.57	\$270.16	31.111	18' 8"	55' 4"	1	Opn	Odd	Rect
B	N Wall Office B13 & 140	33	Pieces	\$28.02	\$61.75	7.111	13' 4"	24' 0"	1	Opn	Odd	Rect
B	N Wall Confere B138 with Insul	49	Pieces	\$42.02	\$92.63	10.667	13' 4"	49' 8"	1	Opn	Odd	Rect
B	H10 between 6.9 & 9	9	Pieces	\$7.88	\$17.37	2.000	19' 0"	18' 4"	1	Opn	Odd	Rect
B	East Wall Vest B123 with Insul	16	Pieces	\$14.01	\$30.88	3.556	13' 4"	12' 8"	1	Opn	Odd	Rect
B	E6 between 12???????????	92	Pieces	\$77.92	\$171.74	19.778	28' 8"	39' 0"	1	Opn	Odd	Rect
A	(12 CMU) So Gym A108 "no" SGT	23	Pieces	\$19.26	\$42.45	4.889	33' 8"	99' 4"	1	Opn	Odd	Rect
A	(12 CMU) No Gym A108 "no" SGT	54	Pieces	\$45.53	\$100.35	11.556	33' 8"	98' 4"	1	Opn	Odd	Rect
A	(12 CMU) Around Stage A110	45	Pieces	\$38.52	\$84.91	9.778	21' 4"	176' 0"	1	Opn		Rect
Material [U325ACLOS] Totals		2,133	Pieces	\$1,812.72	\$3,995.47	460.111	Mat. Lay Rate	400.0	Pieces/Day			

BRI Continued

Wall

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
U325AS Util Brick A Color Slow		Lay 200.0 Pieces/Day	\$1,000/ Piece		SqFt	3.00% waste	3.000	Pieces per SqFt				
CA#1	Alt#1 42-8 N & S Full Brick	83 Pieces	\$83.26	\$311.97	26.944	42' 8"	36' 0"	1	Opn	Odd	Adj	Rect
B	Arch on Piers @ Ent for Mark?	71 Pieces	\$70.81	\$265.34	22.917	3' 0"	17' 0"	1	Opn			Rect
A	West wall Gym	347 Pieces	\$346.77	\$1,299.34	112.222	33' 8"	89' 8"	1	Opn	Odd		Rect
C	42-8 N & S Full Brick	83 Pieces	\$83.26	\$311.97	26.944	42' 8"	36' 0"	1	Opn	Odd		Rect
B	Alcove B127a N Band Rm	238 Pieces	\$237.88	\$891.35	76.985	19' 8"	58' 4"	1	Opn	Odd		Rect
B	Alt#2 (part out)33-8 N Band Rm	201 Pieces	\$200.68	\$751.94	64.944	33' 8"	54' 3"	1	Opn	Odd		Rect
	Brick Piers in Learning Center	179 Pieces	\$179.33	\$671.96	58.036	3' 4"	20' 8"	1				Rect
	Brick Piers in Learning Center	275 Pieces	\$274.67	\$1,029.18	88.889	3' 4"	8' 0"	4				Pier
B	Alt#2 (part out)22-8 N Band Rm	319 Pieces	\$318.61	\$1,193.85	103.111	22' 8"	82' 4"	1	Opn	Odd		Rect
B	Piers @ Ent B123 Arch	165 Pieces	\$164.80	\$617.51	53.333	9' 8"	6' 4"	2		Odd		Pier
B	N Main Ent Brick Piers	1,226 Pieces	\$1,226.38	\$4,595.28	396.888	10' 0"	49' 9"	1				Rect
B	H10 between 6.9 & 9	70 Pieces	\$70.43	\$263.92	22.794	19' 0"	18' 4"	1	Opn	Odd		Rect
B	Face of Pier veneer	130 Pieces	\$129.86	\$486.60	42.027	9' 8"	9' 4"	1		Odd		Rect
B	2x1-2 Pier @ 6.8 & 8	88 Pieces	\$87.89	\$329.34	28.444	9' 8"	4' 0"	2		Odd		Pier
B	2x1-2 Pier @ 6.8 & 8	165 Pieces	\$164.80	\$617.51	53.333	9' 8"	6' 4"	2		Odd		Pier
Material [U325AS] Totals		3,639 Pieces	\$3,639.45	\$13,637.06	1,177.815	Mat. Lay Rate		200.0 Pieces/Day				
U325AS45C Util A Color Special 45		Lay 200.0 Pieces/Day	\$4,500/ Piece		SqFt	3.00% waste	3.000	Pieces per SqFt				
A	Ext Col A	93 Pieces	\$417.15	\$347.35	30.000	16' 8"	279' 3"	1	Opn	Odd		Rect
B	N Main Ent Brick Piers	62 Pieces	\$278.10	\$231.57	20.000	10' 0"	49' 9"	1				Rect
Material [U325AS45C] Totals		155 Pieces	\$695.25	\$578.91	50.000	Mat. Lay Rate		200.0 Pieces/Day				
U325B Utility Brick B Color		Lay 390.0 Pieces/Day	\$1,000/ Piece		SqFt	3.00% waste	3.000	Pieces per SqFt				
A	Ext Col A	1,303 Pieces	\$1,302.87	\$2,503.52	421.640	16' 8"	279' 3"	1	Opn	Odd		Rect
CA#1	Alt#1 42-8 N & S Full Brick	3,399 Pieces	\$3,399.42	\$6,532.14	1,100.135	42' 8"	36' 0"	1	Opn	Odd	Adj	Rect
A	West wall Gym	413 Pieces	\$413.31	\$794.20	133.758	33' 8"	89' 8"	1	Opn	Odd		Rect
C	42-8 N & S Full Brick	3,409 Pieces	\$3,408.69	\$6,549.95	1,103.135	42' 8"	36' 0"	1	Opn	Odd		Rect
CA#1	Alt#1 North Brick&CMU	154 Pieces	\$154.50	\$296.87	49.999	40' 0"	57' 0"	1	Opn	Odd		Rect
C	Col 23 F.5 to N 3 story Classr	576 Pieces	\$576.29	\$1,107.36	186.500	40' 0"	290' 2"	1	Opn	Odd		Rect
CA#1	Alt#1 Returns 1-2" E.5	58 Pieces	\$57.68	\$110.83	18.667	8' 8"	1' 2"	2		Odd		Gable
CA#1	Alt#1 Cor Ent ReturnsCol E.5	165 Pieces	\$164.80	\$316.67	53.333	8' 8"	6' 8"	1		Odd		Rect
C	Cor Ent ReturnsCol E.5	165 Pieces	\$164.80	\$316.67	53.333	8' 8"	6' 8"	1		Odd		Rect
C	Returns 1-2" E.5	58 Pieces	\$57.68	\$110.83	18.667	8' 8"	1' 2"	2		Odd		Gable
B	Alcove B127a N Band Rm	2,950 Pieces	\$2,950.13	\$5,668.81	954.735	19' 8"	58' 4"	1	Opn	Odd		Rect
B	Alt#2 (part out)33-8 N Band Rm	3,035 Pieces	\$3,034.51	\$5,830.94	982.041	33' 8"	54' 3"	1	Opn	Odd		Rect
B	E6 between 12.3 & 17 South Wal	198 Pieces	\$197.76	\$380.00	64.000	26' 0"	94' 0"	1	Opn	Odd		Rect
B	Alcove B127a N Band Rm @26-0	1,022 Pieces	\$1,021.76	\$1,963.36	330.667	10' 8"	41' 4"	1		Odd		Rect
B	Alt2(out)Cor Ent ReturnsCol #3	157 Pieces	\$156.56	\$300.84	50.667	8' 8"	6' 4"	1		Odd		Rect
B	Alt2 (out) Returns 1-2" Col #3	58 Pieces	\$57.68	\$110.83	18.667	8' 8"	1' 2"	2		Odd		Gable
A	Returns 1-2"	5 Pieces	\$4.81	\$9.24	1.556	8' 8"	1' 2"	2		Odd		Gable
B	Alt#2 (part out)22-8 N Band Rm	5,025 Pieces	\$5,025.19	\$9,656.13	1,626.275	22' 8"	82' 4"	1	Opn	Odd		Rect
A	Corr Ent Returns	14 Pieces	\$13.73	\$26.39	4.444	8' 8"	6' 8"	1		Odd		Rect
A	18" Ext @ Cafetorium	3,264 Pieces	\$3,263.71	\$6,271.36	1,056.216	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
B	H7 between 6 & 6.8 N Ext Wall	95 Pieces	\$94.76	\$182.09	30.667	16' 0"	50' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 with Insul	39 Pieces	\$39.48	\$75.87	12.778	28' 8"	9' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 NO Insul	113 Pieces	\$113.30	\$217.71	36.667	28' 8"	26' 0"	1	Opn	Odd		Rect
B	Piers @ Ent B123 Arch	31 Pieces	\$30.90	\$59.38	10.000	9' 8"	6' 4"	2		Odd		Pier
B	H10 between 6.9 & 9	56 Pieces	\$55.91	\$107.42	18.092	19' 0"	18' 4"	1	Opn	Odd		Rect
B	Face of Pier veneer	24 Pieces	\$24.35	\$46.79	7.880	9' 8"	9' 4"	1		Odd		Rect
B	E6 between 12????????	136 Pieces	\$136.14	\$261.60	44.059	28' 8"	39' 0"	1	Opn	Odd		Rect

BRI Continued

Wall

						Height	Length	Qty	Opn	Odd	Adj	Shape
Quantity	Extended Mat. Cost	Lay-Cost	Amount									
B 2x1-2 Pier @ 6.8 & 8	16 Pieces	\$16.48	\$31.67	5.333	9' 8"	4' 0"	2	Odd				Pier
B 2x1-2 Pier @ 6.8 & 8	31 Pieces	\$30.90	\$59.38	10.000	9' 8"	6' 4"	2	Odd				Pier
Material [U325B] Totals	25,968 Pieces	\$25,968.08	\$49,898.85	8,403.909	Mat. Lay Rate	390.0	Pieces/Day					
U325BCLOS Closer Brick b Color	Lay 400.0 Pieces/Day	\$0.850/ Piece		SqFt	3.00% waste	4.500	Pieces per SqFt					
CA#1 Alt#1 42-8 N & S Full Brick	70 Pieces	\$59.10	\$130.26	15.000	42' 8"	36' 0"	1	Opn	Odd	Adj		Rect
U325BS Utility Brick B Color Slo	Lay 200.0 Pieces/Day	\$1.000/ Piece		SqFt	3.00% waste	3.000	Pieces per SqFt					
B 8 CMU Top Radius@ Band	342 Pieces	\$342.45	\$1,283.18	110.827	6' 0"	41' 4"	1	Opn				Rect
B West Wall Vest B123 with Insul	63 Pieces	\$63.17	\$236.71	20.444	28' 8"	9' 8"	1	Opn	Odd			Rect
Material [U325BS] Totals	406 Pieces	\$405.63	\$1,519.89	131.271	Mat. Lay Rate	200.0	Pieces/Day					
U325SA Utility Soldier a Color	Lay 210.0 Pieces/Day	\$1.000/ Piece		SqFt	3.00% waste	3.000	Pieces per SqFt					
CA#1 Alt#1 42-8 N & S Full Brick	151 Pieces	\$151.15	\$539.40	48.917	42' 8"	36' 0"	1	Opn	Odd	Adj		Rect
C 42-8 N & S Full Brick	152 Pieces	\$152.18	\$543.08	49.250	42' 8"	36' 0"	1	Opn	Odd			Rect
C Col 23 F.5 to N 3 story Classr	41 Pieces	\$41.20	\$147.03	13.333	40' 0"	290' 2"	1	Opn	Odd			Rect
B Alt#2 (part out)33-8 N Band Rm	28 Pieces	\$27.81	\$99.24	9.000	33' 8"	54' 3"	1	Opn	Odd			Rect
B Alt#2 (part out)22-8 N Band Rm	10 Pieces	\$10.30	\$36.76	3.333	22' 8"	82' 4"	1	Opn	Odd			Rect
A 18" Ext @ Cafetorium	82 Pieces	\$82.40	\$294.05	26.667	22' 8"	114' 0"	1	Opn	Odd	Adj		Rect
Material [U325SA] Totals	465 Pieces	\$465.05	\$1,659.55	150.500	Mat. Lay Rate	210.0	Pieces/Day					
U325SB Utility Soldier B Color	Lay 250.0 Pieces/Day	\$1.000/ Piece		SqFt	3.00% waste	3.000	Pieces per SqFt					
A Ext Col A	28 Pieces	\$27.81	\$83.36	9.000	16' 8"	279' 3"	1	Opn	Odd			Rect
C Col 23 F.5 to N 3 story Classr	278 Pieces	\$278.10	\$833.64	90.000	40' 0"	290' 2"	1	Opn	Odd			Rect
B Alcove B127a N Band Rm	56 Pieces	\$55.88	\$167.50	18.083	19' 8"	58' 4"	1	Opn	Odd			Rect
B E6 between 12.3 & 17 South Wal	93 Pieces	\$92.70	\$277.88	30.000	26' 0"	94' 0"	1	Opn	Odd			Rect
B H7 between 6 & 6.8 N Ext Wall	62 Pieces	\$61.80	\$185.25	20.000	16' 0"	50' 8"	1	Opn	Odd			Rect
B West Wall Vest B123 with Insul	23 Pieces	\$23.18	\$69.47	7.500	28' 8"	9' 8"	1	Opn	Odd			Rect
B West Wall Vest B123 NO Insul	58 Pieces	\$57.68	\$172.91	18.667	28' 8"	26' 0"	1	Opn	Odd			Rect
B East Wall Vest B123 NO Insul	59 Pieces	\$58.71	\$175.99	19.000	13' 4"	26' 8"	1	Opn	Odd			Rect
B N Wall Top of Main ent.	136 Pieces	\$135.96	\$407.56	44.000	22' 8"	69' 8"	1	Opn	Odd			Rect
B N Wall Top of Main ent.	184 Pieces	\$184.37	\$552.67	59.667	18' 8"	55' 4"	1	Opn	Odd			Rect
B N Wall Office B13 & 140	41 Pieces	\$41.20	\$123.50	13.333	13' 4"	24' 0"	1	Opn	Odd			Rect
B N Wall Confere B138 with Insul	93 Pieces	\$92.70	\$277.88	30.000	13' 4"	49' 8"	1	Opn	Odd			Rect
B H10 between 6.9 & 9	21 Pieces	\$20.60	\$61.75	6.667	19' 0"	18' 4"	1	Opn	Odd			Rect
B East Wall Vest B123 with Insul	10 Pieces	\$10.30	\$30.88	3.333	13' 4"	12' 8"	1	Opn	Odd			Rect
B E6 between 12???????????	124 Pieces	\$123.60	\$370.50	40.000	28' 8"	39' 0"	1	Opn	Odd			Rect
Material [U325SB] Totals	1,265 Pieces	\$1,264.58	\$3,790.73	409.250	Mat. Lay Rate	250.0	Pieces/Day					
Class Totals BRICKS	77,865 Pieces	\$78,075.70	\$159,308.82	24,961.560	Avg. Lay Rate	366.3	Pieces/Day					

Classification **CMU**

C.M.U.

MW04 100 4" Pier CMU	Lay 100.0 Pieces/Day	\$0.600/ Piece		SqFt	5.00% waste	1.125	Pieces per SqFt					
A West wall Gym	265 Pieces	\$159.08	\$1,949.01	224.444	33' 8"	89' 8"	1	Opn	Odd			Rect
CA#1 2Copy Stair C133 SGT	5 Pieces	\$3.07	\$37.66	4.337	13' 4"	13' 4"	1		Odd	Adj		Rect
CA#1 3rdStair C133 SGT	5 Pieces	\$3.07	\$37.66	4.337	13' 4"	13' 4"	1		Odd	Adj		Rect
C3 2Copy Stair C100 SGT	18 Pieces	\$10.87	\$133.15	15.333	13' 4"	23' 0"	1		Odd			Rect
C2 2Copy Stair C100 SGT	18 Pieces	\$10.87	\$133.15	15.333	13' 4"	23' 0"	1		Odd			Rect
CA#1 Alt#1 C133 Stair	26 Pieces	\$15.75	\$192.97	22.222	13' 4"	41' 4"	1	Opn	Odd			Rect
C1 Stair C100 SGT	27 Pieces	\$16.22	\$198.76	22.889	13' 4"	41' 8"	1	Opn	Odd			Rect

Wall

CMU Continued

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
C1	3 8"CMU Corr SGT13-0 FireS	173 Pieces	\$104.02	\$1,274.49	146.768	13' 0"	264' 8"	1	Opn	Odd		Rect
C3	3 8"CMU Corr SGT13-0 FireS	173 Pieces	\$104.02	\$1,274.49	146.768	13' 0"	264' 8"	1	Opn	Odd		Rect
C2	3 8"CMU Corr SGT13-0 FireS	173 Pieces	\$104.02	\$1,274.49	146.768	13' 0"	264' 8"	1	Opn	Odd		Rect
C2	3 8"CMU Corr SGT13-0 FireS	173 Pieces	\$104.02	\$1,274.49	146.768	13' 0"	264' 8"	1	Opn	Odd		Rect
B	8" CMU Corr with SGT base	307 Pieces	\$184.26	\$2,257.57	259.978	13' 4"	497' 4"	1	Opn	Odd		Rect
B2	8" CMU Corr with SGT base2nd F	149 Pieces	\$89.56	\$1,097.27	126.360	12' 0"	242' 0"	1	Opn	Odd		Rect
B2	8" CMU CorSGTnoBB 2nd F	31 Pieces	\$18.59	\$227.71	26.222	12' 0"	39' 4"	1	Opn	Odd		Rect
B2	8" CMU CorSGTnoBB 12-8	98 Pieces	\$59.02	\$723.16	83.278	12' 8"	154' 4"	1	Opn	Odd		Rect
B2	8" CMU CorSGTnoBB12-8"	8 Pieces	\$4.73	\$57.89	6.667	12' 8"	10' 0"	1		Odd		Rect
B	8"CMU Corr SGT13-0 FireS	47 Pieces	\$28.15	\$344.84	39.711	13' 0"	83' 7"	1	Opn	Odd		Rect
B	8" CMU Corr SGT base DisplayCa	46 Pieces	\$27.88	\$341.56	39.333	13' 4"	59' 0"	1	Opn	Odd		Rect
B	8" CMUf @ roof Col 10.1&10.9	503 Pieces	\$301.93	\$3,699.26	426.000	7' 4"	161' 4"	1		Odd		Rect
B	H10 between 6.9 & 9	29 Pieces	\$17.64	\$216.16	24.892	19' 0"	18' 4"	1	Opn	Odd		Rect
Material [MW04 100] Totals		2,278 Pieces	\$1,366.76	\$16,745.72	1,928.407	Mat. Lay Rate	100.0 Pieces/Day					
MW04 140	4" Mediumweight CMU	Lay 140.0 Pieces/Day	\$0.600/ Piece		SqFt	5.00% waste	1.125	Pieces per SqFt				
C3	6 4"CMU 13-0 Reg Wall	833 Pieces	\$499.75	\$4,373.56	705.111	13' 0"	55' 8"	1		Odd		Rect
C2	6 4"CMU 13-0 Reg Wall	833 Pieces	\$499.75	\$4,373.56	705.111	13' 0"	55' 8"	1		Odd		Rect
C1	6 4"CMU 13-0 Reg Wall	833 Pieces	\$499.75	\$4,373.56	705.111	13' 0"	55' 8"	1		Odd		Rect
B2	4"CMU 12-8 FireSafe 2nd Floor	1,047 Pieces	\$628.43	\$5,499.68	886.667	12' 8"	70' 0"	1				Rect
B	Alcove B127a N Band Rm @26-0	130 Pieces	\$78.12	\$683.67	110.222	10' 8"	41' 4"	1		Odd		Rect
B	4"CMU 13-0 FireSafe Reg Wall	2,090 Pieces	\$1,253.86	\$10,973.17	1,769.111	13' 0"	139' 8"	1		Odd		Rect
Material [MW04 140] Totals		5,766 Pieces	\$3,459.65	\$30,277.19	4,881.333	Mat. Lay Rate	140.0 Pieces/Day					
MW04 150	4" Mediumweight CMU	Lay 150.0 Pieces/Day	\$0.600/ Piece		SqFt	5.00% waste	1.125	Pieces per SqFt				
A	(8 CMU) Corr A106 SGT	12 Pieces	\$6.93	\$56.60	9.778	21' 4"	22' 4"	1	Opn	Odd	Adj	Rect
B	West Wall Vest B123 with Insul	23 Pieces	\$13.70	\$111.92	19.333	28' 8"	9' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 NO Insul	61 Pieces	\$36.86	\$301.04	52.000	28' 8"	26' 0"	1	Opn	Odd		Rect
B	East Wall Vest B123 with Insul	10 Pieces	\$5.82	\$47.51	8.206	13' 4"	12' 8"	1	Opn	Odd		Rect
A	(8 CMU) Corr A104 SGT	13 Pieces	\$7.78	\$63.53	10.974	15' 4"	29' 4"	1	Opn	Odd		Rect
A	4" CMU Front of Stage A110	147 Pieces	\$88.36	\$721.77	124.677	2' 11"	47' 4"	1		Odd		Rect
A	4" CMU Pipe Chase A103	90 Pieces	\$54.21	\$442.78	76.485	15' 4"	5' 4"	1				Rect
A#3C	Alt3 out (4 CMU) Serving #119	151 Pieces	\$90.56	\$739.72	127.778	15' 4"	8' 4"	1				Rect
A#3C	Alt3 out (8 CMU) Corr A104 SGT	13 Pieces	\$7.56	\$61.75	10.667	15' 4"	35' 0"	1	Opn	Odd		Rect
Material [MW04 150] Totals		520 Pieces	\$311.78	\$2,546.63	439.898	Mat. Lay Rate	150.0 Pieces/Day					
MW043"RIP	4" x 3 x 16 CMU	Lay 100.0 Pieces/Day	\$0.300/ Piece		SqFt	5.00% waste	3.375	Pieces per SqFt				
A	4" CMU Front of Stage A110	41 Pieces	\$12.43	\$304.50	11.688	2' 11"	47' 4"	1		Odd		Rect
MW04BH	4" Med CMU-Bull Half	Lay 175.0 Pieces/Day	\$0.460/ Piece		SqFt	5.00% waste	2.250	Pieces per SqFt				
CA#1	Alt#1 42-8 N & S Full Brick	47 Pieces	\$21.74	\$198.48	20.000	42' 8"	36' 0"	1	Opn	Odd	Adj	Rect
C	42-8 N & S Full Brick	47 Pieces	\$21.74	\$198.48	20.000	42' 8"	36' 0"	1	Opn	Odd		Rect
C	Col 23 F.5 to N 3 story Classr	488 Pieces	\$224.60	\$2,051.01	206.667	40' 0"	290' 2"	1	Opn	Odd		Rect
B	8" CMU Corr with SGT base	20 Pieces	\$9.42	\$86.01	8.667	13' 4"	497' 4"	1	Opn	Odd		Rect
B	E6 between 12.3 & 17 South Wal	89 Pieces	\$41.06	\$374.92	37.778	26' 0"	94' 0"	1	Opn	Odd		Rect
B	Alt#2 (part out)22-8 N Band Rm	5 Pieces	\$2.42	\$22.05	2.222	22' 8"	82' 4"	1	Opn	Odd		Rect
A	18" Ext @ Cafetorium	42 Pieces	\$19.32	\$176.43	17.778	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
B	H7 between 6 & 6.8 N Ext Wall	32 Pieces	\$14.49	\$132.32	13.333	16' 0"	50' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 with Insul	5 Pieces	\$2.42	\$22.05	2.222	28' 8"	9' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 NO Insul	11 Pieces	\$4.83	\$44.11	4.444	28' 8"	26' 0"	1	Opn	Odd		Rect
B	East Wall Vest B123 NO Insul	24 Pieces	\$11.11	\$101.45	10.222	13' 4"	26' 8"	1	Opn	Odd		Rect

Sample Reports
Quantity/Bid Price Report

CMU Continued

Wall

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
B	N Wall Top of Main ent.	57 Pieces	\$26.08	\$238.18	24.000	22' 8"	69' 8"	1	Opn	Odd		Rect
B	N Wall Top of Main ent.	61 Pieces	\$28.01	\$255.82	25.778	18' 8"	55' 4"	1	Opn	Odd		Rect
B	N Wall Office B13 & 140	21 Pieces	\$9.66	\$88.22	8.889	13' 4"	24' 0"	1	Opn	Odd		Rect
B	N Wall Confere B138 with Insul	47 Pieces	\$21.74	\$198.48	20.000	13' 4"	49' 8"	1	Opn	Odd		Rect
B	H10 between 6.9 & 9	11 Pieces	\$4.83	\$44.11	4.444	19' 0"	18' 4"	1	Opn	Odd		Rect
B	East Wall Vest B123 with Insul	5 Pieces	\$2.42	\$22.05	2.222	13' 4"	12' 8"	1	Opn	Odd		Rect
B	E6 between 12???????????	63 Pieces	\$28.98	\$264.65	26.667	28' 8"	39' 0"	1	Opn	Odd		Rect
Material [MW04BH] Totals		1,076 Pieces	\$494.83	\$4,518.84	455.333	Mat. Lay Rate	175.0 Pieces/Day					

MW04HH		4" Mediumweight CMU-H.H.	Lay	175.0 Pieces/Day	\$0.350/ Piece	SqFt	3.00% waste	2.250	Pieces per SqFt			
C3	6 4"CMU 13-0 Reg Wall	43 Pieces	\$15.05	\$184.15	18.556	13' 0"	55' 8"	1	Odd			Rect
C2	6 4"CMU 13-0 Reg Wall	43 Pieces	\$15.05	\$184.15	18.556	13' 0"	55' 8"	1	Odd			Rect
C1	6 4"CMU 13-0 Reg Wall	43 Pieces	\$15.05	\$184.15	18.556	13' 0"	55' 8"	1	Odd			Rect
B	4"CMU 13-0 FireSafe Reg Wall	108 Pieces	\$37.76	\$462.03	46.556	13' 0"	139' 8"	1	Odd			Rect
Material [MW04HH] Totals		237 Pieces	\$82.92	\$1,014.48	102.222	Mat. Lay Rate	175.0 Pieces/Day					

MW06		6" Mediumweight CMU	Lay	140.0 Pieces/Day	\$0.850/ Piece	SqFt	5.00% waste	1.125	Pieces per SqFt			
A	Ext Col A	648 Pieces	\$550.76	\$3,402.34	548.530	16' 8"	279' 3"	1	Opn	Odd		Rect
B	North wall of Cafetorium SGT	414 Pieces	\$352.09	\$2,175.06	350.667	26' 0"	22' 0"	1	Opn	Odd		Rect
CA#1	Alt#1 42-8 N & S Full Brick	62 Pieces	\$52.66	\$325.29	52.444	42' 8"	36' 0"	1	Opn	Odd	Adj	Rect
B	Arch on Piers @ Ent for Mark?	34 Pieces	\$29.17	\$180.22	29.056	4' 4"	20' 0"	1	Opn	Odd		Rect
C	42-8 N & S Full Brick	62 Pieces	\$52.66	\$325.29	52.444	42' 8"	36' 0"	1	Opn	Odd		Rect
C	Col 23 F.5 to N 3 story Classr	405 Pieces	\$344.51	\$2,128.20	343.111	40' 0"	290' 2"	1	Opn	Odd		Rect
B	8" CMU Corr with SGT base	25 Pieces	\$20.97	\$129.57	20.889	13' 4"	497' 4"	1	Opn	Odd		Rect
B	Alcove B127a N Band Rm	43 Pieces	\$36.70	\$226.74	36.556	19' 8"	58' 4"	1	Opn	Odd		Rect
B	E6 between 12.3 & 17 South Wal	117 Pieces	\$99.07	\$611.99	98.667	26' 0"	94' 0"	1	Opn	Odd		Rect
B	Alt#2 (part out)22-8 N Band Rm	7 Pieces	\$6.25	\$38.59	6.222	22' 8"	82' 4"	1	Opn	Odd		Rect
A	18" Ext @ Cafetorium	59 Pieces	\$49.98	\$308.75	49.778	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
B	H7 between 6 & 6.8 N Ext Wall	40 Pieces	\$33.92	\$209.51	33.778	16' 0"	50' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 with Insul	15 Pieces	\$12.72	\$78.57	12.667	28' 8"	9' 8"	1	Opn	Odd		Rect
B	North wall of Cafetorium	1,941 Pieces	\$1,650.23	\$10,194.40	1,643.556	26' 0"	79' 4"	1	Opn	Odd	Adj	Rect
B	West Wall Vest B123 NO Insul	35 Pieces	\$29.90	\$184.70	29.778	28' 8"	26' 0"	1	Opn	Odd		Rect
B	East Wall Vest B123 NO Insul	57 Pieces	\$48.64	\$300.48	48.444	13' 4"	26' 8"	1	Opn	Odd		Rect
B	Top of Piers @ Ent	239 Pieces	\$202.95	\$1,253.73	202.128	4' 4"	55' 2"	1	Opn	Odd		Rect
B	Piers @ Ent B123 Arch	30 Pieces	\$25.88	\$159.89	25.778	9' 8"	6' 4"	2	Odd			Pier
B	N Wall Top of Main ent.	74 Pieces	\$62.48	\$385.94	62.222	22' 8"	69' 8"	1	Opn	Odd		Rect
B	N Wall Top of Main ent.	71 Pieces	\$60.69	\$374.92	60.444	18' 8"	55' 4"	1	Opn	Odd		Rect
B	N Wall Office B13 & 140	25 Pieces	\$21.42	\$132.32	21.333	13' 4"	24' 0"	1	Opn	Odd		Rect
B	N Wall Confere B138 with Insul	54 Pieces	\$45.52	\$281.19	45.333	13' 4"	49' 8"	1	Opn	Odd		Rect
B	N Main Ent Splitface Piers	129 Pieces	\$109.41	\$675.88	108.967	10' 0"	25' 9"	1				Rect
B	N Main Ent Brick Piers	254 Pieces	\$216.28	\$1,336.11	215.409	10' 0"	49' 9"	1				Rect
B	H10 between 6.9 & 9	13 Pieces	\$10.71	\$66.16	10.667	19' 0"	18' 4"	1	Opn	Odd		Rect
B	Face of Pier veneer	48 Pieces	\$41.22	\$254.65	41.055	9' 8"	9' 4"	1	Odd			Rect
B	East Wall Vest B123 with Insul	7 Pieces	\$6.25	\$38.59	6.222	13' 4"	12' 8"	1	Opn	Odd		Rect
B	E6 between 12???????????	76 Pieces	\$64.26	\$396.97	64.000	28' 8"	39' 0"	1	Opn	Odd		Rect
B	2x1-2 Pier @ 6.8 & 8	4 Pieces	\$3.24	\$19.99	3.222	9' 8"	4' 0"	2	Odd			Pier
B	2x1-2 Pier @ 6.8 & 8	30 Pieces	\$25.88	\$159.89	25.778	9' 8"	6' 4"	2	Odd			Pier
Material [MW06] Totals		5,019 Pieces	\$4,266.41	\$26,355.94	4,249.145	Mat. Lay Rate	140.0 Pieces/Day					

MW081"RIP		8" 1" Rip	Lay	160.0 Pieces/Day	\$0.250/ Piece	SqFt	3.00% waste	9.000	Pieces per SqFt			
C2	1 8" CMU Corr Bearing no SGT	453 Pieces	\$113.21	\$2,121.06	48.852	13' 4"	587' 8"	1	Opn	Odd		Rect

Sample Reports
Quantity/Bid Price Report

CMU Continued

Wall

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
C3	1 8" CMU Corr Bearing no SGT	453 Pieces	\$113.21	\$2,121.06	48.852	13' 4"	587' 8"	1	Opn	Odd		Rect
C1	1 8" CMU Corr Bearing no SGT	453 Pieces	\$113.21	\$2,121.06	48.852	13' 4"	587' 8"	1	Opn	Odd		Rect
B	8" CMU Corr with SGT base	385 Pieces	\$96.30	\$1,804.20	41.554	13' 4"	497' 4"	1	Opn	Odd		Rect
B	8" CMU Corr Bearing no SGT	43 Pieces	\$10.75	\$201.48	4.640	13' 4"	55' 8"	1		Odd		Rect
Material [MW081"RIP] Totals		1,787 Pieces	\$446.70	\$8,368.87	192.749	Mat. Lay Rate	160.0 Pieces/Day					
MW08135	8" Mediumweight 135	Lay 145.0 Pieces/Day	\$0.950/ Piece		SqFt	5.00% waste	1.125	Pieces per SqFt				
A	Ext Col A	4,346 Pieces	\$4,128.42	\$22,032.06	3,678.900	16' 8"	279' 3"	1	Opn	Odd		Rect
A	(8 CMU) Corr A106 SGT	390 Pieces	\$370.82	\$1,978.96	330.445	21' 4"	22' 4"	1	Opn	Odd	Adj	Rect
B	North wall of Cafetorium SGT	397 Pieces	\$377.06	\$2,012.22	336.000	26' 0"	22' 0"	1	Opn	Odd		Rect
CA#1	Copy Reg CMU Stair #133	179 Pieces	\$169.58	\$904.97	151.111	13' 4"	11' 4"	1				Rect
CA#1	2Copy Stair C133 SGT	131 Pieces	\$124.82	\$666.11	111.227	13' 4"	13' 4"	1		Odd	Adj	Rect
CA#1	3rdStair C133 SGT	131 Pieces	\$124.82	\$666.11	111.227	13' 4"	13' 4"	1		Odd	Adj	Rect
C3	3 Copy 5 8" CMU Corr 2side SGT	70 Pieces	\$66.33	\$354.01	59.112	13' 4"	8' 0"	1	Opn	Odd		Rect
B	8 CMU Top Radius@ Band	131 Pieces	\$124.37	\$663.71	110.827	6' 0"	41' 4"	1	Opn			Rect
CA#1	3rd FI 8" CMU Corr 2side SGT	70 Pieces	\$66.33	\$354.01	59.112	13' 4"	8' 0"	1	Opn	Odd		Rect
CA#1	Copy 5 8" CMU Corr 2side SGT	70 Pieces	\$66.33	\$354.01	59.112	13' 4"	8' 0"	1	Opn	Odd		Rect
CA#1	2 Copy Reg CMU Stair #133	273 Pieces	\$259.35	\$1,384.07	231.111	13' 4"	17' 4"	1				Rect
CA#1	2 Copy Reg CMU Stair #133	273 Pieces	\$259.35	\$1,384.07	231.111	13' 4"	17' 4"	1				Rect
C2	Reg CMU Stair #100	179 Pieces	\$169.58	\$904.97	151.111	13' 4"	11' 4"	1				Rect
C3	2Copy Stair C100 SGT	344 Pieces	\$326.93	\$1,744.73	291.333	13' 4"	23' 0"	1		Odd		Rect
C3	2 Copy Reg CMU Stair #133	273 Pieces	\$259.35	\$1,384.07	231.111	13' 4"	17' 4"	1				Rect
C2	3 Copy 5 8" CMU Corr 2side SGT	70 Pieces	\$66.33	\$354.01	59.112	13' 4"	8' 0"	1	Opn	Odd		Rect
C2	2 Copy Reg CMU Stair #133	273 Pieces	\$259.35	\$1,384.07	231.111	13' 4"	17' 4"	1				Rect
CA#1	Alt#1 Reg CMU Stair #133	525 Pieces	\$498.75	\$2,661.67	444.444	13' 4"	34' 0"	1				Rect
C2	2Copy Stair C100 SGT	344 Pieces	\$326.93	\$1,744.73	291.333	13' 4"	23' 0"	1		Odd		Rect
CA#1	Alt#1 North Brick&CMU	2,233 Pieces	\$2,121.31	\$11,320.76	1,890.333	40' 0"	57' 0"	1	Opn	Odd		Rect
C	Col 23 F.5 to N 3 story Classr	9,316 Pieces	\$8,850.38	\$47,231.71	7,886.722	40' 0"	290' 2"	1	Opn	Odd		Rect
CA#1	Alt#1 C133 Stair	559 Pieces	\$530.67	\$2,832.02	472.889	13' 4"	41' 4"	1	Opn	Odd		Rect
CA#1	Alt#1 Cor Ent ReturnsCol E.5	68 Pieces	\$64.84	\$346.02	57.778	8' 8"	6' 8"	1		Odd		Rect
C	Cor Ent ReturnsCol E.5	68 Pieces	\$64.84	\$346.02	57.778	8' 8"	6' 8"	1		Odd		Rect
C1	Stair C100 8" CMU Reg Wall	536 Pieces	\$508.73	\$2,714.91	453.333	13' 4"	34' 8"	1				Rect
C1	4 8"CMU 13-0 Reg Wall	1,507 Pieces	\$1,431.86	\$7,641.37	1,275.952	13' 0"	103' 4"	1	Opn	Odd		Rect
C1	Stair C100 SGT	564 Pieces	\$535.41	\$2,857.31	477.112	13' 4"	41' 8"	1	Opn	Odd		Rect
C2	1 8" CMU Corr Bearing no SGT	7,757 Pieces	\$7,369.55	\$39,328.97	6,567.127	13' 4"	587' 8"	1	Opn	Odd		Rect
C1	3 8"CMU Corr SGT13-0 FireS	3,515 Pieces	\$3,338.99	\$17,819.17	2,975.434	13' 0"	264' 8"	1	Opn	Odd		Rect
C3	5 8" CMU Corr 2side SGT	121 Pieces	\$115.21	\$614.85	102.667	13' 0"	13' 0"	1	Opn	Odd		Rect
C3	4 8"CMU 13-0 Reg Wall	1,507 Pieces	\$1,431.86	\$7,641.37	1,275.952	13' 0"	103' 4"	1	Opn	Odd		Rect
C3	3 8"CMU Corr SGT13-0 FireS	3,515 Pieces	\$3,338.99	\$17,819.17	2,975.434	13' 0"	264' 8"	1	Opn	Odd		Rect
C2	3 8"CMU Corr SGT13-0 FireS	3,515 Pieces	\$3,338.99	\$17,819.17	2,975.434	13' 0"	264' 8"	1	Opn	Odd		Rect
C3	1 8" CMU Corr Bearing no SGT	7,757 Pieces	\$7,369.55	\$39,328.97	6,567.127	13' 4"	587' 8"	1	Opn	Odd		Rect
C2	5 8" CMU Corr 2side SGT	121 Pieces	\$115.21	\$614.85	102.667	13' 0"	13' 0"	1	Opn	Odd		Rect
C2	4 8"CMU 13-0 Reg Wall	1,507 Pieces	\$1,431.86	\$7,641.37	1,275.952	13' 0"	103' 4"	1	Opn	Odd		Rect
C2	3 8"CMU Corr SGT13-0 FireS	3,515 Pieces	\$3,338.99	\$17,819.17	2,975.434	13' 0"	264' 8"	1	Opn	Odd		Rect
C1	5 8" CMU Corr 2side SGT	121 Pieces	\$115.21	\$614.85	102.667	13' 0"	13' 0"	1	Opn	Odd		Rect
C1	1 8" CMU Corr Bearing no SGT	7,757 Pieces	\$7,369.55	\$39,328.97	6,567.127	13' 4"	587' 8"	1	Opn	Odd		Rect
B	8" CMU Corr with SGT base	5,842 Pieces	\$5,550.06	\$29,618.92	4,945.750	13' 4"	497' 4"	1	Opn	Odd		Rect
B2	8" CMU Corr with SGT base2nd F	2,685 Pieces	\$2,550.76	\$13,612.59	2,273.021	12' 0"	242' 0"	1	Opn	Odd		Rect
B	8" CMU Corr Bearing no SGT	789 Pieces	\$749.86	\$4,001.75	668.210	13' 4"	55' 8"	1		Odd		Rect
B	Alcove B127a N Band Rm	16 Pieces	\$15.46	\$82.51	13.778	19' 8"	58' 4"	1	Opn	Odd		Rect
B2	8" CMU Corr with BB No SGT 2 f	531 Pieces	\$504.49	\$2,692.28	449.556	12' 0"	39' 8"	1		Odd		Rect
B2	8" CMU CorSGTnoBB 2nd F	199 Pieces	\$189.03	\$1,008.77	168.444	12' 0"	39' 4"	1	Opn	Odd		Rect

CMU Continued

Wall

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
B	E6 between 12.3 & 17 South Wal	1,936	Pieces \$1,839.39	\$9,816.25	1,639.111	26' 0"	94' 0"	1	Opn	Odd		Rect
B2	8" CMU 2nd Fl no base	4,376	Pieces \$4,157.21	\$22,185.73	3,704.560	12' 8"	303' 4"	1	Opn			Rect
B2	8" CMU CorSGTnoBB 12-8	2,010	Pieces \$1,909.59	\$10,190.88	1,701.667	12' 8"	154' 4"	1	Opn	Odd		Rect
B2	8" CMU @ Learn Cent @ Door	152	Pieces \$144.44	\$770.85	128.717	7' 4"	17' 0"	1				Rect
B2	8" CMU CorSGTnoBB12-8"	142	Pieces \$134.66	\$718.65	120.000	12' 8"	10' 0"	1		Odd		Rect
B	8" CMU Band rm B127	156	Pieces \$148.13	\$790.52	132.000	8' 0"	18' 0"	1		Odd		Rect
B	Alt2(out)Cor Ent ReturnsCol #3	65	Pieces \$61.60	\$328.72	54.889	8' 8"	6' 4"	1		Odd		Rect
A	Corr Ent Returns	68	Pieces \$64.84	\$346.02	57.778	8' 8"	6' 8"	1		Odd		Rect
B	H7 between 6 & 6.8 N Ext Wall	720	Pieces \$684.29	\$3,651.81	609.778	16' 0"	50' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 with Insul	260	Pieces \$246.88	\$1,317.53	220.000	28' 8"	9' 8"	1	Opn	Odd		Rect
B	8"CMU 13-0 FireSafe Reg Wall	9,945	Pieces \$9,447.46	\$50,418.11	8,418.785	13' 0"	690' 7"	1	Opn	Odd		Rect
B	8"CMU Corr SGT13-0 FireS	1,019	Pieces \$968.20	\$5,166.96	862.775	13' 0"	83' 7"	1	Opn	Odd		Rect
B	8" CMU Corr SGT base DisplayCa	316	Pieces \$300.00	\$1,601.00	267.333	13' 4"	59' 0"	1	Opn	Odd		Rect
B	8" CMU Corr 2side SGT	236	Pieces \$224.44	\$1,197.75	200.000	13' 0"	33' 4"	1	Opn	Odd		Rect
B	North wall of Cafetorium	1,716	Pieces \$1,630.16	\$8,699.68	1,452.667	26' 0"	79' 4"	1	Opn	Odd	Adj	
B	West Wall Vest B123 NO Insul	325	Pieces \$308.73	\$1,647.58	275.111	28' 8"	26' 0"	1	Opn	Odd		Rect
B	8" CMUf @ roof Col 10.1&10.9	1,007	Pieces \$956.60	\$5,105.09	852.444	7' 4"	161' 4"	1		Odd		Rect
B	8" CMU Fill in @ roof	8	Pieces \$7.48	\$39.93	6.667	4' 8"	1' 8"	1		Odd		Rect
B	N Wall Top of Main ent.	1,070	Pieces \$1,016.34	\$5,423.88	905.676	22' 8"	69' 8"	1	Opn	Odd		Rect
B	N Wall Top of Main ent.	499	Pieces \$474.11	\$2,530.16	422.484	18' 8"	55' 4"	1	Opn	Odd		Rect
B	N Wall Office B13 & 140	239	Pieces \$227.43	\$1,213.72	202.667	13' 4"	24' 0"	1	Opn	Odd		Rect
B	N Wall Confere B138 with Insul	433	Pieces \$411.28	\$2,194.88	366.500	13' 4"	49' 8"	1	Opn	Odd		Rect
B	H10 between 6.9 & 9	196	Pieces \$186.67	\$996.21	166.346	19' 0"	19' 4"	1	Opn	Odd		Rect
B	East Wall Vest B123 with Insul	130	Pieces \$123.95	\$661.47	110.451	13' 4"	12' 8"	1	Opn	Odd		Rect
B	E6 between 12???????????	748	Pieces \$710.68	\$3,792.70	633.302	28' 8"	39' 0"	1	Opn	Odd		Rect
B	E&W Walls Office B136 & 140	256	Pieces \$243.00	\$1,296.82	216.542	10' 0"	25' 1"	1				Rect
A	(8 CMU) Corr A104 SGT	387	Pieces \$367.39	\$1,960.65	327.387	15' 4"	29' 4"	1	Opn	Odd		Rect
A	(8 CMU) Top Radius	200	Pieces \$189.76	\$1,012.69	169.099	5' 1"	50' 4"	1	Opn			Rect
A	8" CMU A 101, 102, 103, 117&8	1,646	Pieces \$1,563.83	\$8,345.67	1,393.556	15' 4"	96' 4"	1	Opn			Rect
A	8" CMU Projection Rm Walls	435	Pieces \$413.34	\$2,205.86	368.333	14' 2"	26' 0"	1				Rect
A	8" CMU Slope Hand Rail	224	Pieces \$213.22	\$1,137.86	190.000	4' 0"	57' 0"	1		Odd		Rect
A	8"CMU Slope Hand Rail on Stage	174	Pieces \$165.59	\$883.68	147.556	6' 0"	34' 8"	1		Odd		BotL
A#3C	Alt3 out (8 CMU) Corr A104 SGT	504	Pieces \$478.80	\$2,555.21	426.667	15' 4"	35' 0"	1	Opn	Odd		Rect
A#3C	Alt3 out (8 CMU) Serving #119	757	Pieces \$719.45	\$3,839.46	641.111	15' 4"	45' 0"	1	Opn			Rect
A	(12 CMU) So Gym A108 "no" SGT	13	Pieces \$12.47	\$66.54	11.111	33' 8"	99' 4"	1	Opn	Odd		Rect
A	(12 CMU) Gym A108 SGT	78	Pieces \$74.56	\$397.92	66.444	33' 8"	125' 0"	1	Opn	Odd		Rect
A	(12 CMU) Corr A106 SGT	78	Pieces \$74.28	\$396.40	66.191	21' 4"	104' 8"	1		Odd		Rect
Material [MW08135] Totals		106,618	Pieces \$101,286.66	\$540,535.15	90,258.231	Mat. Lay Rate	145.0	Pieces/Day				
MW08150 8" Fast No Striking		Lay	150.0	Pieces/Day	\$0.950/ Piece	SqFt	5.00% waste	1.125	Pieces per SqFt			
B	North wall of Cafetorium SGT	104	Pieces \$98.75	\$509.44	88.000	26' 0"	22' 0"	1	Opn	Odd		Rect
CA#1	Alt#1 42-8 N & S Full Brick	1,308	Pieces \$1,242.45	\$6,409.54	1,107.167	42' 8"	36' 0"	1	Opn	Odd	Adj	Rect
A	West wall Gym	134	Pieces \$127.46	\$657.55	113.584	33' 8"	89' 8"	1	Opn	Odd		Rect
C	42-8 N & S Full Brick	1,320	Pieces \$1,254.17	\$6,470.00	1,117.611	42' 8"	36' 0"	1	Opn	Odd		Rect
CA#1	Alt#1 North Brick&CMU	169	Pieces \$160.10	\$825.92	142.667	40' 0"	57' 0"	1	Opn	Odd		Rect
C	Col 23 F.5 to N 3 story Classr	776	Pieces \$736.90	\$3,801.53	656.667	40' 0"	290' 2"	1	Opn	Odd		Rect
C	Col 17 between E.5 & H.9	3,831	Pieces \$3,639.17	\$18,773.76	3,242.928	40' 0"	85' 7"	1	Opn	Odd		Rect
B	Alcove B127a N Band Rm	1,107	Pieces \$1,051.19	\$5,422.85	936.729	19' 8"	58' 4"	1	Opn	Odd		Rect
B	N Mech Rm 33-8	3,231	Pieces \$3,069.31	\$15,833.94	2,735.112	20' 4"	149' 8"	1	Opn	Odd		Rect
B	Alt#2 (part out)33-8 N Band Rm	1,953	Pieces \$1,855.12	\$9,570.17	1,653.125	33' 8"	54' 3"	1	Opn	Odd		Rect
B	E6 between 12.3 & 17 South Wal	269	Pieces \$255.36	\$1,317.35	227.556	26' 0"	94' 0"	1	Opn	Odd		Rect
B	Alcove B127a N Band Rm @26-0	521	Pieces \$494.76	\$2,552.37	440.889	10' 8"	41' 4"	1		Odd		Rect

Sample Reports
Quantity/Bid Price Report

Wall

CMU Continued

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
B	Alt#2 (part out)22-8 N Band Rm	125 Pieces	\$118.70	\$612.36	105.778	22' 8"	82' 4"	1	Opn	Odd		Rect
B	E Wall (12 CMU) Band B127	83 Pieces	\$78.55	\$405.24	70.000	22' 8"	35' 0"	1		Odd		Rect
A	N Wall (12 CMU) Serving #119	177 Pieces	\$168.33	\$868.37	150.000	22' 8"	45' 0"	1	Opn	Odd		Rect
A	18" Ext @ Cafetorium	354 Pieces	\$335.90	\$1,732.84	299.327	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
A	Alt2 12CMU Col 4.3 @ C&D (Out)	76 Pieces	\$71.82	\$370.50	64.000	33' 8"	48' 0"	1	Opn	Odd		Rect
B	West Wall Vest B123 with Insul	30 Pieces	\$28.93	\$149.23	25.778	28' 8"	9' 8"	1	Opn	Odd		Rect
A	(12 CMU) Projection RM Radi	277 Pieces	\$263.59	\$1,359.80	234.889	24' 10"	50' 4"	1	Opn	Odd	Adj	Rect
B	North wall of Cafetorium	375 Pieces	\$356.11	\$1,837.09	317.333	26' 0"	79' 4"	1	Opn	Odd	Adj	Rect
B	West Wall Vest B123 NO Insul	82 Pieces	\$77.81	\$401.38	69.333	28' 8"	26' 0"	1	Opn	Odd		Rect
B	N Wall Top of Main ent.	316 Pieces	\$299.92	\$1,547.24	267.266	22' 8"	69' 8"	1	Opn	Odd		Rect
B	N Wall Top of Main ent.	83 Pieces	\$78.74	\$406.22	70.169	18' 8"	55' 4"	1	Opn	Odd		Rect
B	H10 between 6.9 & 9	54 Pieces	\$50.91	\$262.63	45.366	19' 0"	18' 4"	1	Opn	Odd		Rect
B	E6 between 12????????	119 Pieces	\$112.75	\$581.68	100.477	28' 8"	39' 0"	1	Opn	Odd		Rect
B	Below barrel parapet	130 Pieces	\$123.69	\$638.09	110.222	10' 8"	41' 4"	1		Odd		Rect
A	(12 CMU) So Gym A108 "no" SGT	313 Pieces	\$297.26	\$1,533.48	264.889	33' 8"	99' 4"	1	Opn	Odd		Rect
A	(12 CMU) No Gym A108 "no" SGT	310 Pieces	\$294.26	\$1,518.04	262.222	33' 8"	98' 4"	1	Opn	Odd		Rect
A	(12 CMU) Gym A108 SGT	197 Pieces	\$187.03	\$964.86	166.667	33' 8"	125' 0"	1	Opn	Odd		Rect
Material [MW08150] Totals		17,820 Pieces	\$16,929.04	\$87,333.47	15,085.749	Mat. Lay Rate	150.0 Pieces/Day					
MW087" RIP 8" CMU 7" Rip		Lay 150.0 Pieces/Day	\$0.950/ Piece		SqFt	3.00% waste	1.286	Pieces per SqFt				
C2	1 8" CMU Corr Bearing no SGT	453 Pieces	\$430.21	\$2,262.47	341.961	13' 4"	587' 8"	1	Opn	Odd		Rect
C3	1 8" CMU Corr Bearing no SGT	453 Pieces	\$430.21	\$2,262.47	341.961	13' 4"	587' 8"	1	Opn	Odd		Rect
C1	1 8" CMU Corr Bearing no SGT	453 Pieces	\$430.21	\$2,262.47	341.961	13' 4"	587' 8"	1	Opn	Odd		Rect
B	8" CMU Corr with SGT base	385 Pieces	\$365.94	\$1,924.48	290.876	13' 4"	497' 4"	1	Opn	Odd		Rect
B	8" CMU Corr Bearing no SGT	43 Pieces	\$40.87	\$214.91	32.482	13' 4"	55' 8"	1		Odd		Rect
Material [MW087"RIP] Totals		1,787 Pieces	\$1,697.44	\$8,926.79	1,349.242	Mat. Lay Rate	150.0 Pieces/Day					
MW08BASE 8" VMU behind SGT		Lay 100.0 Pieces/Day	\$0.950/ Piece		SqFt	5.00% waste	1.125	Pieces per SqFt				
A	N Wall (12 CMU) Serving #119	7 Pieces	\$6.98	\$54.00	6.218	22' 8"	45' 0"	1	Opn	Odd		Rect
MW08BB 8" Mediumweight CMU-B.B.		Lay 120.0 Pieces/Day	\$1.150/ Piece		SqFt	3.00% waste	1.125	Pieces per SqFt				
A	Ext Col A	211 Pieces	\$242.27	\$1,315.65	181.810	16' 8"	279' 3"	1	Opn	Odd		Rect
B	North wall of Cafetorium SGT	34 Pieces	\$39.09	\$212.27	29.333	26' 0"	22' 0"	1	Opn	Odd		Rect
CA#1	Alt#1 42-8 N & S Full Brick	28 Pieces	\$31.98	\$173.67	24.000	42' 8"	36' 0"	1	Opn	Odd	Adj	Rect
C	42-8 N & S Full Brick	28 Pieces	\$31.98	\$173.67	24.000	42' 8"	36' 0"	1	Opn	Odd		Rect
CA#1	Alt#1 North Brick&CMU	124 Pieces	\$142.58	\$774.30	107.000	40' 0"	57' 0"	1	Opn	Odd		Rect
C	Col 23 F.5 to N 3 story Classr	668 Pieces	\$768.67	\$4,174.21	576.833	40' 0"	290' 2"	1	Opn	Odd		Rect
C2	1 8" CMU Corr Bearing no SGT	453 Pieces	\$520.78	\$2,828.09	390.813	13' 4"	587' 8"	1	Opn	Odd		Rect
C3	1 8" CMU Corr Bearing no SGT	453 Pieces	\$520.78	\$2,828.09	390.813	13' 4"	587' 8"	1	Opn	Odd		Rect
C1	1 8" CMU Corr Bearing no SGT	453 Pieces	\$520.78	\$2,828.09	390.813	13' 4"	587' 8"	1	Opn	Odd		Rect
B	8" CMU Corr with SGT base	385 Pieces	\$442.98	\$2,405.60	332.430	13' 4"	497' 4"	1	Opn	Odd		Rect
B2	8" CMU Corr with SGT base2nd F	188 Pieces	\$215.70	\$1,171.36	161.869	12' 0"	242' 0"	1	Opn	Odd		Rect
B	8" CMU Corr Bearing no SGT	43 Pieces	\$49.47	\$268.64	37.123	13' 4"	55' 8"	1		Odd		Rect
C	Col 17 between E.5 & H.9	66 Pieces	\$76.00	\$412.74	57.036	40' 0"	85' 7"	1	Opn	Odd		Rect
B	Alcove B127a N Band Rm	43 Pieces	\$49.05	\$266.36	36.808	19' 8"	58' 4"	1	Opn	Odd		Rect
B2	8" CMU Corr with BB No SGT 2 f	31 Pieces	\$35.24	\$191.36	26.444	12' 0"	39' 8"	1		Odd		Rect
B	N Mech Rm 33-8	116 Pieces	\$132.96	\$722.03	99.778	20' 4"	149' 8"	1	Opn	Odd		Rect
B	Alt#2 (part out)33-8 N Band Rm	41 Pieces	\$46.60	\$253.07	34.972	33' 8"	54' 3"	1	Opn	Odd		Rect
B	E6 between 12.3 & 17 South Wall	145 Pieces	\$167.01	\$906.96	125.333	26' 0"	94' 0"	1	Opn	Odd		Rect
B	H7 between 6 & 6.8 N Ext Wall	39 Pieces	\$45.01	\$244.43	33.778	16' 0"	50' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 with Insul	15 Pieces	\$17.18	\$93.27	12.889	28' 8"	9' 8"	1	Opn	Odd		Rect
B	North wall of Cafetorium	123 Pieces	\$140.96	\$765.45	105.778	26' 0"	79' 4"	1	Opn	Odd	Adj	Rect

CMU Continued

Wall

	Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
B West Wall Vest B123 NO Insul	40 Pieces	\$46.20	\$250.86	34.667	28' 8"	26' 0"	1	Opn	Odd		Rect
B East Wall Vest B123 NO Insul	21 Pieces	\$23.69	\$128.65	17.778	13' 4"	26' 8"	1	Opn	Odd		Rect
B 8" CMUf @ roof Col 10.1&10.9	123 Pieces	\$141.99	\$771.08	106.556	7' 4"	161' 4"	1		Odd		Rect
B 8" CMU Fill in @ roof	1 Piece	\$1.48	\$8.04	1.111	4' 8"	1' 8"	1		Odd		Rect
B N Wall Top of Main ent.	51 Pieces	\$58.76	\$319.09	44.095	22' 8"	69' 8"	1	Opn	Odd		Rect
B N Wall Top of Main ent.	40 Pieces	\$46.35	\$251.71	34.784	18' 8"	55' 4"	1	Opn	Odd		Rect
B N Wall Office B13 & 140	19 Pieces	\$21.32	\$115.78	16.000	13' 4"	24' 0"	1	Opn	Odd		Rect
B N Wall Confere B138 with Insul	36 Pieces	\$41.51	\$225.41	31.149	13' 4"	49' 8"	1	Opn	Odd		Rect
B H10 between 6.9 & 9	26 Pieces	\$29.67	\$161.14	22.269	19' 0"	18' 4"	1	Opn	Odd		Rect
B East Wall Vest B123 with Insul	8 Pieces	\$9.59	\$52.05	7.193	13' 4"	12' 8"	1	Opn	Odd		Rect
B E6 between 12??????????	58 Pieces	\$66.39	\$360.55	49.824	28' 8"	39' 0"	1	Opn	Odd		Rect
Material [MW08BB] Totals	4,108 Pieces	\$4,724.04	\$25,653.68	3,545.078	Mat. Lay Rate	120.0 Pieces/Day					

MW08BH	8MW CMU-1/2 Bullnose	Lay	225.0 Pieces/Day	\$0.600/ Piece	SqFt	2.00% waste	2.250	Pieces per SqFt		
B Alcove B127a N Band Rm	28 Pieces	\$16.60	\$93.06	12.056	19' 8"	58' 4"	1	Opn	Odd	Rect
B 8" CMU Band rm B127	28 Pieces	\$16.52	\$92.63	12.000	8' 0"	18' 0"	1		Odd	Rect
A 8" CMU Slope Hand Rail	87 Pieces	\$52.33	\$293.32	38.000	4' 0"	57' 0"	1		Odd	Rect
A 8"CMU Slope Hand Rail on Stage	53 Pieces	\$31.82	\$178.39	23.111	6' 0"	34' 8"	1		Odd	BotL
Material [MW08BH] Totals	195 Pieces	\$117.27	\$657.39	85.167	Mat. Lay Rate	225.0 Pieces/Day				

MW08HH	8" Mediumweight CMU-H.H.	Lay	160.0 Pieces/Day	\$0.750/ Piece	SqFt	2.00% waste	2.250	Pieces per SqFt		
C1 4 8"CMU 13-0 Reg Wall	80 Pieces	\$60.01	\$378.44	34.864	13' 0"	103' 4"	1	Opn	Odd	Rect
C1 3 8"CMU Corr SGT13-0 FireS	205 Pieces	\$153.95	\$970.85	89.441	13' 0"	264' 8"	1	Opn	Odd	Rect
C3 5 8" CMU Corr 2side SGT	10 Pieces	\$7.46	\$47.04	4.333	13' 0"	13' 0"	1	Opn	Odd	Rect
C3 4 8"CMU 13-0 Reg Wall	80 Pieces	\$60.01	\$378.44	34.864	13' 0"	103' 4"	1	Opn	Odd	Rect
C3 3 8"CMU Corr SGT13-0 FireS	205 Pieces	\$153.95	\$970.85	89.441	13' 0"	264' 8"	1	Opn	Odd	Rect
C2 3 8"CMU Corr SGT13-0 FireS	205 Pieces	\$153.95	\$970.85	89.441	13' 0"	264' 8"	1	Opn	Odd	Rect
C2 5 8" CMU Corr 2side SGT	10 Pieces	\$7.46	\$47.04	4.333	13' 0"	13' 0"	1	Opn	Odd	Rect
C2 4 8"CMU 13-0 Reg Wall	80 Pieces	\$60.01	\$378.44	34.864	13' 0"	103' 4"	1	Opn	Odd	Rect
C2 3 8"CMU Corr SGT13-0 FireS	205 Pieces	\$153.95	\$970.85	89.441	13' 0"	264' 8"	1	Opn	Odd	Rect
C1 5 8" CMU Corr 2side SGT	10 Pieces	\$7.46	\$47.04	4.333	13' 0"	13' 0"	1	Opn	Odd	Rect
B Alcove B127a N Band Rm	43 Pieces	\$32.02	\$201.92	18.602	19' 8"	58' 4"	1	Opn	Odd	Rect
B N Mech Rm 33-8	114 Pieces	\$85.87	\$541.53	49.889	20' 4"	149' 8"	1	Opn	Odd	Rect
B 8"CMU 13-0 FireSafe Reg Wall	525 Pieces	\$393.86	\$2,483.78	228.822	13' 0"	690' 7"	1	Opn	Odd	Rect
B 8"CMU Corr SGT13-0 FireS	64 Pieces	\$47.95	\$302.35	27.855	13' 0"	83' 7"	1	Opn	Odd	Rect
B 8" CMU Corr 2side SGT	26 Pieces	\$19.13	\$120.61	11.111	13' 0"	33' 4"	1	Opn	Odd	Rect
A (12 CMU) So Gym A108 "no" SGT	76 Pieces	\$56.99	\$359.41	33.111	33' 8"	99' 4"	1	Opn	Odd	Rect
A (12 CMU) No Gym A108 "no" SGT	75 Pieces	\$56.42	\$355.79	32.778	33' 8"	98' 4"	1	Opn	Odd	Rect
Material [MW08HH] Totals	2,014 Pieces	\$1,510.44	\$9,525.21	877.525	Mat. Lay Rate	160.0 Pieces/Day				

MW10	10" Mediumweight CMU	Lay	125.0 Pieces/Day	\$1.170/ Piece	SqFt	5.00% waste	1.125	Pieces per SqFt		
B North wall of Cafetorium SGT	8 Pieces	\$9.21	\$46.31	6.667	26' 0"	22' 0"	1	Opn	Odd	Rect
CA#1 Alt#1 42-8 N & S Full Brick	28 Pieces	\$33.17	\$166.73	24.000	42' 8"	36' 0"	1	Opn	Odd	Adj Rect
B Arch on Piers @ Ent for Mark?	27 Pieces	\$31.67	\$159.20	22.917	3' 0"	17' 0"	1	Opn		Rect
B Arch on Piers @ Ent for Mark?	26 Pieces	\$30.80	\$154.80	22.283	4' 4"	20' 0"	1	Opn	Odd	Rect
C 42-8 N & S Full Brick	28 Pieces	\$33.17	\$166.73	24.000	42' 8"	36' 0"	1	Opn	Odd	Rect
B 10" CMU Band Small Rms	1,557 Pieces	\$1,821.42	\$9,155.43	1,317.903	21' 4"	62' 0"	1			Rect
B West Wall Vest B123 NO Insul	389 Pieces	\$455.16	\$2,287.87	329.333	28' 8"	26' 0"	1	Opn	Odd	Rect
B East Wall Vest B123 NO Insul	221 Pieces	\$257.99	\$1,296.77	186.667	13' 4"	26' 8"	1	Opn	Odd	Rect
Material [MW10] Totals	2,284 Pieces	\$2,672.59	\$13,433.83	1,933.770	Mat. Lay Rate	125.0 Pieces/Day				

Sample Reports
Quantity/Bid Price Report

Wall

CMU Continued

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
MW10BB 10" Mediumweight CMU-B.B.		Lay	110.0 Pieces/Day	\$1.250/ Piece	SqFt	3.00% waste	1.125	Pieces per SqFt				
B	Arch on Piers @ Ent for Mark?	13 Pieces	\$16.14	\$87.96	11.142	4' 4"	20' 0"	1	Opn	Odd		Rect
B	Top of Piers @ Ent	43 Pieces	\$53.23	\$290.12	36.751	4' 4"	55' 2"	1	Opn	Odd		Rect
Material [MW10BB] Totals		55 Pieces	\$69.37	\$378.07	47.892	Mat. Lay Rate	110.0 Pieces/Day					
MW12 12" Mediumweight CMU		Lay	110.0 Pieces/Day	\$1.320/ Piece	SqFt	5.00% waste	1.125	Pieces per SqFt				
A	West wall Gym	2,868 Pieces	\$3,785.77	\$19,166.88	2,427.946	33' 8"	89' 8"	1	Opn	Odd		Rect
B	W Wall (12 CMU) Band B127	1,103 Pieces	\$1,455.65	\$7,369.75	933.556	20' 0"	57' 0"	1	Opn	Odd		Rect
B2	(12 CMU) IDF D226	198 Pieces	\$261.95	\$1,326.24	168.000	15' 0"	12' 0"	1		Odd		Rect
B	Alt#2 (part out)22-8 N Band Rm	1,816 Pieces	\$2,396.74	\$12,134.38	1,537.111	22' 8"	82' 4"	1	Opn	Odd		Rect
B	E Wall (12 CMU) Band B127	799 Pieces	\$1,055.09	\$5,341.80	676.667	22' 8"	35' 0"	1		Odd		Rect
A	N Wall (12 CMU) Serving #119	701 Pieces	\$925.85	\$4,687.48	593.782	22' 8"	45' 0"	1	Opn	Odd		Rect
A	18" Ext @ Cafetorium	1,835 Pieces	\$2,422.73	\$12,265.97	1,553.780	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
A	Alt2 12CMU Col 4.3 @ C&D (Out)	1,649 Pieces	\$2,176.71	\$11,020.41	1,396.000	33' 8"	48' 0"	1	Opn	Odd		Rect
A	(12 CMU) Projection RM Radi	594 Pieces	\$784.39	\$3,971.27	503.057	24' 10"	50' 4"	1	Opn	Odd	Adj	Rect
A	(12 CMU) So Gym A108 "no" SGT	2,381 Pieces	\$3,143.45	\$15,914.87	2,016.000	33' 8"	99' 4"	1	Opn	Odd		Rect
A	(12 CMU) No Gym A108 "no" SGT	2,323 Pieces	\$3,066.18	\$15,523.66	1,966.444	33' 8"	98' 4"	1	Opn	Odd		Rect
A	(12 CMU) Gym A108 SGT	3,676 Pieces	\$4,852.39	\$24,566.99	3,112.000	33' 8"	125' 0"	1	Opn	Odd		Rect
A	(12 CMU) Corr A106 SGT	2,457 Pieces	\$3,242.79	\$16,417.81	2,079.710	21' 4"	104' 8"	1		Odd		Rect
A	(12 CMU) Around Stage A110	3,545 Pieces	\$4,679.83	\$23,693.36	3,001.333	21' 4"	176' 0"	1	Opn			Rect
Material [MW12] Totals		25,947 Pieces	\$34,249.53	\$173,400.87	21,965.386	Mat. Lay Rate	110.0 Pieces/Day					
MW12 HA 12" Mediumweight half		Lay	175.0 Pieces/Day	\$0.650/ Piece	SqFt	3.00% waste	2.250	Pieces per SqFt				
A	(12 CMU) So Gym A108 "no" SGT	136 Pieces	\$88.37	\$582.22	58.667	33' 8"	99' 4"	1	Opn	Odd		Rect
A	(12 CMU) No Gym A108 "no" SGT	136 Pieces	\$88.37	\$582.22	58.667	33' 8"	98' 4"	1	Opn	Odd		Rect
A	(12 CMU) Gym A108 SGT	49 Pieces	\$32.14	\$211.72	21.333	33' 8"	125' 0"	1	Opn	Odd		Rect
Material [MW12 HA] Totals		321 Pieces	\$208.88	\$1,376.16	138.667	Mat. Lay Rate	175.0 Pieces/Day					
MW12BB 12" Mediumweight CMU-B.B.		Lay	100.0 Pieces/Day	\$1.520/ Piece	SqFt	5.00% waste	1.125	Pieces per SqFt				
A	West wall Gym	200 Pieces	\$304.67	\$1,473.50	169.685	33' 8"	89' 8"	1	Opn	Odd		Rect
B	W Wall (12 CMU) Band B127	83 Pieces	\$126.88	\$613.65	70.667	20' 0"	57' 0"	1	Opn	Odd		Rect
B2	(12 CMU) IDF D226	9 Pieces	\$14.36	\$69.47	8.000	15' 0"	12' 0"	1		Odd		Rect
B	Alt#2 (part out)22-8 N Band Rm	123 Pieces	\$187.13	\$905.04	104.222	22' 8"	82' 4"	1	Opn	Odd		Rect
B	E Wall (12 CMU) Band B127	55 Pieces	\$83.79	\$405.24	46.667	22' 8"	35' 0"	1		Odd		Rect
A	N Wall (12 CMU) Serving #119	106 Pieces	\$161.60	\$781.53	90.000	22' 8"	45' 0"	1	Opn	Odd		Rect
A	18" Ext @ Cafetorium	235 Pieces	\$357.19	\$1,727.52	198.938	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
A	Alt2 12CMU Col 4.3 @ C&D (Out)	38 Pieces	\$57.46	\$277.88	32.000	33' 8"	48' 0"	1	Opn	Odd		Rect
A	(12 CMU) Projection RM Radi	79 Pieces	\$120.50	\$582.77	67.111	24' 10"	50' 4"	1	Opn	Odd	Adj	Rect
A	(12 CMU) So Gym A108 "no" SGT	235 Pieces	\$356.71	\$1,725.16	198.667	33' 8"	99' 4"	1	Opn	Odd		Rect
A	(12 CMU) No Gym A108 "no" SGT	232 Pieces	\$353.12	\$1,707.80	196.667	33' 8"	98' 4"	1	Opn	Odd		Rect
A	(12 CMU) Gym A108 SGT	295 Pieces	\$448.88	\$2,170.93	250.000	33' 8"	125' 0"	1	Opn	Odd		Rect
Material [MW12BB] Totals		1,692 Pieces	\$2,572.28	\$12,440.48	1,432.624	Mat. Lay Rate	100.0 Pieces/Day					
MW12BBSLO 12" CMU-B.B. Slow/Cuts		Lay	50.0 Pieces/Day	\$1.520/ Piece	SqFt	5.00% waste	1.125	Pieces per SqFt				
A	(12 CMU) Projection RM Radi	40 Pieces	\$60.25	\$582.77	33.556	24' 10"	50' 4"	1	Opn	Odd	Adj	Rect
MW12HH 12" Mediumweight CMU-H.H.		Lay	145.0 Pieces/Day	\$0.750/ Piece	SqFt	3.00% waste	2.250	Pieces per SqFt				
A	West wall Gym	66 Pieces	\$49.16	\$338.73	28.281	33' 8"	89' 8"	1	Opn	Odd		Rect
B2	(12 CMU) IDF D226	9 Pieces	\$6.95	\$47.91	4.000	15' 0"	12' 0"	1		Odd		Rect
A	Alt2 12CMU Col 4.3 @ C&D (Out)	37 Pieces	\$27.81	\$191.64	16.000	33' 8"	48' 0"	1	Opn	Odd		Rect

Sample Reports
Quantity/Bid Price Report

CMU Continued

					Wall				
	Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn Odd Adj	Shape
A (12 CMU) Gym A108 SGT	97 Pieces	\$72.42	\$499.06	41.667	33' 8"	125' 0"	1	Opn Odd	Rect
Material [MW12HH] Totals	208 Pieces	\$156.34	\$1,077.35	89.948	Mat. Lay Rate	145.0 Pieces/Day			
Class Totals C.M.U.	179,821 Pieces	\$176,702.57	\$965,507.41	149109.827	Avg. Lay Rate	137.1 Pieces/Day			

Classification **DRI**

Drip Edging

S.S. DRIP	Stainless Stel Drip .0156	Lay	2,000.0 LinFt/Day	\$0.650/ LinFt	LinFt	Show as LinFt					
A Ext Col A		10	LinFt	\$6.28	\$3.73	9.667	16' 8"	279' 3"	1	Opn Odd	Rect
CA#1 Alt#1 42-8 N & S Full Brick		124	LinFt	\$80.82	\$47.99	124.333	42' 8"	36' 0"	1	Opn Odd Adj	Rect
A West wall Gym		92	LinFt	\$60.02	\$35.64	92.333	33' 8"	89' 8"	1	Opn Odd	Rect
C 42-8 N & S Full Brick		111	LinFt	\$72.37	\$42.97	111.333	42' 8"	36' 0"	1	Opn Odd	Rect
CA#1 Alt#1 North Brick&CMU		57	LinFt	\$37.05	\$22.00	57.000	40' 0"	57' 0"	1	Opn Odd	Rect
C Col 23 F.5 to N 3 story Classr		1,278	LinFt	\$830.38	\$493.04	1,277.500	40' 0"	290' 2"	1	Opn Odd	Rect
C Col 17 between E.5 & H.9		97	LinFt	\$62.76	\$37.26	96.555	40' 0"	85' 7"	1	Opn Odd	Rect
B Alcove B127a N Band Rm		86	LinFt	\$55.74	\$33.09	85.750	19' 8"	58' 4"	1	Opn Odd	Rect
B N Mech Rm 33-8		131	LinFt	\$85.37	\$50.69	131.333	20' 4"	149' 8"	1	Opn Odd	Rect
B Alt#2 (part out)33-8 N Band Rm		45	LinFt	\$29.39	\$17.45	45.208	33' 8"	54' 3"	1	Opn Odd	Rect
B E6 between 12.3 & 17 South Wal		255	LinFt	\$165.97	\$98.54	255.333	26' 0"	94' 0"	1	Opn Odd	Rect
B W Wall (12 CMU) Band B127		41	LinFt	\$26.43	\$15.70	40.667	20' 0"	57' 0"	1	Opn Odd	Rect
Dumpster Privacy Wall		26	LinFt	\$16.95	\$10.07	26.083	8' 0"	28' 2"	1	Odd	Rect
Dumpster Privacy Wall Ends		4	LinFt	\$2.82	\$1.67	4.333	8' 0"	6' 0"	2		Pier
B2 (12 CMU) IDF D226		12	LinFt	\$7.80	\$4.63	12.000	15' 0"	12' 0"	1	Odd	Rect
B Alcove B127a N Band Rm @26-0		41	LinFt	\$26.87	\$15.95	41.333	10' 8"	41' 4"	1	Odd	Rect
B Alt#2 (part out)22-8 N Band Rm		92	LinFt	\$60.02	\$35.64	92.333	22' 8"	82' 4"	1	Opn Odd	Rect
B E Wall (12 CMU) Band B127		35	LinFt	\$22.75	\$13.51	35.000	22' 8"	35' 0"	1	Odd	Rect
A N Wall (12 CMU) Serving #119		25	LinFt	\$16.25	\$9.65	25.000	22' 8"	45' 0"	1	Opn Odd	Rect
A 18" Ext @ Cafetorium		202	LinFt	\$131.30	\$77.96	202.000	22' 8"	114' 0"	1	Opn Odd Adj	Rect
A Alt2 12CMU Col 4.3 @ C&D (Out)		48	LinFt	\$31.20	\$18.53	48.000	33' 8"	48' 0"	1	Opn Odd	Rect
B H7 between 6 & 6.8 N Ext Wall		117	LinFt	\$75.83	\$45.03	116.667	16' 0"	50' 8"	1	Opn Odd	Rect
B West Wall Vest B123 with Insul		20	LinFt	\$12.78	\$7.59	19.667	28' 8"	9' 8"	1	Opn Odd	Rect
A (12 CMU) Projection RM Radi		34	LinFt	\$22.32	\$13.25	34.334	24' 10"	50' 4"	1	Opn Odd Adj	Rect
B West Wall Vest B123 NO Insul		46	LinFt	\$29.90	\$17.75	46.000	28' 8"	26' 0"	1	Opn Odd	Rect
B N Wall Top of Main ent.		168	LinFt	\$109.43	\$64.97	168.348	22' 8"	69' 8"	1	Opn Odd	Rect
B N Wall Top of Main ent.		149	LinFt	\$97.07	\$57.63	149.333	18' 8"	55' 4"	1	Opn Odd	Rect
B N Wall Office B13 & 140		57	LinFt	\$37.27	\$22.13	57.333	13' 4"	24' 0"	1	Opn Odd	Rect
B N Wall Confere B138 with Insul		120	LinFt	\$77.78	\$46.18	119.667	13' 4"	49' 8"	1	Opn Odd	Rect
B H10 between 6.9 & 9		22	LinFt	\$14.35	\$8.52	22.083	19' 0"	18' 4"	1	Opn Odd	Rect
B East Wall Vest B123 with Insul		23	LinFt	\$14.73	\$8.75	22.667	13' 4"	12' 8"	1	Opn Odd	Rect
B E6 between 12???????????		139	LinFt	\$90.35	\$53.65	139.000	28' 8"	39' 0"	1	Opn Odd	Rect
B E&W Walls Office B136 & 140		25	LinFt	\$16.32	\$9.69	25.104	10' 0"	25' 1"	1		Rect
A (12 CMU) So Gym A108 "no" SGT		93	LinFt	\$60.23	\$35.76	92.667	33' 8"	99' 4"	1	Opn Odd	Rect
A (12 CMU) No Gym A108 "no" SGT		89	LinFt	\$57.85	\$34.35	89.000	33' 8"	98' 4"	1	Opn Odd	Rect
Material [S.S. DRIP] Totals	3,915 LinFt	\$2,544.73	\$1,510.95	3,914.965	Mat. Lay Rate	2,000.0 LinFt/Day					

Classification **FIR**

Fire Safeing

FIRESAFE4	Fire Safeing 4" High x 6"	Lay	10,000.0 LinFt/Day	\$0.000/ LinFt	LinFt	Show as LinFt					
A (8 CMU) Corr A106 SGT		22	LinFt	\$0.00	\$1.72	22.333	21' 4"	22' 4"	1	Opn Odd Adj	Rect
C3 3 Copy 5 8" CMU Corr 2side SGT		8	LinFt	\$0.00	\$0.62	8.000	13' 4"	8' 0"	1	Opn Odd	Rect
CA#1 3rd FI 8" CMU Corr 2side SGT		8	LinFt	\$0.00	\$0.62	8.000	13' 4"	8' 0"	1	Opn Odd	Rect

FIR Continued

Wall

	Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
CA#1 Copy 5 8" CMU Corr 2side SGT	8 LinFt	\$0.00	\$0.62	8.000	13' 4"	8' 0"	1	Opn	Odd		Rect
C2 3 Copy 5 8" CMU Corr 2side SGT	8 LinFt	\$0.00	\$0.62	8.000	13' 4"	8' 0"	1	Opn	Odd		Rect
C3 5 8" CMU Corr 2side SGT	13 LinFt	\$0.00	\$1.00	13.000	13' 0"	13' 0"	1	Opn	Odd		Rect
C2 5 8" CMU Corr 2side SGT	13 LinFt	\$0.00	\$1.00	13.000	13' 0"	13' 0"	1	Opn	Odd		Rect
C1 5 8" CMU Corr 2side SGT	13 LinFt	\$0.00	\$1.00	13.000	13' 0"	13' 0"	1	Opn	Odd		Rect
B2 8" CMU CorSGTnoBB 2nd F	39 LinFt	\$0.00	\$3.04	39.333	12' 0"	39' 4"	1	Opn	Odd		Rect
B2 8" CMU 2nd Fl no base	302 LinFt	\$0.00	\$23.32	302.114	12' 8"	303' 4"	1	Opn			Rect
B2 4"CMU 12-8 FireSafe 2nd Floor	70 LinFt	\$0.00	\$5.40	70.000	12' 8"	70' 0"	1				Rect
B2 8" CMU CorSGTnoBB 12-8	155 LinFt	\$0.00	\$11.96	155.000	12' 8"	154' 4"	1	Opn	Odd		Rect
B2 8" CMU @ Learn Cent @ Door	18 LinFt	\$0.00	\$1.35	17.552	7' 4"	17' 0"	1				Rect
B2 8" CMU CorSGTnoBB12-8"	10 LinFt	\$0.00	\$0.77	10.000	12' 8"	10' 0"	1		Odd		Rect
B 10" CMU Band Small Rms	62 LinFt	\$0.00	\$4.77	61.777	21' 4"	62' 0"	1				Rect
B 4"CMU 13-0 FireSafe Reg Wall	140 LinFt	\$0.00	\$10.78	139.667	13' 0"	139' 8"	1		Odd		Rect
B 8"CMU 13-0 FireSafe Reg Wall	686 LinFt	\$0.01	\$52.99	686.465	13' 0"	690' 7"	1	Opn	Odd		Rect
B 8"CMU Corr SGT13-0 FireS	84 LinFt	\$0.00	\$6.45	83.565	13' 0"	83' 7"	1	Opn	Odd		Rect
B 8" CMU Corr 2side SGT	33 LinFt	\$0.00	\$2.57	33.333	13' 0"	33' 4"	1	Opn	Odd		Rect
A (8 CMU) Corr A104 SGT	28 LinFt	\$0.00	\$2.15	27.807	15' 4"	29' 4"	1	Opn	Odd		Rect
A 4" CMU Pipe Chase A103	5 LinFt	\$0.00	\$0.39	4.988	15' 4"	5' 4"	1				Rect
A 8" CMU A 101, 102, 103, 117&8	96 LinFt	\$0.00	\$7.38	95.667	15' 4"	96' 4"	1	Opn			Rect
A 8" CMU Projection Rm Walls	26 LinFt	\$0.00	\$2.01	26.000	14' 2"	26' 0"	1				Rect
A#3C Alt3 out (4 CMU) Serving #119	8 LinFt	\$0.00	\$0.64	8.333	15' 4"	8' 4"	1				Rect
A#3C Alt3 out (8 CMU) Corr A104 SGT	35 LinFt	\$0.00	\$2.70	35.000	15' 4"	35' 0"	1	Opn	Odd		Rect
A#3C Alt3 out (8 CMU) Serving #119	45 LinFt	\$0.00	\$3.47	45.000	15' 4"	45' 0"	1	Opn			Rect
A (12 CMU) Corr A106 SGT	101 LinFt	\$0.00	\$7.77	100.631	21' 4"	104' 8"	1		Odd		Rect
A (12 CMU) Around Stage A110	174 LinFt	\$0.00	\$13.43	174.000	21' 4"	176' 0"	1	Opn			Rect
Material [FIRESAFE4] Totals	2,210 LinFt	\$0.02	\$170.55	2,209.566	Mat. Lay Rate	10,000.0 LinFt/Day					

Classification **FLA**

Flashing

WRGRACE24	W.R. Grace 24" Flashing	Lay	500.0 LinFt/Day	\$2.000/ LinFt	LinFt	Show as LinFt					
A Ext Col A	272 LinFt	\$543.12	\$419.22	271.559	16' 8"	279' 3"	1	Opn	Odd		Rect
CA#1 Alt#1 42-8 N & S Full Brick	124 LinFt	\$248.67	\$191.94	124.333	42' 8"	36' 0"	1	Opn	Odd	Adj	Rect
A West wall Gym	92 LinFt	\$184.67	\$142.54	92.333	33' 8"	89' 8"	1	Opn	Odd		Rect
C 42-8 N & S Full Brick	111 LinFt	\$222.67	\$171.87	111.333	42' 8"	36' 0"	1	Opn	Odd		Rect
CA#1 Alt#1 North Brick&CMU	57 LinFt	\$114.00	\$87.99	57.000	40' 0"	57' 0"	1	Opn	Odd		Rect
C Col 23 F.5 to N 3 story Classr	1,278 LinFt	\$2,555.00	\$1,972.17	1,277.500	40' 0"	290' 2"	1	Opn	Odd		Rect
CA#1 Alt#1 Cor Ent ReturnsCol E.5	7 LinFt	\$13.33	\$10.29	6.667	8' 8"	6' 8"	1		Odd		Rect
C Cor Ent ReturnsCol E.5	7 LinFt	\$13.33	\$10.29	6.667	8' 8"	6' 8"	1		Odd		Rect
C Col 17 between E.5 & H.9	97 LinFt	\$193.11	\$149.06	96.555	40' 0"	85' 7"	1	Opn	Odd		Rect
B Alcove B127a N Band Rm	86 LinFt	\$171.50	\$132.38	85.750	19' 8"	58' 4"	1	Opn	Odd		Rect
B N Mech Rm 33-8	131 LinFt	\$262.67	\$202.75	131.333	20' 4"	149' 8"	1	Opn	Odd		Rect
B Alt#2 (part out)33-8 N Band Rm	45 LinFt	\$90.42	\$69.79	45.208	33' 8"	54' 3"	1	Opn	Odd		Rect
B E6 between 12.3 & 17 South Wal	255 LinFt	\$510.67	\$394.18	255.333	26' 0"	94' 0"	1	Opn	Odd		Rect
B W Wall (12 CMU) Band B127	41 LinFt	\$81.33	\$62.78	40.667	20' 0"	57' 0"	1	Opn	Odd		Rect
Dumpster Privacy Wall	26 LinFt	\$52.17	\$40.27	26.083	8' 0"	28' 2"	1		Odd		Rect
Dumpster Privacy Wall Ends	4 LinFt	\$8.67	\$6.69	4.333	8' 0"	6' 0"	2				Pier
B2 (12 CMU) IDF D226	12 LinFt	\$24.00	\$18.53	12.000	15' 0"	12' 0"	1		Odd		Rect
B Alcove B127a N Band Rm @26-0	41 LinFt	\$82.67	\$63.81	41.333	10' 8"	41' 4"	1		Odd		Rect
B Alt2(out)Cor Ent ReturnsCol #3	6 LinFt	\$12.67	\$9.78	6.333	8' 8"	6' 4"	1		Odd		Rect
B Alt#2 (part out)22-8 N Band Rm	92 LinFt	\$184.67	\$142.54	92.333	22' 8"	82' 4"	1	Opn	Odd		Rect
A Corr Ent Returns	7 LinFt	\$13.33	\$10.29	6.667	8' 8"	6' 8"	1		Odd		Rect
B E Wall (12 CMU) Band B127	35 LinFt	\$70.00	\$54.03	35.000	22' 8"	35' 0"	1		Odd		Rect

FLA Continued

						Wall						
		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
A	N Wall (12 CMU) Serving #119	25 LinFt	\$50.00	\$38.59	25.000	22' 8"	45' 0"	1	Opn	Odd		Rect
A	18" Ext @ Cafetorium	202 LinFt	\$404.00	\$311.84	202.000	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
A	Alt2 12CMU Col 4.3 @ C&D (Out)	48 LinFt	\$96.00	\$74.10	48.000	33' 8"	48' 0"	1	Opn	Odd		Rect
B	H7 between 6 & 6.8 N Ext Wall	117 LinFt	\$233.33	\$180.11	116.667	16' 0"	50' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 with Insul	20 LinFt	\$39.33	\$30.36	19.667	28' 8"	9' 8"	1	Opn	Odd		Rect
A	(12 CMU) Projection RM Radi	34 LinFt	\$68.67	\$53.00	34.334	24' 10"	50' 4"	1	Opn	Odd	Adj	Rect
B	West Wall Vest B123 NO Insul	46 LinFt	\$92.00	\$71.01	46.000	28' 8"	26' 0"	1	Opn	Odd		Rect
B	N Wall Top of Main ent.	168 LinFt	\$336.70	\$259.89	168.348	22' 8"	69' 8"	1	Opn	Odd		Rect
B	N Wall Top of Main ent.	149 LinFt	\$298.67	\$230.54	149.333	18' 8"	55' 4"	1	Opn	Odd		Rect
B	N Wall Office B13 & 140	57 LinFt	\$114.67	\$88.51	57.333	13' 4"	24' 0"	1	Opn	Odd		Rect
B	N Wall Confere B138 with Insul	120 LinFt	\$239.33	\$184.74	119.667	13' 4"	49' 8"	1	Opn	Odd		Rect
B	H10 between 6.9 & 9	22 LinFt	\$44.17	\$34.09	22.083	19' 0"	18' 4"	1	Opn	Odd		Rect
B	East Wall Vest B123 with Insul	23 LinFt	\$45.33	\$34.99	22.667	13' 4"	12' 8"	1	Opn	Odd		Rect
B	E6 between 12???????????	139 LinFt	\$278.00	\$214.58	139.000	28' 8"	39' 0"	1	Opn	Odd		Rect
B	E&W Walls Office B136 & 140	25 LinFt	\$50.21	\$38.75	25.104	10' 0"	25' 1"	1				Rect
B	Below barrel parapet	41 LinFt	\$82.67	\$63.81	41.333	10' 8"	41' 4"	1		Odd		Rect
A	(12 CMU) So Gym A108 "no" SGT	93 LinFt	\$185.33	\$143.06	92.667	33' 8"	99' 4"	1	Opn	Odd		Rect
A	(12 CMU) No Gym A108 "no" SGT	89 LinFt	\$178.00	\$137.40	89.000	33' 8"	98' 4"	1	Opn	Odd		Rect
Material [WRGRACE24] Totals		4,245 LinFt	\$8,489.05	\$6,552.57	4,244.523	Mat. Lay Rate	500.0 LinFt/Day					

Classification **GLA**

Glass Blocks

NOCOSTGLA No Cost for this item		Lay	90.0 Pieces/Day	\$78.222/ Piece	SqFt	7.111	SqFt per Piece					
B	Alcove B127a N Band Rm	2 Pieces		\$151.56	\$16.62	13.778	19' 8"	58' 4"	1	Opn	Odd	Rect

Classification **GRO**

Grout

3000PSI 3000 PSI Grout in Cu.Ft.		Lay	175.0 CbcFt/Day	\$3.600/ CbcFt	CbcFt	Show as CbcFt						
A	Ext Col A	178 CbcFt	\$639.46	\$783.47	177.627	16' 8"	279' 3"	1	Opn	Odd		Rect
B	North wall of Cafetorium SGT	37 CbcFt	\$134.27	\$164.50	37.296	26' 0"	22' 0"	1	Opn	Odd		Rect
CA#1	Alt#1 42-8 N & S Full Brick	123 CbcFt	\$441.13	\$540.48	122.537	42' 8"	36' 0"	1	Opn	Odd	Adj	Rect
B	Arch on Piers @ Ent for Mark?	15 CbcFt	\$52.31	\$64.10	14.532	4' 4"	20' 0"	1	Opn	Odd		Rect
A	West wall Gym	161 CbcFt	\$577.82	\$707.96	160.507	33' 8"	89' 8"	1	Opn	Odd		Rect
B	8 CMU Top Radius@ Band	0 CbcFt	\$0.00	\$0.00	0.001	6' 0"	41' 4"	1	Opn			Rect
C	42-8 N & S Full Brick	123 CbcFt	\$441.13	\$540.48	122.537	42' 8"	36' 0"	1	Opn	Odd		Rect
CA#1	Alt#1 North Brick&CMU	42 CbcFt	\$152.74	\$187.14	42.427	40' 0"	57' 0"	1	Opn	Odd		Rect
C	Col 23 F.5 to N 3 story Classr	338 CbcFt	\$1,215.38	\$1,489.10	337.604	40' 0"	290' 2"	1	Opn	Odd		Rect
C2	1 8" CMU Corr Bearing no SGT	155 CbcFt	\$557.87	\$683.51	154.963	13' 4"	587' 8"	1	Opn	Odd		Rect
C3	1 8" CMU Corr Bearing no SGT	155 CbcFt	\$557.87	\$683.51	154.963	13' 4"	587' 8"	1	Opn	Odd		Rect
C1	1 8" CMU Corr Bearing no SGT	155 CbcFt	\$557.87	\$683.51	154.963	13' 4"	587' 8"	1	Opn	Odd		Rect
B	8" CMU Corr with SGT base	142 CbcFt	\$511.86	\$627.14	142.183	13' 4"	497' 4"	1	Opn	Odd		Rect
B2	8" CMU Corr with SGT base2nd F	64 CbcFt	\$231.06	\$283.10	64.184	12' 0"	242' 0"	1	Opn	Odd		Rect
B	8" CMU Corr Bearing no SGT	15 CbcFt	\$52.99	\$64.93	14.720	13' 4"	55' 8"	1		Odd		Rect
C	Col 17 between E.5 & H.9	23 CbcFt	\$81.42	\$99.75	22.616	40' 0"	85' 7"	1	Opn	Odd		Rect
B	Alcove B127a N Band Rm	46 CbcFt	\$165.75	\$203.07	46.040	19' 8"	58' 4"	1	Opn	Odd		Rect
B2	8" CMU Corr with BB No SGT 2 f	10 CbcFt	\$37.75	\$46.25	10.486	12' 0"	39' 8"	1		Odd		Rect
B	N Mech Rm 33-8	404 CbcFt	\$1,454.83	\$1,782.48	404.119	20' 4"	149' 8"	1	Opn	Odd		Rect
B	Alt#2 (part out)33-8 N Band Rm	136 CbcFt	\$490.54	\$601.02	136.261	33' 8"	54' 3"	1	Opn	Odd		Rect
B	E6 between 12.3 & 17 South Wal	100 CbcFt	\$360.89	\$442.17	100.249	26' 0"	94' 0"	1	Opn	Odd		Rect
B	W Wall (12 CMU) Band B127	53 CbcFt	\$190.97	\$233.98	53.049	20' 0"	57' 0"	1	Opn	Odd		Rect
B2	(12 CMU) IDF D226	6 CbcFt	\$21.62	\$26.49	6.005	15' 0"	12' 0"	1		Odd		Rect

Sample Reports
Quantity/Bid Price Report

GRO Continued

Wall

	Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
B Alcove B127a N Band Rm @26-0	87	CbcFt	\$312.64	\$383.06	86.846	10' 8"	41' 4"	1	Odd		Rect
B Alt#2 (part out)22-8 N Band Rm	124	CbcFt	\$445.62	\$545.98	123.784	22' 8"	82' 4"	1	Opn	Odd	Rect
B E Wall (12 CMU) Band B127	49	CbcFt	\$175.11	\$214.55	48.642	22' 8"	35' 0"	1	Odd		Rect
A N Wall (12 CMU) Serving #119	103	CbcFt	\$369.21	\$452.37	102.559	22' 8"	45' 0"	1	Opn	Odd	Rect
A 18" Ext @ Cafetorium	368	CbcFt	\$1,324.94	\$1,623.33	368.038	22' 8"	114' 0"	1	Opn	Odd	Adj Rect
A Alt2 12CMU Col 4.3 @ C&D (Out)	51	CbcFt	\$183.13	\$224.38	50.870	33' 8"	48' 0"	1	Opn	Odd	Rect
B H7 between 6 & 6.8 N Ext Wall	26	CbcFt	\$93.01	\$113.96	25.837	16' 0"	50' 8"	1	Opn	Odd	Rect
B West Wall Vest B123 with Insul	13	CbcFt	\$45.46	\$55.70	12.629	28' 8"	9' 8"	1	Opn	Odd	Rect
A (12 CMU) Projection RM Radi	76	CbcFt	\$272.05	\$333.32	75.569	24' 10"	50' 4"	1	Opn	Odd	Adj Rect
B North wall of Cafetorium	134	CbcFt	\$484.17	\$593.21	134.492	26' 0"	79' 4"	1	Opn	Odd	Adj Rect
B West Wall Vest B123 NO Insul	34	CbcFt	\$122.28	\$149.82	33.967	28' 8"	26' 0"	1	Opn	Odd	Rect
B East Wall Vest B123 NO Insul	20	CbcFt	\$73.72	\$90.33	20.478	13' 4"	26' 8"	1	Opn	Odd	Rect
B 8" CMUf @ roof Col 10.1&10.9	325	CbcFt	\$1,168.75	\$1,431.97	324.652	7' 4"	161' 4"	1	Odd		Rect
B 8" CMU Fill in @ roof	0	CbcFt	\$1.59	\$1.94	0.441	4' 8"	1' 8"	1	Odd		Rect
B Top of Piers @ Ent	20	CbcFt	\$72.61	\$88.97	20.170	4' 4"	55' 2"	1	Opn	Odd	Rect
B N Wall Top of Main ent.	95	CbcFt	\$343.55	\$420.93	95.431	22' 8"	69' 8"	1	Opn	Odd	Rect
B N Wall Top of Main ent.	34	CbcFt	\$123.32	\$151.10	34.257	18' 8"	55' 4"	1	Opn	Odd	Rect
B N Wall Office B13 & 140	6	CbcFt	\$22.84	\$27.98	6.344	13' 4"	24' 0"	1	Opn	Odd	Rect
B N Wall Confere B138 with Insul	28	CbcFt	\$100.46	\$123.09	27.906	13' 4"	49' 8"	1	Opn	Odd	Rect
B H10 between 6.9 & 9	22	CbcFt	\$79.42	\$97.30	22.061	19' 0"	18' 4"	1	Opn	Odd	Rect
B East Wall Vest B123 with Insul	8	CbcFt	\$28.93	\$35.45	8.037	13' 4"	12' 8"	1	Opn	Odd	Rect
B E6 between 12??????????	49	CbcFt	\$176.62	\$216.39	49.060	28' 8"	39' 0"	1	Opn	Odd	Rect
B Below barrel parapet	18	CbcFt	\$65.79	\$80.61	18.275	10' 8"	41' 4"	1	Odd		Rect
A (12 CMU) So Gym A108 "no" SGT	237	CbcFt	\$851.70	\$1,043.51	236.583	33' 8"	99' 4"	1	Opn	Odd	Rect
A (12 CMU) No Gym A108 "no" SGT	234	CbcFt	\$843.13	\$1,033.01	234.202	33' 8"	98' 4"	1	Opn	Odd	Rect
A (12 CMU) Gym A108 SGT	258	CbcFt	\$927.32	\$1,136.17	257.589	33' 8"	125' 0"	1	Opn	Odd	Rect
Material [3000PSI] Totals	4,899	CbcFt	\$17,634.91	\$21,606.54	4,898.586	Mat. Lay Rate	175.0	CbcFt/Day			

Classification **INR**

Rigid Insul.

BLUE2"	Blue 2 Rigid Insulation	Lay 1,500.0	SqFt/Day	\$0.600/ SqFt	SqFt	Show as SqFt					
A Ext Col A	3,912	SqFt	\$2,347.01	\$2,012.92	3,911.691	16' 8"	279' 3"	1	Opn	Odd	Rect
CA#1 Alt#1 42-8 N & S Full Brick	1,204	SqFt	\$722.17	\$619.37	1,203.611	42' 8"	36' 0"	1	Opn	Odd	Adj Rect
A West wall Gym	1,316	SqFt	\$789.43	\$677.06	1,315.721	33' 8"	89' 8"	1	Opn	Odd	Rect
C 42-8 N & S Full Brick	1,214	SqFt	\$728.43	\$624.74	1,214.056	42' 8"	36' 0"	1	Opn	Odd	Rect
CA#1 Alt#1 North Brick&CMU	918	SqFt	\$550.51	\$472.14	917.509	40' 0"	57' 0"	1	Opn	Odd	Rect
C Col 23 F.5 to N 3 story Classr	3,961	SqFt	\$2,376.90	\$2,038.55	3,961.499	40' 0"	290' 2"	1	Opn	Odd	Rect
CA#1 Alt#1 Cor Ent ReturnsCol E.5	58	SqFt	\$34.67	\$29.73	57.778	8' 8"	6' 8"	1	Odd		Rect
C Cor Ent ReturnsCol E.5	58	SqFt	\$34.67	\$29.73	57.778	8' 8"	6' 8"	1	Odd		Rect
B Alcove B127a N Band Rm	990	SqFt	\$594.27	\$509.67	990.442	19' 8"	58' 4"	1	Opn	Odd	Rect
B Alt#2 (part out)33-8 N Band Rm	1,103	SqFt	\$661.81	\$567.60	1,103.019	33' 8"	54' 3"	1	Opn	Odd	Rect
B E6 between 12.3 & 17 South Wal	1,331	SqFt	\$798.40	\$684.75	1,330.667	26' 0"	94' 0"	1	Opn	Odd	Rect
B Alcove B127a N Band Rm @26-0	193	SqFt	\$115.73	\$99.26	192.889	10' 8"	41' 4"	1	Odd		Rect
B Alt2(out)Cor Ent ReturnsCol #3	55	SqFt	\$32.93	\$28.25	54.889	8' 8"	6' 4"	1	Odd		Rect
B Alt#2 (part out)22-8 N Band Rm	1,702	SqFt	\$1,020.91	\$875.58	1,701.511	22' 8"	82' 4"	1	Opn	Odd	Rect
A Corr Ent Returns	58	SqFt	\$34.67	\$29.73	57.778	8' 8"	6' 8"	1	Odd		Rect
A 18" Ext @ Cafetorium	1,534	SqFt	\$920.57	\$789.52	1,534.279	22' 8"	114' 0"	1	Opn	Odd	Adj Rect
B H7 between 6 & 6.8 N Ext Wall	691	SqFt	\$414.40	\$355.41	690.667	16' 0"	50' 8"	1	Opn	Odd	Rect
B West Wall Vest B123 with Insul	235	SqFt	\$140.93	\$120.87	234.889	28' 8"	9' 8"	1	Opn	Odd	Rect
B West Wall Vest B123 NO Insul	309	SqFt	\$185.60	\$159.18	309.333	28' 8"	26' 0"	1	Opn	Odd	Rect
B N Wall Top of Main ent.	1,073	SqFt	\$644.01	\$552.34	1,073.350	22' 8"	69' 8"	1	Opn	Odd	Rect
B N Wall Top of Main ent.	571	SqFt	\$342.78	\$293.99	571.303	18' 8"	55' 4"	1	Opn	Odd	Rect

Sample Reports
Quantity/Bid Price Report

INR Continued

						Wall						
		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
B	N Wall Office B13 & 140	249 SqFt	\$149.33	\$128.08	248.889	13' 4"	24' 0"	1	Opn	Odd		Rect
B	N Wall Confere B138 with Insul	482 SqFt	\$289.00	\$247.86	481.668	13' 4"	49' 8"	1	Opn	Odd		Rect
B	H10 between 6.9 & 9	256 SqFt	\$153.42	\$131.58	255.706	19' 0"	18' 4"	1	Opn	Odd		Rect
B	East Wall Vest B123 with Insul	138 SqFt	\$82.80	\$71.02	138.004	13' 4"	12' 8"	1	Opn	Odd		Rect
B	E6 between 12???????????	796 SqFt	\$477.49	\$409.52	795.821	28' 8"	39' 0"	1	Opn	Odd		Rect
B	E&W Walls Office B136 & 140	233 SqFt	\$139.78	\$119.88	232.968	10' 0"	25' 1"	1				Rect
Material [BLUE2] Totals		24,638 SqFt	\$14,782.63	\$12,678.32	24,637.714	Mat. Lay Rate		1,500.0	SqFt/Day			

Classification **MOR**

Mortar (CuFt)

Mortar[L]		[L] Type N White Port/Lime---- Reg Sand		\$3.82 / CbcFt	CbcFt	Show as CbcFt							
A	(8 CMU) Corr A106 SGT	1	CbcFt	\$3.23	\$0.00	0.846	21' 4"	22' 4"	1	Opn	Odd	Adj	Rect
B	North wall of Cafetorium SGT	1	CbcFt	\$1.98	\$0.00	0.519	26' 0"	22' 0"	1	Opn	Odd		Rect
CA#1	2Copy Stair C133 SGT	1	CbcFt	\$5.53	\$0.00	1.449	13' 4"	13' 4"	1		Odd	Adj	Rect
CA#1	3rdStair C133 SGT	1	CbcFt	\$5.53	\$0.00	1.449	13' 4"	13' 4"	1		Odd	Adj	Rect
C3	3 Copy 5 8" CMU Corr 2side SGT	0	CbcFt	\$0.56	\$0.00	0.146	13' 4"	8' 0"	1	Opn	Odd		Rect
CA#1	3rd FI 8" CMU Corr 2side SGT	0	CbcFt	\$0.56	\$0.00	0.146	13' 4"	8' 0"	1	Opn	Odd		Rect
CA#1	Copy 5 8" CMU Corr 2side SGT	0	CbcFt	\$0.56	\$0.00	0.146	13' 4"	8' 0"	1	Opn	Odd		Rect
C3	2Copy Stair C100 SGT	2	CbcFt	\$6.47	\$0.00	1.694	13' 4"	23' 0"	1		Odd		Rect
C2	3 Copy 5 8" CMU Corr 2side SGT	0	CbcFt	\$0.56	\$0.00	0.146	13' 4"	8' 0"	1	Opn	Odd		Rect
C2	2Copy Stair C100 SGT	2	CbcFt	\$6.47	\$0.00	1.694	13' 4"	23' 0"	1		Odd		Rect
CA#1	Alt#1 C133 Stair	3	CbcFt	\$10.32	\$0.00	2.702	13' 4"	41' 4"	1	Opn	Odd		Rect
C1	Stair C100 SGT	3	CbcFt	\$10.64	\$0.00	2.785	13' 4"	41' 8"	1	Opn	Odd		Rect
C1	3 8"CMU Corr SGT13-0 FireS	19	CbcFt	\$71.86	\$0.00	18.819	13' 0"	264' 8"	1	Opn	Odd		Rect
C3	5 8" CMU Corr 2side SGT	1	CbcFt	\$2.68	\$0.00	0.702	13' 0"	13' 0"	1	Opn	Odd		Rect
C3	3 8"CMU Corr SGT13-0 FireS	19	CbcFt	\$71.86	\$0.00	18.819	13' 0"	264' 8"	1	Opn	Odd		Rect
C2	3 8"CMU Corr SGT13-0 FireS	19	CbcFt	\$71.86	\$0.00	18.819	13' 0"	264' 8"	1	Opn	Odd		Rect
C2	5 8" CMU Corr 2side SGT	1	CbcFt	\$2.68	\$0.00	0.702	13' 0"	13' 0"	1	Opn	Odd		Rect
C2	3 8"CMU Corr SGT13-0 FireS	19	CbcFt	\$71.86	\$0.00	18.819	13' 0"	264' 8"	1	Opn	Odd		Rect
C1	5 8" CMU Corr 2side SGT	1	CbcFt	\$2.68	\$0.00	0.702	13' 0"	13' 0"	1	Opn	Odd		Rect
B	8" CMU Corr with SGT base	34	CbcFt	\$130.12	\$0.00	34.075	13' 4"	497' 4"	1	Opn	Odd		Rect
B2	8" CMU Corr with SGT base2nd F	16	CbcFt	\$62.68	\$0.00	16.415	12' 0"	242' 0"	1	Opn	Odd		Rect
B2	8" CMU CorSGTnoBB 2nd F	3	CbcFt	\$12.52	\$0.00	3.278	12' 0"	39' 4"	1	Opn	Odd		Rect
B2	8" CMU CorSGTnoBB 12-8	11	CbcFt	\$41.62	\$0.00	10.900	12' 8"	154' 4"	1	Opn	Odd		Rect
B2	8" CMU CorSGTnoBB12-8"	1	CbcFt	\$3.18	\$0.00	0.833	12' 8"	10' 0"	1		Odd		Rect
B	8"CMU Corr SGT13-0 FireS	5	CbcFt	\$19.99	\$0.00	5.236	13' 0"	83' 7"	1	Opn	Odd		Rect
B	8" CMU Corr SGT base DisplayCa	5	CbcFt	\$18.77	\$0.00	4.917	13' 4"	59' 0"	1	Opn	Odd		Rect
B	8" CMU Corr 2side SGT	1	CbcFt	\$3.80	\$0.00	0.995	13' 0"	33' 4"	1	Opn	Odd		Rect
B	West Wall Vest B123 NO Insul	2	CbcFt	\$8.27	\$0.00	2.167	28' 8"	26' 0"	1	Opn	Odd		Rect
B	East Wall Vest B123 NO Insul	2	CbcFt	\$7.32	\$0.00	1.917	13' 4"	26' 8"	1	Opn	Odd		Rect
A	(8 CMU) Corr A104 SGT	1	CbcFt	\$3.71	\$0.00	0.970	15' 4"	29' 4"	1	Opn	Odd		Rect
A#3C	Alt3 out (8 CMU) Corr A104 SGT	1	CbcFt	\$3.30	\$0.00	0.865	15' 4"	35' 0"	1	Opn	Odd		Rect
A	(12 CMU) Gym A108 SGT	6	CbcFt	\$21.08	\$0.00	5.519	33' 8"	125' 0"	1	Opn	Odd		Rect
A	(12 CMU) Corr A106 SGT	6	CbcFt	\$21.66	\$0.00	5.672	21' 4"	104' 8"	1		Odd		Rect
Mortar [S] Totals		185 CbcFt	\$705.92	\$0.00	184.867								

Mortar[S]		[S] Silo Mix-Type N Port/Lime-1:1:6 Mix		\$4.07 / CbcFt	CbcFt	Show as CbcFt							
A	Ext Col A	882	CbcFt	\$3,595.18	\$0.00	882.453	16' 8"	279' 3"	1	Opn	Odd		Rect
CA#1	A#1 Copy Locker Base SGT 3rd	1	CbcFt	\$3.76	\$0.00	0.924	0' 5"	7' 4"	1				Rect
A	(8 CMU) Corr A106 SGT	33	CbcFt	\$133.95	\$0.00	32.879	21' 4"	22' 4"	1	Opn	Odd	Adj	Rect
B	(8 CMU) Splitface Top Radius	18	CbcFt	\$72.71	\$0.00	17.847	6' 0"	41' 4"	1	Opn			Rect

MOR Continued

Wall

	Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
B North wall of Cafetorium SGT	71	CbcFt \$288.40	\$0.00	70.790	26' 0"	22' 0"	1	Opn	Odd		Rect
CA#1 Alt#1 42-8 N & S Full Brick	249	CbcFt \$1,014.53	\$0.00	249.021	42' 8"	36' 0"	1	Opn	Odd	Adj	Rect
B Arch on Piers @ Ent for Mark?	7	CbcFt \$30.51	\$0.00	7.489	3' 0"	17' 0"	1	Opn			Rect
B Arch on Piers @ Ent for Mark?	15	CbcFt \$60.36	\$0.00	14.816	4' 4"	20' 0"	1	Opn	Odd		Rect
CA#1 Copy Reg CMU Stair #133	14	CbcFt \$55.41	\$0.00	13.600	13' 4"	11' 4"	1				Rect
A West wall Gym	447	CbcFt \$1,821.94	\$0.00	447.204	33' 8"	89' 8"	1	Opn	Odd		Rect
CA#1 2Copy Stair C133 SGT	10	CbcFt \$42.31	\$0.00	10.386	13' 4"	13' 4"	1		Odd	Adj	Rect
CA#1 3rdStair C133 SGT	10	CbcFt \$42.31	\$0.00	10.386	13' 4"	13' 4"	1		Odd	Adj	Rect
C3 3 Copy 5 8" CMU Corr 2side SGT	5	CbcFt \$21.67	\$0.00	5.320	13' 4"	8' 0"	1	Opn	Odd		Rect
B 8 CMU Top Radius@ Band	22	CbcFt \$89.89	\$0.00	22.065	6' 0"	41' 4"	1	Opn			Rect
C 42-8 N & S Full Brick	249	CbcFt \$1,013.40	\$0.00	248.743	42' 8"	36' 0"	1	Opn	Odd		Rect
CA#1 3rd Fl 8" CMU Corr 2side SGT	5	CbcFt \$21.67	\$0.00	5.320	13' 4"	8' 0"	1	Opn	Odd		Rect
CA#1 Copy 5 8" CMU Corr 2side SGT	5	CbcFt \$21.67	\$0.00	5.320	13' 4"	8' 0"	1	Opn	Odd		Rect
CA#1 2 Copy Reg CMU Stair #133	21	CbcFt \$84.74	\$0.00	20.800	13' 4"	17' 4"	1				Rect
CA#1 2 Copy Reg CMU Stair #133	21	CbcFt \$84.74	\$0.00	20.800	13' 4"	17' 4"	1				Rect
CA#1 A#1 Copy Locker Base SGT	1	CbcFt \$3.76	\$0.00	0.924	0' 5"	7' 4"	1				Rect
C2 Reg CMU Stair #100	14	CbcFt \$55.41	\$0.00	13.600	13' 4"	11' 4"	1				Rect
C3 2Copy Stair C100 SGT	28	CbcFt \$112.23	\$0.00	27.547	13' 4"	23' 0"	1		Odd		Rect
C3 2 Copy Reg CMU Stair #133	21	CbcFt \$84.74	\$0.00	20.800	13' 4"	17' 4"	1				Rect
C3 4 Copy Locker Base SGT 1st Fl	1	CbcFt \$3.76	\$0.00	0.924	0' 5"	7' 4"	1				Rect
C2 4 Copy Locker Base SGT 1st Fl	1	CbcFt \$3.76	\$0.00	0.924	0' 5"	7' 4"	1				Rect
C2 3 Copy 5 8" CMU Corr 2side SGT	5	CbcFt \$21.67	\$0.00	5.320	13' 4"	8' 0"	1	Opn	Odd		Rect
C2 2 Copy Reg CMU Stair #133	21	CbcFt \$84.74	\$0.00	20.800	13' 4"	17' 4"	1				Rect
CA#1 Alt#1 Reg CMU Stair #133	40	CbcFt \$162.96	\$0.00	40.000	13' 4"	34' 0"	1				Rect
C2 2Copy Stair C100 SGT	28	CbcFt \$112.23	\$0.00	27.547	13' 4"	23' 0"	1		Odd		Rect
CA#1 Alt#1 Locker Base SGT 1st Fl	1	CbcFt \$3.76	\$0.00	0.924	0' 5"	4' 4"	1				Rect
CA#1 Alt#1 North Brick&CMU	289	CbcFt \$1,178.12	\$0.00	289.174	40' 0"	57' 0"	1	Opn	Odd		Rect
C Col 23 F.5 to N 3 story Classr	1,335	CbcFt \$5,437.13	\$0.00	1,334.569	40' 0"	290' 2"	1	Opn	Odd		Rect
CA#1 Alt#1 C133 Stair	44	CbcFt \$181.23	\$0.00	44.483	13' 4"	41' 4"	1	Opn	Odd		Rect
CA#1 Alt#1 Returns 1-2" E.5	2	CbcFt \$8.99	\$0.00	2.206	8' 8"	1' 2"	2		Odd		Gable
CA#1 Alt#1 Cor Ent ReturnsCol E.5	12	CbcFt \$46.86	\$0.00	11.503	8' 8"	6' 8"	1		Odd		Rect
C Cor Ent ReturnsCol E.5	12	CbcFt \$46.86	\$0.00	11.503	8' 8"	6' 8"	1		Odd		Rect
C Returns 1-2" E.5	2	CbcFt \$8.99	\$0.00	2.206	8' 8"	1' 2"	2		Odd		Gable
C1 2 Locker Base SGT 1st Fl	15	CbcFt \$62.41	\$0.00	15.319	0' 5"	242' 4"	1				Rect
C1 Stair C100 8" CMU Reg Wall	41	CbcFt \$166.22	\$0.00	40.800	13' 4"	34' 8"	1		Opn	Odd	Rect
C1 4 8"CMU 13-0 Reg Wall	121	CbcFt \$492.43	\$0.00	120.870	13' 0"	103' 4"	1	Opn	Odd		Rect
C1 Stair C100 SGT	45	CbcFt \$183.01	\$0.00	44.921	13' 4"	41' 8"	1	Opn	Odd		Rect
C2 1 8" CMU Corr Bearing no SGT	695	CbcFt \$2,832.33	\$0.00	695.208	13' 4"	587' 8"	1	Opn	Odd		Rect
C1 3 8"CMU Corr SGT13-0 FireS	296	CbcFt \$1,205.80	\$0.00	295.970	13' 0"	264' 8"	1	Opn	Odd		Rect
C3 6 4"CMU 13-0 Reg Wall	64	CbcFt \$261.68	\$0.00	64.231	13' 0"	55' 8"	1		Odd		Rect
C2 6 4"CMU 13-0 Reg Wall	64	CbcFt \$261.68	\$0.00	64.231	13' 0"	55' 8"	1		Odd		Rect
C1 6 4"CMU 13-0 Reg Wall	64	CbcFt \$261.68	\$0.00	64.231	13' 0"	55' 8"	1		Odd		Rect
C3 5 8" CMU Corr 2side SGT	10	CbcFt \$40.70	\$0.00	9.990	13' 0"	13' 0"	1	Opn	Odd		Rect
C3 4 8"CMU 13-0 Reg Wall	121	CbcFt \$492.43	\$0.00	120.870	13' 0"	103' 4"	1	Opn	Odd		Rect
C3 3 8"CMU Corr SGT13-0 FireS	296	CbcFt \$1,205.80	\$0.00	295.970	13' 0"	264' 8"	1	Opn	Odd		Rect
C2 3 8"CMU Corr SGT13-0 FireS	296	CbcFt \$1,205.80	\$0.00	295.970	13' 0"	264' 8"	1	Opn	Odd		Rect
C3 2 Locker Base SGT 1st Fl	14	CbcFt \$57.40	\$0.00	14.090	0' 5"	222' 8"	1				Rect
C3 1 8" CMU Corr Bearing no SGT	695	CbcFt \$2,832.33	\$0.00	695.208	13' 4"	587' 8"	1	Opn	Odd		Rect
C2 5 8" CMU Corr 2side SGT	10	CbcFt \$40.70	\$0.00	9.990	13' 0"	13' 0"	1	Opn	Odd		Rect
C2 4 8"CMU 13-0 Reg Wall	121	CbcFt \$492.43	\$0.00	120.870	13' 0"	103' 4"	1	Opn	Odd		Rect
C2 3 8"CMU Corr SGT13-0 FireS	296	CbcFt \$1,205.80	\$0.00	295.970	13' 0"	264' 8"	1	Opn	Odd		Rect
C2 2 Locker Base SGT 1st Fl	14	CbcFt \$57.40	\$0.00	14.090	0' 5"	222' 8"	1				Rect
C1 5 8" CMU Corr 2side SGT	10	CbcFt \$40.70	\$0.00	9.990	13' 0"	13' 0"	1	Opn	Odd		Rect

Sample Reports
Quantity/Bid Price Report

MOR Continued

Wall

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
C1	1 8" CMU Corr Bearing no SGT	695 CbcFt	\$2,832.33	\$0.00	695.208	13' 4"	587' 8"	1	Opn	Odd		Rect
B	8" CMU Corr with SGT base	561 CbcFt	\$2,286.73	\$0.00	561.289	13' 4"	497' 4"	1	Opn	Odd		Rect
B2	8" CMU Corr with SGT base2nd F	230 CbcFt	\$937.34	\$0.00	230.075	12' 0"	242' 0"	1	Opn	Odd		Rect
A	Locker Base SGT	16 CbcFt	\$63.26	\$0.00	15.528	0' 5"	245' 0"	1				Rect
B	8" CMU Corr Bearing no SGT	70 CbcFt	\$285.32	\$0.00	70.034	13' 4"	55' 8"	1		Odd		Rect
C	Col 17 between E.5 & H.9	299 CbcFt	\$1,216.51	\$0.00	298.597	40' 0"	85' 7"	1	Opn	Odd		Rect
B	Alcove B127a N Band Rm	217 CbcFt	\$884.36	\$0.00	217.069	19' 8"	58' 4"	1	Opn	Odd		Rect
B2	8" CMU Corr with BB No SGT 2 f	43 CbcFt	\$174.53	\$0.00	42.840	12' 0"	39' 8"	1		Odd		Rect
B2	8" CMU CorSGTnoBB 2nd F	17 CbcFt	\$71.01	\$0.00	17.429	12' 0"	39' 4"	1	Opn	Odd		Rect
B	N Mech Rm 33-8	264 CbcFt	\$1,074.64	\$0.00	263.775	20' 4"	149' 8"	1	Opn	Odd		Rect
B	Alt#2 (part out)33-8 N Band Rm	275 CbcFt	\$1,120.77	\$0.00	275.099	33' 8"	54' 3"	1	Opn	Odd		Rect
B	E6 between 12.3 & 17 South Wal	343 CbcFt	\$1,396.35	\$0.00	342.740	26' 0"	94' 0"	1	Opn	Odd		Rect
B	W Wall (12 CMU) Band B127	98 CbcFt	\$400.23	\$0.00	98.239	20' 0"	57' 0"	1	Opn	Odd		Rect
	Dumpster Privacy Wall	70 CbcFt	\$283.83	\$0.00	69.667	8' 0"	28' 2"	1		Odd		Rect
	Dumpster Privacy Wall Ends	11 CbcFt	\$43.65	\$0.00	10.713	8' 0"	6' 0"	2				Pier
	Brick Piers in Learning Center	6 CbcFt	\$25.79	\$0.00	6.331	3' 4"	20' 8"	1				Rect
	Brick Piers in Learning Center	10 CbcFt	\$39.51	\$0.00	9.697	3' 4"	8' 0"	4				Pier
B2	(12 CMU) IDF D226	18 CbcFt	\$73.33	\$0.00	18.000	15' 0"	12' 0"	1		Odd		Rect
B2	8" CMU 2nd Fl no base	333 CbcFt	\$1,358.34	\$0.00	333.410	12' 8"	303' 4"	1	Opn			Rect
B2	4"CMU 12-8 FireSafe 2nd Floor	77 CbcFt	\$312.61	\$0.00	76.731	12' 8"	70' 0"	1				Rect
B2	8" CMU CorSGTnoBB 12-8	160 CbcFt	\$653.31	\$0.00	160.357	12' 8"	154' 4"	1	Opn	Odd		Rect
B2	8" CMU @ Learn Cent @ Door	12 CbcFt	\$47.20	\$0.00	11.585	7' 4"	17' 0"	1				Rect
B2	8" CMU CorSGTnoBB12-8"	11 CbcFt	\$46.35	\$0.00	11.377	12' 8"	10' 0"	1		Odd		Rect
B	8" CMU Band rm B127	13 CbcFt	\$52.80	\$0.00	12.960	8' 0"	18' 0"	1		Odd		Rect
B	Alcove B127a N Band Rm @26-0	85 CbcFt	\$347.48	\$0.00	85.291	10' 8"	41' 4"	1		Odd		Rect
B	Alt2(out)Cor Ent ReturnsCol #3	11 CbcFt	\$44.52	\$0.00	10.928	8' 8"	6' 4"	1		Odd		Rect
B	Alt2 (out) Returns 1-2" Col #3	2 CbcFt	\$8.99	\$0.00	2.206	8' 8"	1' 2"	2		Odd		Gable
A	Returns 1-2"	2 CbcFt	\$8.99	\$0.00	2.206	8' 8"	1' 2"	2		Odd		Gable
B	Alt#2 (part out)22-8 N Band Rm	370 CbcFt	\$1,505.48	\$0.00	369.526	22' 8"	82' 4"	1	Opn	Odd		Rect
A	Corr Ent Returns	12 CbcFt	\$46.86	\$0.00	11.503	8' 8"	6' 8"	1		Odd		Rect
B	10" CMU Band Small Rms	129 CbcFt	\$525.25	\$0.00	128.925	21' 4"	62' 0"	1				Rect
B	E Wall (12 CMU) Band B127	80 CbcFt	\$324.32	\$0.00	79.606	22' 8"	35' 0"	1		Odd		Rect
A	N Wall (12 CMU) Serving #119	85 CbcFt	\$346.82	\$0.00	85.127	22' 8"	45' 0"	1	Opn	Odd		Rect
A	18" Ext @ Cafetorium	392 CbcFt	\$1,596.24	\$0.00	391.805	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
A	Alt2 12CMU Col 4.3 @ C&D (Out)	149 CbcFt	\$605.35	\$0.00	148.586	33' 8"	48' 0"	1	Opn	Odd		Rect
B	H7 between 6 & 6.8 N Ext Wall	137 CbcFt	\$556.57	\$0.00	136.613	16' 0"	50' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 with Insul	52 CbcFt	\$213.86	\$0.00	52.493	28' 8"	9' 8"	1	Opn	Odd		Rect
B	4"CMU 13-0 FireSafe Reg Wall	161 CbcFt	\$656.55	\$0.00	161.154	13' 0"	139' 8"	1		Odd		Rect
B	8"CMU 13-0 FireSafe Reg Wall	797 CbcFt	\$3,248.24	\$0.00	797.294	13' 0"	690' 7"	1	Opn	Odd		Rect
B	8"CMU Corr SGT13-0 FireS	87 CbcFt	\$353.25	\$0.00	86.707	13' 0"	83' 7"	1	Opn	Odd		Rect
B	8" CMU Corr SGT base DisplayCa	27 CbcFt	\$111.89	\$0.00	27.464	13' 4"	59' 0"	1	Opn	Odd		Rect
B	8" CMU Corr 2side SGT	20 CbcFt	\$81.17	\$0.00	19.923	13' 0"	33' 4"	1	Opn	Odd		Rect
A	(12 CMU) Projection RM Radi	106 CbcFt	\$431.16	\$0.00	105.830	24' 10"	50' 4"	1	Opn	Odd	Adj	Rect
B	North wall of Cafetorium	319 CbcFt	\$1,297.70	\$0.00	318.525	26' 0"	79' 4"	1	Opn	Odd	Adj	Rect
B	West Wall Vest B123 NO Insul	135 CbcFt	\$551.78	\$0.00	135.436	28' 8"	26' 0"	1	Opn	Odd		Rect
B	East Wall Vest B123 NO Insul	48 CbcFt	\$194.47	\$0.00	47.733	13' 4"	26' 8"	1	Opn	Odd		Rect
B	8" CMUf @ roof Col 10.1&10.9	123 CbcFt	\$501.83	\$0.00	123.175	7' 4"	161' 4"	1		Odd		Rect
B	8" CMU Fill in @ roof	1 CbcFt	\$2.85	\$0.00	0.700	4' 8"	1' 8"	1		Odd		Rect
B	Top of Piers @ Ent	63 CbcFt	\$258.34	\$0.00	63.410	4' 4"	55' 2"	1	Opn	Odd		Rect
B	Piers @ Ent B123 Arch	12 CbcFt	\$48.72	\$0.00	11.958	9' 8"	6' 4"	2		Odd		Pier
B	N Wall Top of Main ent.	241 CbcFt	\$980.67	\$0.00	240.709	22' 8"	69' 8"	1	Opn	Odd		Rect
B	N Wall Top of Main ent.	126 CbcFt	\$513.81	\$0.00	126.118	18' 8"	55' 4"	1	Opn	Odd		Rect
B	N Wall Office B13 & 140	46 CbcFt	\$186.02	\$0.00	45.659	13' 4"	24' 0"	1	Opn	Odd		Rect

MOR Continued

Wall

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
B	N Wall Confere B138 with Insul	94	CbcFt	\$383.12	\$0.00	94.038	13' 4"	49' 8"	1	Opn	Odd	Rect
B	N Main Ent Splitface Piers	28	CbcFt	\$113.78	\$0.00	27.927	10' 0"	25' 9"	1			Rect
B	N Main Ent Brick Piers	63	CbcFt	\$258.42	\$0.00	63.429	10' 0"	49' 9"	1			Rect
B	H10 between 6.9 & 9	61	CbcFt	\$248.10	\$0.00	60.898	19' 0"	18' 4"	1	Opn	Odd	Rect
B	Face of Pier veneer	11	CbcFt	\$45.39	\$0.00	11.142	9' 8"	9' 4"	1		Odd	Rect
B	East Wall Vest B123 with Insul	27	CbcFt	\$109.17	\$0.00	26.797	13' 4"	12' 8"	1	Opn	Odd	Rect
B	E6 between 12???????????	178	CbcFt	\$725.79	\$0.00	178.149	28' 8"	39' 0"	1	Opn	Odd	Rect
B	E&W Walls Office B136 & 140	41	CbcFt	\$165.59	\$0.00	40.645	10' 0"	25' 1"	1			Rect
B	Below barrel parapet	63	CbcFt	\$256.92	\$0.00	63.063	10' 8"	41' 4"	1		Odd	Rect
B	2x1-2 Pier @ 6.8 & 8	6	CbcFt	\$22.48	\$0.00	5.517	9' 8"	4' 0"	2		Odd	Pier
B	2x1-2 Pier @ 6.8 & 8	12	CbcFt	\$48.72	\$0.00	11.958	9' 8"	6' 4"	2		Odd	Pier
A	(8 CMU) Corr A104 SGT	31	CbcFt	\$126.26	\$0.00	30.992	15' 4"	29' 4"	1	Opn	Odd	Rect
A	(8 CMU) Top Radius	15	CbcFt	\$62.00	\$0.00	15.219	5' 1"	50' 4"	1	Opn		Rect
A	4" CMU Front of Stage A110	14	CbcFt	\$56.32	\$0.00	13.824	2' 11"	47' 4"	1		Odd	Rect
A	4" CMU Pipe Chase A103	7	CbcFt	\$26.97	\$0.00	6.619	15' 4"	5' 4"	1			Rect
A	8" CMU A 101, 102, 103, 117&8	125	CbcFt	\$510.97	\$0.00	125.420	15' 4"	96' 4"	1	Opn		Rect
A	8" CMU Projection Rm Walls	33	CbcFt	\$135.06	\$0.00	33.150	14' 2"	26' 0"	1			Rect
A	8" CMU Slope Hand Rail	21	CbcFt	\$83.60	\$0.00	20.520	4' 0"	57' 0"	1		Odd	Rect
A	8"CMU Slope Hand Rail on Stage	15	CbcFt	\$62.58	\$0.00	15.360	6' 0"	34' 8"	1		Odd	BotL
A#3C	Alt3 out (4 CMU) Serving #119	11	CbcFt	\$45.05	\$0.00	11.058	15' 4"	8' 4"	1			Rect
A#3C	Alt3 out (8 CMU) Corr A104 SGT	40	CbcFt	\$163.50	\$0.00	40.131	15' 4"	35' 0"	1	Opn	Odd	Rect
A#3C	Alt3 out (8 CMU) Serving #119	58	CbcFt	\$235.07	\$0.00	57.700	15' 4"	45' 0"	1	Opn		Rect
A	(12 CMU) So Gym A108 "no" SGT	326	CbcFt	\$1,326.41	\$0.00	325.574	33' 8"	99' 4"	1	Opn	Odd	Rect
A	(12 CMU) No Gym A108 "no" SGT	319	CbcFt	\$1,300.09	\$0.00	319.112	33' 8"	98' 4"	1	Opn	Odd	Rect
A	(12 CMU) Gym A108 SGT	397	CbcFt	\$1,615.52	\$0.00	396.537	33' 8"	125' 0"	1	Opn	Odd	Rect
A	(12 CMU) Corr A106 SGT	210	CbcFt	\$855.49	\$0.00	209.984	21' 4"	104' 8"	1		Odd	Rect
A	(12 CMU) Around Stage A110	295	CbcFt	\$1,202.70	\$0.00	295.209	21' 4"	176' 0"	1	Opn		Rect
Mortar [S] Totals		17,395	CbcFt	\$70,869.49	\$0.00	17,395.238						
Class Totals Mortar (CuFt)				\$71,575.41	\$0.00	17,580.105						

Classification **P****

Precast Cu Ft

DUMPSTERC Precast Dumpster Cap		Lay	50.0 CbcFt/Day	\$65.000/ CbcFt	CbcFt	Show as CbcFt						
	Dumpster Privacy Wall	20	CbcFt	\$1,318.66	\$313.19	20.287	8' 0"	28' 2"	1	Odd		Rect
	Dumpster Privacy Wall Ends	3	CbcFt	\$219.07	\$52.03	3.370	8' 0"	6' 0"	2			Pier
Material [DUMPSTERC] Totals		24	CbcFt	\$1,537.73	\$365.22	23.657	Mat. Lay Rate	50.0 CbcFt/Day				
PCS4-0SIL Precast Window Sill 4-0"		Lay	60.0 CbcFt/Day	\$65.000/ CbcFt	CbcFt	Show as CbcFt						
CA#1	Alt#1 42-8 N & S Full Brick	10	CbcFt	\$664.44	\$131.51	10.222	42' 8"	36' 0"	1	Opn	Odd	Adj Rect
C	42-8 N & S Full Brick	10	CbcFt	\$664.44	\$131.51	10.222	42' 8"	36' 0"	1	Opn	Odd	Rect
C	Col 23 F.5 to N 3 story Classr	144	CbcFt	\$9,329.91	\$1,846.57	143.537	40' 0"	290' 2"	1	Opn	Odd	Rect
B	E6 between 12.3 & 17 South Wal	10	CbcFt	\$664.44	\$131.51	10.222	26' 0"	94' 0"	1	Opn	Odd	Rect
B	H7 between 6 & 6.8 N Ext Wall	10	CbcFt	\$664.44	\$131.51	10.222	16' 0"	50' 8"	1	Opn	Odd	Rect
B	N Wall Top of Main ent.	12	CbcFt	\$775.19	\$153.42	11.926	22' 8"	69' 8"	1	Opn	Odd	Rect
B	N Wall Top of Main ent.	23	CbcFt	\$1,495.00	\$295.89	23.000	18' 8"	55' 4"	1	Opn	Odd	Rect
B	N Wall Office B13 & 140	10	CbcFt	\$664.44	\$131.51	10.222	13' 4"	24' 0"	1	Opn	Odd	Rect
B	H10 between 6.9 & 9	5	CbcFt	\$332.22	\$65.75	5.111	19' 0"	18' 4"	1	Opn	Odd	Rect
B	E6 between 12???????????	31	CbcFt	\$1,993.33	\$394.52	30.667	28' 8"	39' 0"	1	Opn	Odd	Rect
Material [PCS4-0SIL] Totals		265	CbcFt	\$17,247.87	\$3,413.69	265.352	Mat. Lay Rate	60.0 CbcFt/Day				

Sample Reports
Quantity/Bid Price Report

P Continued**

Wall

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
PCS4-8SIL Precast Window Sill 4-8"		Lay	60.0 Pieces/Day	\$193.796/ Piece	CbcFt		2.981	CbcFt per Piece				
CA#1	Alt#1 42-8 N & S Full Brick	5 Pieces	\$968.98	\$64.32	14.907	42' 8"	36' 0"	1	Opn	Odd	Adj	Rect
C	42-8 N & S Full Brick	5 Pieces	\$968.98	\$64.32	14.907	42' 8"	36' 0"	1	Opn	Odd		Rect
C	Col 23 F.5 to N 3 story Classr	7 Pieces	\$1,356.57	\$90.05	20.870	40' 0"	290' 2"	1	Opn	Odd		Rect
B	E6 between 12.3 & 17 South Wal	5 Pieces	\$968.98	\$64.32	14.907	26' 0"	94' 0"	1	Opn	Odd		Rect
B	Alt#2 (part out)22-8 N Band Rm	1 Piece	\$193.80	\$12.86	2.981	22' 8"	82' 4"	1	Opn	Odd		Rect
A	18" Ext @ Cafetorium	8 Pieces	\$1,550.37	\$102.92	23.852	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
B	H7 between 6 & 6.8 N Ext Wall	2 Pieces	\$387.59	\$25.73	5.963	16' 0"	50' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 with Insul	1 Piece	\$193.80	\$12.86	2.981	28' 8"	9' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 NO Insul	2 Pieces	\$387.59	\$25.73	5.963	28' 8"	26' 0"	1	Opn	Odd		Rect
B	East Wall Vest B123 NO Insul	3 Pieces	\$636.76	\$42.27	9.796	13' 4"	26' 8"	1	Opn	Odd		Rect
B	N Wall Top of Main ent.	6 Pieces	\$1,162.78	\$77.19	17.889	22' 8"	69' 8"	1	Opn	Odd		Rect
B	N Wall Top of Main ent.	2 Pieces	\$387.59	\$25.73	5.963	18' 8"	55' 4"	1	Opn	Odd		Rect
B	N Wall Confere B138 with Insul	7 Pieces	\$1,411.94	\$93.73	21.722	13' 4"	49' 8"	1	Opn	Odd		Rect
B	East Wall Vest B123 with Insul	1 Piece	\$193.80	\$12.86	2.981	13' 4"	12' 8"	1	Opn	Odd		Rect
Material [PCS4-8SIL] Totals		56 Pieces	\$10,769.54	\$714.91	165.685	Mat. Lay Rate	60.0 Pieces/Day					
PCSBAND Precast Band		Lay	60.0 CbcFt/Day	\$65.000/ CbcFt	CbcFt		Show as CbcFt					
CA#1	Alt#1 North Brick&CMU	16 CbcFt	\$1,020.14	\$201.91	15.694	40' 0"	57' 0"	1	Opn	Odd		Rect
C	Col 23 F.5 to N 3 story Classr	45 CbcFt	\$2,911.46	\$576.23	44.792	40' 0"	290' 2"	1	Opn	Odd		Rect
B	E6 between 12.3 & 17 South Wal	15 CbcFt	\$987.04	\$195.35	15.185	26' 0"	94' 0"	1	Opn	Odd		Rect
A	18" Ext @ Cafetorium	19 CbcFt	\$1,259.37	\$249.25	19.375	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
B	H7 between 6 & 6.8 N Ext Wall	7 CbcFt	\$457.41	\$90.53	7.037	16' 0"	50' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 with Insul	3 CbcFt	\$174.54	\$34.54	2.685	28' 8"	9' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 NO Insul	7 CbcFt	\$469.44	\$92.91	7.222	28' 8"	26' 0"	1	Opn	Odd		Rect
B	East Wall Vest B123 NO Insul	2 CbcFt	\$138.43	\$27.40	2.130	13' 4"	26' 8"	1	Opn	Odd		Rect
B	Piers @ Ent B123 Arch	3 CbcFt	\$192.59	\$38.12	2.963	9' 8"	6' 4"	2		Odd		Pier
B	N Wall Office B13 & 140	2 CbcFt	\$144.44	\$28.59	2.222	13' 4"	24' 0"	1	Opn	Odd		Rect
B	N Wall Confere B138 with Insul	4 CbcFt	\$275.28	\$54.48	4.235	13' 4"	49' 8"	1	Opn	Odd		Rect
B	Face of Pier veneer	2 CbcFt	\$148.84	\$29.46	2.290	9' 8"	9' 4"	1		Odd		Rect
B	East Wall Vest B123 with Insul	2 CbcFt	\$139.60	\$27.63	2.148	13' 4"	12' 8"	1	Opn	Odd		Rect
B	E6 between 12??????????	4 CbcFt	\$266.62	\$52.77	4.102	28' 8"	39' 0"	1	Opn	Odd		Rect
B	2x1-2 Pier @ 6.8 & 8	2 CbcFt	\$108.33	\$21.44	1.667	9' 8"	4' 0"	2		Odd		Pier
B	2x1-2 Pier @ 6.8 & 8	3 CbcFt	\$192.59	\$38.12	2.963	9' 8"	6' 4"	2		Odd		Pier
Material [PCSBAND] Totals		137 CbcFt	\$8,886.13	\$1,758.74	136.710	Mat. Lay Rate	60.0 CbcFt/Day					
PCSBAND8" Precast Band 8" Wide		Lay	60.0 Pieces/Day	\$115.556/ Piece	CbcFt		1.778	CbcFt per Piece				
A	West wall Gym	22 Pieces	\$2,503.36	\$278.70	38.513	33' 8"	89' 8"	1	Opn	Odd		Rect
CA#1	Alt#1 North Brick&CMU	14 Pieces	\$1,627.41	\$181.18	25.037	40' 0"	57' 0"	1	Opn	Odd		Rect
C	Col 23 F.5 to N 3 story Classr	72 Pieces	\$8,372.96	\$932.16	128.815	40' 0"	290' 2"	1	Opn	Odd		Rect
B	Alt#2 (part out)33-8 N Band Rm	13 Pieces	\$1,558.80	\$173.54	23.981	33' 8"	54' 3"	1	Opn	Odd		Rect
B	E6 between 12.3 & 17 South Wal	24 Pieces	\$2,715.56	\$302.32	41.778	26' 0"	94' 0"	1	Opn	Odd		Rect
A	18" Ext @ Cafetorium	28 Pieces	\$3,283.69	\$365.57	50.518	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
Material [PCSBAND8"] Totals		174 Pieces	\$20,061.77	\$2,233.47	308.643	Mat. Lay Rate	60.0 Pieces/Day					
PCSHEADAR Precast Head Arched Panel		Lay	60.0 Pieces/Day	\$86.667/ Piece	CbcFt		1.333	CbcFt per Piece				
B	Arch on Piers @ Ent for Mark?	7 Pieces	\$593.14	\$88.05	9.125	4' 4"	20' 0"	1	Opn	Odd		Rect
B	H10 between 6.9 & 9	7 Pieces	\$593.14	\$88.05	9.125	19' 0"	18' 4"	1	Opn	Odd		Rect
Material [PCSHEADAR] Totals		14 Pieces	\$1,186.28	\$176.09	18.250	Mat. Lay Rate	60.0 Pieces/Day					

P Continued**

Wall

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
PCSHEADER Precast Header Panel		Lay	60.0 CbcFt/Day	\$65.000/ CbcFt	CbcFt	Show as CbcFt						
B	Top of Piers @ Ent	32	CbcFt	\$2,080.00	\$411.67	32.000	4' 4"	55' 2"	1	Opn	Odd	Rect
PCSSIGN Precast Curved Sign Panel		Lay	30.0 CbcFt/Day	\$125.000/ CbcFt	CbcFt	Show as CbcFt						
B	H7 between 6 & 6.8 N Ext Wall	1	CbcFt	\$166.67	\$34.31	1.333	16' 0"	50' 8"	1	Opn	Odd	Rect
B	N Wall Top of Main ent.	22	CbcFt	\$2,749.99	\$566.05	22.000	18' 8"	55' 4"	1	Opn	Odd	Rect
Material [PCSSIGN] Totals		23	CbcFt	\$2,916.66	\$600.35	23.333	Mat. Lay Rate	30.0 CbcFt/Day				
Class Totals Precast Cu Ft				\$64,685.98	\$9,674.13	973.630						

Classification **REB**

Rebar

		Lay	LinFt/Day	\$0.350/ LinFt	LinFt	Show as LinFt						
#5 #5 Rebar / Give Vert. Ht		Lay	1,700.0 LinFt/Day	\$0.350/ LinFt	LinFt							
B	Alcove B127a N Band Rm @26-0	251	LinFt	\$87.73	\$113.82	250.667	10' 8"	41' 4"	1	Odd		Rect
B	Below barrel parapet	256	LinFt	\$89.48	\$116.09	255.667	10' 8"	41' 4"	1	Odd		Rect
Material [#5] Totals		506	LinFt	\$177.22	\$229.90	506.333	Mat. Lay Rate	1,700.0 LinFt/Day				
#5BB REBA #5 Bond Beam Rebar - 240"		Lay	1,700.0 LinFt/Day	\$0.350/ LinFt	LinFt	Show as LinFt						
A	Ext Col A	608	LinFt	\$212.78	\$276.03	607.930	16' 8"	279' 3"	1	Opn	Odd	Rect
B	North wall of Cafetorium SGT	96	LinFt	\$33.72	\$43.74	96.333	26' 0"	22' 0"	1	Opn	Odd	Rect
CA#1	Alt#1 42-8 N & S Full Brick	80	LinFt	\$28.12	\$36.48	80.333	42' 8"	36' 0"	1	Opn	Odd	Adj Rect
B	Arch on Piers @ Ent for Mark?	38	LinFt	\$13.16	\$17.07	37.592	4' 4"	20' 0"	1	Opn	Odd	Rect
A	West wall Gym	572	LinFt	\$200.04	\$259.51	571.556	33' 8"	89' 8"	1	Opn	Odd	Rect
C	42-8 N & S Full Brick	80	LinFt	\$28.12	\$36.48	80.333	42' 8"	36' 0"	1	Opn	Odd	Rect
CA#1	Alt#1 North Brick&CMU	358	LinFt	\$125.47	\$162.78	358.500	40' 0"	57' 0"	1	Opn	Odd	Rect
C	Col 23 F.5 to N 3 story Classr	1,931	LinFt	\$675.68	\$876.54	1,930.500	40' 0"	290' 2"	1	Opn	Odd	Rect
C2	1 8" CMU Corr Bearing no SGT	1,306	LinFt	\$457.02	\$592.89	1,305.771	13' 4"	587' 8"	1	Opn	Odd	Rect
C3	1 8" CMU Corr Bearing no SGT	1,306	LinFt	\$457.02	\$592.89	1,305.771	13' 4"	587' 8"	1	Opn	Odd	Rect
C1	1 8" CMU Corr Bearing no SGT	1,306	LinFt	\$457.02	\$592.89	1,305.771	13' 4"	587' 8"	1	Opn	Odd	Rect
B	8" CMU Corr with SGT base	1,110	LinFt	\$388.43	\$503.90	1,109.789	13' 4"	497' 4"	1	Opn	Odd	Rect
B2	8" CMU Corr with SGT base2nd F	540	LinFt	\$188.92	\$245.08	539.775	12' 0"	242' 0"	1	Opn	Odd	Rect
B	8" CMU Corr Bearing no SGT	124	LinFt	\$43.35	\$56.24	123.868	13' 4"	55' 8"	1	Opn	Odd	Rect
C	Col 17 between E.5 & H.9	188	LinFt	\$65.72	\$85.26	187.776	40' 0"	85' 7"	1	Opn	Odd	Rect
B	Alcove B127a N Band Rm	123	LinFt	\$43.02	\$55.81	122.923	19' 8"	58' 4"	1	Opn	Odd	Rect
B2	8" CMU Corr with BB No SGT 2 f	88	LinFt	\$30.68	\$39.81	87.667	12' 0"	39' 8"	1	Opn	Odd	Rect
B	N Mech Rm 33-8	333	LinFt	\$116.43	\$151.05	332.667	20' 4"	149' 8"	1	Opn	Odd	Rect
B	Alt#2 (part out)33-8 N Band Rm	117	LinFt	\$41.10	\$53.31	117.417	33' 8"	54' 3"	1	Opn	Odd	Rect
B	E6 between 12.3 & 17 South Wal	418	LinFt	\$146.18	\$189.64	417.667	26' 0"	94' 0"	1	Opn	Odd	Rect
B	W Wall (12 CMU) Band B127	237	LinFt	\$82.95	\$107.61	237.000	20' 0"	57' 0"	1	Opn	Odd	Rect
B2	(12 CMU) IDF D226	24	LinFt	\$8.40	\$10.90	24.000	15' 0"	12' 0"	1	Opn	Odd	Rect
B	Alt#2 (part out)22-8 N Band Rm	346	LinFt	\$121.10	\$157.10	346.000	22' 8"	82' 4"	1	Opn	Odd	Rect
B	E Wall (12 CMU) Band B127	148	LinFt	\$51.92	\$67.35	148.333	22' 8"	35' 0"	1	Opn	Odd	Rect
A	N Wall (12 CMU) Serving #119	295	LinFt	\$103.25	\$133.94	295.000	22' 8"	45' 0"	1	Opn	Odd	Rect
A	18" Ext @ Cafetorium	672	LinFt	\$235.14	\$305.04	671.815	22' 8"	114' 0"	1	Opn	Odd	Adj Rect
A	Alt2 12CMU Col 4.3 @ C&D (Out)	113	LinFt	\$39.43	\$51.16	112.667	33' 8"	48' 0"	1	Opn	Odd	Rect
B	H7 between 6 & 6.8 N Ext Wall	110	LinFt	\$38.38	\$49.79	109.667	16' 0"	50' 8"	1	Opn	Odd	Rect
B	West Wall Vest B123 with Insul	39	LinFt	\$13.53	\$17.56	38.667	28' 8"	9' 8"	1	Opn	Odd	Rect
A	(12 CMU) Projection RM Radi	327	LinFt	\$114.45	\$148.47	327.000	24' 10"	50' 4"	1	Opn	Odd	Adj Rect
B	North wall of Cafetorium	351	LinFt	\$122.73	\$159.22	350.667	26' 0"	79' 4"	1	Opn	Odd	Adj Rect
B	West Wall Vest B123 NO Insul	112	LinFt	\$39.32	\$51.00	112.333	28' 8"	26' 0"	1	Opn	Odd	Rect
B	East Wall Vest B123 NO Insul	58	LinFt	\$20.13	\$26.11	57.500	13' 4"	26' 8"	1	Opn	Odd	Rect

REB Continued

						Wall						
		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
B	8" CMUf @ roof Col 10.1&10.9	357 LinFt	\$125.01	\$162.17	357.167	7' 4"	161' 4"	1		Odd		Rect
B	8" CMU Fill in @ roof	3 LinFt	\$1.17	\$1.51	3.333	4' 8"	1' 8"	1		Odd		Rect
B	Top of Piers @ Ent	123 LinFt	\$42.96	\$55.74	122.752	4' 4"	55' 2"	1	Opn	Odd		Rect
B	N Wall Top of Main ent.	145 LinFt	\$50.67	\$65.74	144.785	22' 8"	69' 8"	1	Opn	Odd		Rect
B	N Wall Top of Main ent.	117 LinFt	\$40.90	\$53.06	116.851	18' 8"	55' 4"	1	Opn	Odd		Rect
B	N Wall Office B13 & 140	52 LinFt	\$18.26	\$23.69	52.167	13' 4"	24' 0"	1	Opn	Odd		Rect
B	N Wall Confere B138 with Insul	102 LinFt	\$35.62	\$46.21	101.781	13' 4"	49' 8"	1	Opn	Odd		Rect
B	H10 between 6.9 & 9	75 LinFt	\$26.30	\$34.12	75.139	19' 0"	18' 4"	1	Opn	Odd		Rect
B	East Wall Vest B123 with Insul	22 LinFt	\$7.55	\$9.80	21.580	13' 4"	12' 8"	1	Opn	Odd		Rect
B	E6 between 12???????????	166 LinFt	\$58.15	\$75.44	166.139	28' 8"	39' 0"	1	Opn	Odd		Rect
A	(12 CMU) So Gym A108 "no" SGT	659 LinFt	\$230.48	\$298.99	658.500	33' 8"	99' 4"	1	Opn	Odd		Rect
A	(12 CMU) No Gym A108 "no" SGT	653 LinFt	\$228.38	\$296.27	652.500	33' 8"	98' 4"	1	Opn	Odd		Rect
A	(12 CMU) Gym A108 SGT	825 LinFt	\$288.75	\$374.59	825.000	33' 8"	125' 0"	1	Opn	Odd		Rect
Material [#5BB REBA] Totals		16,848 LinFt	\$5,896.90	\$7,649.96	16,848.282	Mat. Lay Rate	1,700.0 LinFt/Day					

#6	#6 Rebar / Give Vert. Ht	Lay	1,500.0 LinFt/Day	\$0.440/ LinFt	LinFt	Show as LinFt						
CA#1 Alt#1	42-8 N & S Full Brick	427 LinFt	\$187.73	\$219.56	426.667	42' 8"	36' 0"	1	Opn	Odd	Adj	Rect
C	42-8 N & S Full Brick	427 LinFt	\$187.73	\$219.56	426.667	42' 8"	36' 0"	1	Opn	Odd		Rect
C	Col 23 F.5 to N 3 story Classr	560 LinFt	\$246.40	\$288.17	560.000	40' 0"	290' 2"	1	Opn	Odd		Rect
B	8" CMU Corr with SGT base	53 LinFt	\$23.47	\$27.44	53.333	13' 4"	497' 4"	1	Opn	Odd		Rect
B	E6 between 12.3 & 17 South Wal	260 LinFt	\$114.40	\$133.79	260.000	26' 0"	94' 0"	1	Opn	Odd		Rect
B	Alt#2 (part out)22-8 N Band Rm	45 LinFt	\$19.95	\$23.33	45.333	22' 8"	82' 4"	1	Opn	Odd		Rect
A	18" Ext @ Cafetorium	405 LinFt	\$178.35	\$208.58	405.333	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
B	H7 between 6 & 6.8 N Ext Wall	64 LinFt	\$28.16	\$32.93	64.000	16' 0"	50' 8"	1	Opn	Odd		Rect
B	East Wall Vest B123 NO Insul	53 LinFt	\$23.47	\$27.44	53.333	13' 4"	26' 8"	1	Opn	Odd		Rect
B	N Wall Confere B138 with Insul	80 LinFt	\$35.20	\$41.17	80.000	13' 4"	49' 8"	1	Opn	Odd		Rect
B	East Wall Vest B123 with Insul	27 LinFt	\$11.73	\$13.72	26.667	13' 4"	12' 8"	1	Opn	Odd		Rect
Material [#6] Totals		2,401 LinFt	\$1,056.59	\$1,235.70	2,401.333	Mat. Lay Rate	1,500.0 LinFt/Day					
Class Totals Rebar		19,756 LinFt	\$7,130.70	\$9,115.57	19,755.949	Avg. Lay Rate	1,672.9 LinFt/Day					

Classification **SB**

ACOUSTA-WAL # IIIRF

12ACOUST	12" Sound Block	Lay	90.0 Pieces/Day	\$3.750/ Piece	SqFt	3.00% waste	1.125	Pieces per SqFt				
A	18" Ext @ Cafetorium	160 Pieces	\$599.65	\$1,331.50	138.000	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
A	(12 CMU) Projection RM Radi	304 Pieces	\$1,138.47	\$2,527.92	262.000	24' 10"	50' 4"	1	Opn	Odd	Adj	Rect
A	(12 CMU) So Gym A108 "no" SGT	826 Pieces	\$3,097.72	\$6,878.35	712.889	33' 8"	99' 4"	1	Opn	Odd		Rect
A	(12 CMU) No Gym A108 "no" SGT	826 Pieces	\$3,097.72	\$6,878.35	712.889	33' 8"	98' 4"	1	Opn	Odd		Rect
A	(12 CMU) Gym A108 SGT	422 Pieces	\$1,583.62	\$3,516.37	364.444	33' 8"	125' 0"	1	Opn	Odd		Rect
Material [12ACOUST] Totals		2,538 Pieces	\$9,517.20	\$21,132.50	2,190.222	Mat. Lay Rate	90.0 Pieces/Day					

8ACOUST	8" Sound Block	Lay	100.0 Pieces/Day	\$3.500/ Piece	SqFt	3.00% waste	1.125	Pieces per SqFt				
B	North wall of Cafetorium	160 Pieces	\$559.68	\$1,198.35	138.000	26' 0"	79' 4"	1	Opn	Odd	Adj	Rect
Class Totals ACOUSTA-WAL # IIIRF		2,698 Pieces	\$10,076.88	\$22,330.85	2,328.222	Avg. Lay Rate	90.5 Pieces/Day					

Classification **SGT**

Stru.Glaze Tile

12X12	12 x 12 Glazed Brick Acce	Lay	70.0 Pieces/Day	\$10.000/ Piece	SqFt	1 Piece = 1 SqFt						
A	Ext Col A	4 Pieces	\$40.00	\$44.11	4.000	16' 8"	279' 3"	1	Opn	Odd		Rect
CA#1 Alt#1	42-8 N & S Full Brick	6 Pieces	\$60.00	\$66.16	6.000	42' 8"	36' 0"	1	Opn	Odd	Adj	Rect

Sample Reports
Quantity/Bid Price Report

SGT Continued

Wall

						Height	Length	Qty	Opn	Odd	Adj	Shape
Quantity	Extended Mat. Cost	Lay-Cost	Amount									
C 42-8 N & S Full Brick	6 Pieces	\$60.00	\$66.16	6.000	42' 8"	36' 0"	1	Opn	Odd			Rect
CA#1 Alt#1 North Brick&CMU	2 Pieces	\$20.00	\$22.05	2.000	40' 0"	57' 0"	1	Opn	Odd			Rect
B Alt#2 (part out)33-8 N Band Rm	1 Piece	\$10.00	\$11.03	1.000	33' 8"	54' 3"	1	Opn	Odd			Rect
B Alt#2 (part out)22-8 N Band Rm	3 Pieces	\$30.00	\$33.08	3.000	22' 8"	82' 4"	1	Opn	Odd			Rect
A 18" Ext @ Cafetorium	2 Pieces	\$20.00	\$22.05	2.000	22' 8"	114' 0"	1	Opn	Odd	Adj		Rect
B N Wall Top of Main ent.	8 Pieces	\$80.00	\$88.22	8.000	22' 8"	69' 8"	1	Opn	Odd			Rect
B N Wall Top of Main ent.	12 Pieces	\$120.00	\$132.32	12.000	18' 8"	55' 4"	1	Opn	Odd			Rect
B H10 between 6.9 & 9	1 Piece	\$10.00	\$11.03	1.000	19' 0"	18' 4"	1	Opn	Odd			Rect
B E6 between 12????????	2 Pieces	\$20.00	\$22.05	2.000	28' 8"	39' 0"	1	Opn	Odd			Rect
Material [12X12] Totals	47 Pieces	\$470.00	\$518.27	47.000	Mat. Lay Rate	70.0 Pieces/Day						
6T4"	4x5x12 SGT Reg	Lay	80.0 Pieces/Day	\$4.500/ Piece	SqFt	2.00% waste	2.250	Pieces per SqFt				
CA#1 A#1 Copy Locker Base SGT 3rd	0 Pieces	\$0.00	\$0.00	0.000	0' 5"	7' 4"	1					Rect
CA#1 A#1 Copy Locker Base SGT	0 Pieces	\$0.00	\$0.00	0.000	0' 5"	7' 4"	1					Rect
C3 4 Copy Locker Base SGT 1st FI	0 Pieces	\$0.00	\$0.00	0.000	0' 5"	7' 4"	1					Rect
C2 4 Copy Locker Base SGT 1st FI	0 Pieces	\$0.00	\$0.00	0.000	0' 5"	7' 4"	1					Rect
C1 2 Locker Base SGT 1st FI	235 Pieces	\$1,057.23	\$2,222.39	102.364	0' 5"	242' 4"	1					Rect
C3 2 Locker Base SGT 1st FI	215 Pieces	\$966.96	\$2,032.63	93.624	0' 5"	222' 8"	1					Rect
C2 2 Locker Base SGT 1st FI	215 Pieces	\$966.96	\$2,032.63	93.624	0' 5"	222' 8"	1					Rect
A Locker Base SGT	238 Pieces	\$1,072.53	\$2,254.55	103.845	0' 5"	245' 0"	1					Rect
A N Wall (12 CMU) Serving #119	12 Pieces	\$55.05	\$115.72	5.330	22' 8"	45' 0"	1	Opn	Odd			Rect
Material [6T4"] Totals	915 Pieces	\$4,118.73	\$8,657.91	398.787	Mat. Lay Rate	80.0 Pieces/Day						
6T4"8X8SC	4x5x12 SGT 8x8 Score	Lay	75.0 Pieces/Day	\$7.400/ Piece	SqFt	2.00% waste	1.125	Pieces per SqFt				
A (8 CMU) Corr A106 SGT	11 Pieces	\$83.03	\$113.21	9.778	21' 4"	22' 4"	1	Opn	Odd	Adj		Rect
B North wall of Cafetorium SGT	7 Pieces	\$50.95	\$69.47	6.000	26' 0"	22' 0"	1	Opn	Odd			Rect
A (8 CMU) Corr A104 SGT	13 Pieces	\$95.21	\$129.82	11.212	15' 4"	29' 4"	1	Opn	Odd			Rect
A#3C Alt3 out (8 CMU) Corr A104 SGT	11 Pieces	\$84.92	\$115.78	10.000	15' 4"	35' 0"	1	Opn	Odd			Rect
A (12 CMU) Gym A108 SGT	73 Pieces	\$541.57	\$738.44	63.778	33' 8"	125' 0"	1	Opn	Odd			Rect
A (12 CMU) Corr A106 SGT	75 Pieces	\$556.60	\$758.93	65.548	21' 4"	104' 8"	1	Opn	Odd			Rect
Material [6T4"8X8SC] Totals	191 Pieces	\$1,412.27	\$1,925.65	166.316	Mat. Lay Rate	75.0 Pieces/Day						
6T4"B	4x5x12 SGT Bullnose	Lay	80.0 Pieces/Day	\$18.000/ Piece	SqFt	1.00% waste	2.251	Pieces per SqFt				
CA#1 A#1 Copy Locker Base SGT 3rd	12 Pieces	\$218.28	\$115.85	5.333	0' 5"	7' 4"	1					Rect
A (8 CMU) Corr A106 SGT	9 Pieces	\$163.72	\$86.89	4.000	21' 4"	22' 4"	1	Opn	Odd	Adj		Rect
B North wall of Cafetorium SGT	2 Pieces	\$27.29	\$14.48	0.667	26' 0"	22' 0"	1	Opn	Odd			Rect
CA#1 A#1 Copy Locker Base SGT	12 Pieces	\$218.28	\$115.85	5.333	0' 5"	7' 4"	1					Rect
C3 4 Copy Locker Base SGT 1st FI	12 Pieces	\$218.28	\$115.85	5.333	0' 5"	7' 4"	1					Rect
C2 4 Copy Locker Base SGT 1st FI	12 Pieces	\$218.28	\$115.85	5.333	0' 5"	7' 4"	1					Rect
CA#1 Alt#1 Locker Base SGT 1st FI	12 Pieces	\$218.28	\$115.85	5.333	0' 5"	4' 4"	1					Rect
C1 2 Locker Base SGT 1st FI	12 Pieces	\$218.28	\$115.85	5.333	0' 5"	242' 4"	1					Rect
C3 2 Locker Base SGT 1st FI	12 Pieces	\$218.28	\$115.85	5.333	0' 5"	222' 8"	1					Rect
C2 2 Locker Base SGT 1st FI	12 Pieces	\$218.28	\$115.85	5.333	0' 5"	222' 8"	1					Rect
A Locker Base SGT	12 Pieces	\$218.28	\$115.85	5.333	0' 5"	245' 0"	1					Rect
A N Wall (12 CMU) Serving #119	2 Pieces	\$36.36	\$19.30	0.888	22' 8"	45' 0"	1	Opn	Odd			Rect
A (8 CMU) Corr A104 SGT	8 Pieces	\$136.44	\$72.41	3.333	15' 4"	29' 4"	1	Opn	Odd			Rect
A#3C Alt3 out (8 CMU) Corr A104 SGT	11 Pieces	\$191.01	\$101.37	4.667	15' 4"	35' 0"	1	Opn	Odd			Rect
A (12 CMU) Gym A108 SGT	6 Pieces	\$109.15	\$57.93	2.667	33' 8"	125' 0"	1	Opn	Odd			Rect
A (12 CMU) Corr A106 SGT	8 Pieces	\$136.44	\$72.41	3.333	21' 4"	104' 8"	1	Opn	Odd			Rect
Material [6T4"B] Totals	154 Pieces	\$2,764.94	\$1,467.42	67.552	Mat. Lay Rate	80.0 Pieces/Day						

Wall

SGT Continued

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
8T4"8X8H 4x8x8 SGT Bullnose		Lay	100.0 Pieces/Day	\$14.000/ Piece	SqFt	2.250	Pieces per SqFt					
CA#1	2Copy Stair C133 SGT	22	Pieces \$308.00	\$169.81	9.778	13' 4"	13' 4"	1		Odd	Adj	Rect
CA#1	3rdStair C133 SGT	22	Pieces \$308.00	\$169.81	9.778	13' 4"	13' 4"	1		Odd	Adj	Rect
C3	3 Copy 5 8" CMU Corr 2side SGT	2	Pieces \$28.00	\$15.44	0.889	13' 4"	8' 0"	1	Opn	Odd		Rect
CA#1	3rd FI 8" CMU Corr 2side SGT	2	Pieces \$28.00	\$15.44	0.889	13' 4"	8' 0"	1	Opn	Odd		Rect
CA#1	Copy 5 8" CMU Corr 2side SGT	2	Pieces \$28.00	\$15.44	0.889	13' 4"	8' 0"	1	Opn	Odd		Rect
C3	2Copy Stair C100 SGT	22	Pieces \$308.00	\$169.81	9.778	13' 4"	23' 0"	1		Odd		Rect
C2	3 Copy 5 8" CMU Corr 2side SGT	2	Pieces \$28.00	\$15.44	0.889	13' 4"	8' 0"	1	Opn	Odd		Rect
C2	2Copy Stair C100 SGT	22	Pieces \$308.00	\$169.81	9.778	13' 4"	23' 0"	1		Odd		Rect
CA#1	Alt#1 C133 Stair	24	Pieces \$336.00	\$185.25	10.667	13' 4"	41' 4"	1	Opn	Odd		Rect
C1	Stair C100 SGT	24	Pieces \$336.00	\$185.25	10.667	13' 4"	41' 8"	1	Opn	Odd		Rect
C1	3 8"CMU Corr SGT13-0 FireS	44	Pieces \$616.00	\$339.63	19.556	13' 0"	264' 8"	1	Opn	Odd		Rect
C3	5 8" CMU Corr 2side SGT	2	Pieces \$28.00	\$15.44	0.889	13' 0"	13' 0"	1	Opn	Odd		Rect
C3	3 8"CMU Corr SGT13-0 FireS	44	Pieces \$616.00	\$339.63	19.556	13' 0"	264' 8"	1	Opn	Odd		Rect
C2	3 8"CMU Corr SGT13-0 FireS	44	Pieces \$616.00	\$339.63	19.556	13' 0"	264' 8"	1	Opn	Odd		Rect
C2	5 8" CMU Corr 2side SGT	2	Pieces \$28.00	\$15.44	0.889	13' 0"	13' 0"	1	Opn	Odd		Rect
C2	3 8"CMU Corr SGT13-0 FireS	44	Pieces \$616.00	\$339.63	19.556	13' 0"	264' 8"	1	Opn	Odd		Rect
C1	5 8" CMU Corr 2side SGT	2	Pieces \$28.00	\$15.44	0.889	13' 0"	13' 0"	1	Opn	Odd		Rect
B	8" CMU Corr with SGT base	64	Pieces \$896.00	\$494.01	28.444	13' 4"	497' 4"	1	Opn	Odd		Rect
B2	8" CMU Corr with SGT base2nd F	31	Pieces \$434.00	\$239.28	13.778	12' 0"	242' 0"	1	Opn	Odd		Rect
B2	8" CMU CorSGTnoBB 12-8	12	Pieces \$168.00	\$92.63	5.333	12' 8"	154' 4"	1	Opn	Odd		Rect
B	8"CMU Corr SGT13-0 FireS	6	Pieces \$84.00	\$46.31	2.667	13' 0"	83' 7"	1	Opn	Odd		Rect
B	8" CMU Corr 2side SGT	6	Pieces \$84.00	\$46.31	2.667	13' 0"	33' 4"	1	Opn	Odd		Rect
Material [8T4"8X8H] Totals		445	Pieces \$6,230.00	\$3,434.89	197.778	Mat. Lay Rate	100.0	Pieces/Day				
8T4"8X8SC 4x 8x8 SGT Reg		Lay	100.0 Pieces/Day	\$4.500/ Piece	SqFt	2.00% waste	2.250	Pieces per SqFt				
CA#1	2Copy Stair C133 SGT	8	Pieces \$37.11	\$62.41	3.594	13' 4"	13' 4"	1		Odd	Adj	Rect
CA#1	3rdStair C133 SGT	8	Pieces \$37.11	\$62.41	3.594	13' 4"	13' 4"	1		Odd	Adj	Rect
C3	3 Copy 5 8" CMU Corr 2side SGT	1	Piece \$4.59	\$7.72	0.445	13' 4"	8' 0"	1	Opn	Odd		Rect
CA#1	3rd FI 8" CMU Corr 2side SGT	1	Piece \$4.59	\$7.72	0.445	13' 4"	8' 0"	1	Opn	Odd		Rect
CA#1	Copy 5 8" CMU Corr 2side SGT	1	Piece \$4.59	\$7.72	0.445	13' 4"	8' 0"	1	Opn	Odd		Rect
C3	2Copy Stair C100 SGT	13	Pieces \$57.38	\$96.49	5.556	13' 4"	23' 0"	1		Odd		Rect
C2	3 Copy 5 8" CMU Corr 2side SGT	1	Piece \$4.59	\$7.72	0.445	13' 4"	8' 0"	1	Opn	Odd		Rect
C2	2Copy Stair C100 SGT	13	Pieces \$57.38	\$96.49	5.556	13' 4"	23' 0"	1		Odd		Rect
CA#1	Alt#1 C133 Stair	30	Pieces \$133.11	\$223.85	12.889	13' 4"	41' 4"	1	Opn	Odd		Rect
C1	Stair C100 SGT	31	Pieces \$140.00	\$235.43	13.556	13' 4"	41' 8"	1	Opn	Odd		Rect
C1	3 8"CMU Corr SGT13-0 FireS	309	Pieces \$1,389.59	\$2,336.82	134.552	13' 0"	264' 8"	1	Opn	Odd		Rect
C3	5 8" CMU Corr 2side SGT	11	Pieces \$50.49	\$84.91	4.889	13' 0"	13' 0"	1	Opn	Odd		Rect
C3	3 8"CMU Corr SGT13-0 FireS	309	Pieces \$1,389.59	\$2,336.82	134.552	13' 0"	264' 8"	1	Opn	Odd		Rect
C2	3 8"CMU Corr SGT13-0 FireS	309	Pieces \$1,389.59	\$2,336.82	134.552	13' 0"	264' 8"	1	Opn	Odd		Rect
C2	5 8" CMU Corr 2side SGT	11	Pieces \$50.49	\$84.91	4.889	13' 0"	13' 0"	1	Opn	Odd		Rect
C2	3 8"CMU Corr SGT13-0 FireS	309	Pieces \$1,389.59	\$2,336.82	134.552	13' 0"	264' 8"	1	Opn	Odd		Rect
C1	5 8" CMU Corr 2side SGT	11	Pieces \$50.49	\$84.91	4.889	13' 0"	13' 0"	1	Opn	Odd		Rect
B	8" CMU Corr with SGT base	572	Pieces \$2,574.91	\$4,330.15	249.326	13' 4"	497' 4"	1	Opn	Odd		Rect
B2	8" CMU Corr with SGT base2nd F	276	Pieces \$1,239.77	\$2,084.89	120.046	12' 0"	242' 0"	1	Opn	Odd		Rect
B2	8" CMU CorSGTnoBB 2nd F	60	Pieces \$270.81	\$455.41	26.222	12' 0"	39' 4"	1	Opn	Odd		Rect
B2	8" CMU CorSGTnoBB 12-8	190	Pieces \$855.46	\$1,438.60	82.833	12' 8"	154' 4"	1	Opn	Odd		Rect
B2	8" CMU CorSGTnoBB12-8"	15	Pieces \$68.85	\$115.78	6.667	12' 8"	10' 0"	1		Odd		Rect
B	8"CMU Corr SGT13-0 FireS	91	Pieces \$410.09	\$689.63	39.709	13' 0"	83' 7"	1	Opn	Odd		Rect
B	8" CMU Corr SGT base DisplayCa	90	Pieces \$406.22	\$683.12	39.333	13' 4"	59' 0"	1	Opn	Odd		Rect
B	8" CMU Corr 2side SGT	13	Pieces \$59.67	\$100.35	5.778	13' 0"	33' 4"	1	Opn	Odd		Rect

SGT Continued

Wall

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
B	West Wall Vest B123 NO Insul	40 Pieces	\$179.01	\$301.04	17.333	28' 8"	26' 0"	1	Opn	Odd		Rect
B	East Wall Vest B123 NO Insul	35 Pieces	\$158.36	\$266.30	15.333	13' 4"	26' 8"	1	Opn	Odd		Rect
Material [8T4"8X8SC] Totals		2,759 Pieces	\$12,413.42	\$20,875.23	1,201.977	Mat. Lay Rate	100.0	Pieces/Day				
8X8	8 x 8 Glazed Brick Acce	Lay 110.0 Pieces/Day	\$4.500/ Piece		SqFt	2.00% waste	2.250	Pieces per SqFt				
A	Ext Col A	4 Pieces	\$18.36	\$28.07	1.778	16' 8"	279' 3"	1	Opn	Odd		Rect
CA#1	Alt#1 42-8 N & S Full Brick	6 Pieces	\$27.54	\$42.10	2.667	42' 8"	36' 0"	1	Opn	Odd	Adj	Rect
C	42-8 N & S Full Brick	6 Pieces	\$27.54	\$42.10	2.667	42' 8"	36' 0"	1	Opn	Odd		Rect
B	Alt#2 (part out)33-8 N Band Rm	2 Pieces	\$9.18	\$14.03	0.889	33' 8"	54' 3"	1	Opn	Odd		Rect
B	Alt#2 (part out)22-8 N Band Rm	6 Pieces	\$27.54	\$42.10	2.667	22' 8"	82' 4"	1	Opn	Odd		Rect
B	H10 between 6.9 & 9	1 Piece	\$4.59	\$7.02	0.444	19' 0"	18' 4"	1	Opn	Odd		Rect
B	E6 between 12???????????	1 Piece	\$4.59	\$7.02	0.444	28' 8"	39' 0"	1	Opn	Odd		Rect
Material [8X8] Totals		27 Pieces	\$119.34	\$182.45	11.556	Mat. Lay Rate	110.0	Pieces/Day				
Class Totals Stru.Glaze Tile		4,537 Pieces	\$27,528.70	\$37,061.81	2,090.965	Avg. Lay Rate	92.9	Pieces/Day				

Classification **SPL**

Splitface CMU

		Lay	140.0 Pieces/Day	\$2.250/ Piece		SqFt	3.00% waste	1.125	Pieces per SqFt			
SF04BLK	4" Splitface Black	Lay 140.0 Pieces/Day	\$2.250/ Piece		SqFt	3.00% waste	1.125	Pieces per SqFt				
CA#1	Alt#1 North Brick&CMU	174 Pieces	\$391.66	\$931.78	150.222	40' 0"	57' 0"	1	Opn	Odd		Rect
C	Col 23 F.5 to N 3 story Classr	834 Pieces	\$1,876.02	\$4,463.15	719.556	40' 0"	290' 2"	1	Opn	Odd		Rect
B	E6 between 12.3 & 17 South Wal	275 Pieces	\$618.77	\$1,472.09	237.333	26' 0"	94' 0"	1	Opn	Odd		Rect
A	18" Ext @ Cafetorium	340 Pieces	\$764.19	\$1,818.06	293.110	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
B	H7 between 6 & 6.8 N Ext Wall	136 Pieces	\$307.07	\$730.53	117.778	16' 0"	50' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 with Insul	30 Pieces	\$67.21	\$159.89	25.778	28' 8"	9' 8"	1	Opn	Odd		Rect
B	West Wall Vest B123 NO Insul	60 Pieces	\$135.57	\$322.54	52.000	28' 8"	26' 0"	1	Opn	Odd		Rect
B	East Wall Vest B123 NO Insul	53 Pieces	\$119.93	\$285.32	46.000	13' 4"	26' 8"	1	Opn	Odd		Rect
B	Piers @ Ent B123 Arch	31 Pieces	\$69.52	\$165.40	26.667	9' 8"	6' 4"	2		Odd		Pier
B	N Wall Top of Main ent.	1,486 Pieces	\$3,343.40	\$7,954.14	1,282.378	22' 8"	69' 8"	1	Opn	Odd		Rect
B	N Wall Office B13 & 140	254 Pieces	\$572.42	\$1,361.83	219.556	13' 4"	24' 0"	1	Opn	Odd		Rect
B	N Wall Confere B138 with Insul	152 Pieces	\$341.41	\$812.23	130.950	13' 4"	49' 8"	1	Opn	Odd		Rect
B	N Main Ent Splitface Piers	252 Pieces	\$567.80	\$1,350.82	217.781	10' 0"	25' 9"	1				Rect
B	Face of Pier veneer	24 Pieces	\$54.79	\$130.34	21.014	9' 8"	9' 4"	1		Odd		Rect
B	East Wall Vest B123 with Insul	38 Pieces	\$85.58	\$203.60	32.825	13' 4"	12' 8"	1	Opn	Odd		Rect
B	E6 between 12???????????	120 Pieces	\$268.99	\$639.93	103.171	28' 8"	39' 0"	1	Opn	Odd		Rect
B	E&W Walls Office B136 & 140	283 Pieces	\$637.37	\$1,516.34	244.467	10' 0"	25' 1"	1				Rect
B	2x1-2 Pier @ 6.8 & 8	16 Pieces	\$37.08	\$88.22	14.222	9' 8"	4' 0"	2		Odd		Pier
B	2x1-2 Pier @ 6.8 & 8	31 Pieces	\$69.52	\$165.40	26.667	9' 8"	6' 4"	2		Odd		Pier
Material [SF04BLK] Totals		4,590 Pieces	\$10,328.30	\$24,571.62	3,961.473	Mat. Lay Rate	140.0	Pieces/Day				
SF08BLK	8" Splitface Black	Lay 135.0 Pieces/Day	\$2.500/ Piece		SqFt	3.00% waste	1.125	Pieces per SqFt				
B	(8 CMU) Splitface Top Radius	129 Pieces	\$321.69	\$714.30	111.047	6' 0"	41' 4"	1	Opn			Rect
B	Below barrel parapet	383 Pieces	\$957.90	\$2,126.97	330.667	10' 8"	41' 4"	1		Odd		Rect
Material [SF08BLK] Totals		512 Pieces	\$1,279.59	\$2,841.27	441.714	Mat. Lay Rate	135.0	Pieces/Day				
Class Totals Splitface CMU		5,102 Pieces	\$11,607.89	\$27,412.89	4,403.187	Avg. Lay Rate	139.5	Pieces/Day				

Wall

Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
----------	--------------------	----------	--------	--------	--------	-----	-----	-----	-----	-------

Classification **WEL**

Cotten Weep Rop

WEPECOTT	Cotton Weep Rope	Lay	3,000.0 LinFt/Day	\$0.040/ LinFt	LinFt	LinFt	Show as LinFt					
A	Ext Col A	135	LinFt	\$5.39	\$34.69	134.833	16' 8"	279' 3"	1	Opn	Odd	Rect
CA#1	Alt#1 42-8 N & S Full Brick	62	LinFt	\$2.48	\$15.94	61.958	42' 8"	36' 0"	1	Opn	Odd Adj	Rect
A	West wall Gym	45	LinFt	\$1.81	\$11.66	45.333	33' 8"	89' 8"	1	Opn	Odd	Rect
C	42-8 N & S Full Brick	56	LinFt	\$2.23	\$14.31	55.625	42' 8"	36' 0"	1	Opn	Odd	Rect
CA#1	Alt#1 North Brick&CMU	28	LinFt	\$1.12	\$7.20	28.000	40' 0"	57' 0"	1	Opn	Odd	Rect
C	Col 23 F.5 to N 3 story Classr	639	LinFt	\$25.55	\$164.33	638.667	40' 0"	290' 2"	1	Opn	Odd	Rect
CA#1	Alt#1 Cor Ent ReturnsCol E.5	3	LinFt	\$0.12	\$0.77	3.000	8' 8"	6' 8"	1		Odd	Rect
C	Cor Ent ReturnsCol E.5	3	LinFt	\$0.12	\$0.77	3.000	8' 8"	6' 8"	1		Odd	Rect
C	Col 17 between E.5 & H.9	48	LinFt	\$1.91	\$12.26	47.667	40' 0"	85' 7"	1	Opn	Odd	Rect
B	Alcove B127a N Band Rm	43	LinFt	\$1.71	\$10.99	42.708	19' 8"	58' 4"	1	Opn	Odd	Rect
B	N Mech Rm 33-8	65	LinFt	\$2.60	\$16.72	65.000	20' 4"	149' 8"	1	Opn	Odd	Rect
B	Alt#2 (part out)33-8 N Band Rm	22	LinFt	\$0.88	\$5.66	22.000	33' 8"	54' 3"	1	Opn	Odd	Rect
B	E6 between 12.3 & 17 South Wal	128	LinFt	\$5.11	\$32.85	127.667	26' 0"	94' 0"	1	Opn	Odd	Rect
B	W Wall (12 CMU) Band B127	20	LinFt	\$0.80	\$5.15	20.000	20' 0"	57' 0"	1	Opn	Odd	Rect
B2	(12 CMU) IDF D226	6	LinFt	\$0.24	\$1.54	6.000	15' 0"	12' 0"	1		Odd	Rect
B	Alcove B127a N Band Rm @26-0	20	LinFt	\$0.80	\$5.15	20.000	10' 8"	41' 4"	1		Odd	Rect
B	Alt2(out)Cor Ent ReturnsCol #3	3	LinFt	\$0.12	\$0.77	3.000	8' 8"	6' 4"	1		Odd	Rect
B	Alt#2 (part out)22-8 N Band Rm	46	LinFt	\$1.84	\$11.84	46.000	22' 8"	82' 4"	1	Opn	Odd	Rect
A	Corr Ent Returns	3	LinFt	\$0.12	\$0.77	3.000	8' 8"	6' 8"	1		Odd	Rect
B	E Wall (12 CMU) Band B127	17	LinFt	\$0.68	\$4.37	17.000	22' 8"	35' 0"	1		Odd	Rect
A	N Wall (12 CMU) Serving #119	12	LinFt	\$0.48	\$3.09	12.000	22' 8"	45' 0"	1	Opn	Odd	Rect
A	18" Ext @ Cafetorium	100	LinFt	\$4.00	\$25.73	100.000	22' 8"	114' 0"	1	Opn	Odd Adj	Rect
A	Alt2 12CMU Col 4.3 @ C&D (Out)	24	LinFt	\$0.96	\$6.18	24.000	33' 8"	48' 0"	1	Opn	Odd	Rect
B	H7 between 6 & 6.8 N Ext Wall	58	LinFt	\$2.32	\$14.92	58.000	16' 0"	50' 8"	1	Opn	Odd	Rect
B	West Wall Vest B123 with Insul	9	LinFt	\$0.36	\$2.32	9.000	28' 8"	9' 8"	1	Opn	Odd	Rect
A	(12 CMU) Projection RM Radi	17	LinFt	\$0.68	\$4.37	17.000	24' 10"	50' 4"	1	Opn	Odd Adj	Rect
B	West Wall Vest B123 NO Insul	23	LinFt	\$0.92	\$5.92	23.000	28' 8"	26' 0"	1	Opn	Odd	Rect
B	N Wall Top of Main ent.	83	LinFt	\$3.33	\$21.44	83.333	22' 8"	69' 8"	1	Opn	Odd	Rect
B	N Wall Top of Main ent.	74	LinFt	\$2.96	\$19.04	74.000	18' 8"	55' 4"	1	Opn	Odd	Rect
B	N Wall Office B13 & 140	29	LinFt	\$1.15	\$7.38	28.667	13' 4"	24' 0"	1	Opn	Odd	Rect
B	N Wall Confere B138 with Insul	59	LinFt	\$2.36	\$15.18	59.000	13' 4"	49' 8"	1	Opn	Odd	Rect
B	H10 between 6.9 & 9	10	LinFt	\$0.41	\$2.66	10.333	19' 0"	18' 4"	1	Opn	Odd	Rect
B	East Wall Vest B123 with Insul	11	LinFt	\$0.44	\$2.83	11.000	13' 4"	12' 8"	1	Opn	Odd	Rect
B	E6 between 12???????????	69	LinFt	\$2.76	\$17.75	69.000	28' 8"	39' 0"	1	Opn	Odd	Rect
B	E&W Walls Office B136 & 140	12	LinFt	\$0.48	\$3.09	12.000	10' 0"	25' 1"	1			Rect
B	Below barrel parapet	20	LinFt	\$0.80	\$5.15	20.000	10' 8"	41' 4"	1		Odd	Rect
A	(12 CMU) So Gym A108 "no" SGT	46	LinFt	\$1.84	\$11.84	46.000	33' 8"	99' 4"	1	Opn	Odd	Rect
A	(12 CMU) No Gym A108 "no" SGT	44	LinFt	\$1.76	\$11.32	44.000	33' 8"	98' 4"	1	Opn	Odd	Rect
Material [WEPECOTT] Totals		2,091	LinFt	\$83.63	\$537.95	2,090.792	Mat. Lay Rate	3,000.0	LinFt/Day			

Classification **WIR**

Wire

HDL9GA08"	Hot-Dipp./Ladder 9ga-- 8"	Lay	0.0 LinFt/Day	\$0.150/ LinFt	LinFt	LinFt	Show as LinFt					
B	(8 CMU) Splitface Top Radius	181	LinFt	\$27.20	\$0.00	181.333	6' 0"	41' 4"	1	Opn		Rect
B	North wall of Cafetorium SGT	96	LinFt	\$14.40	\$0.00	96.000	26' 0"	22' 0"	1	Opn	Odd	Rect
A	West wall Gym	197	LinFt	\$29.60	\$0.00	197.333	33' 8"	89' 8"	1	Opn	Odd	Rect
B	8 CMU Top Radius@ Band	181	LinFt	\$27.18	\$0.00	181.184	6' 0"	41' 4"	1	Opn		Rect
CA#1	Alt#1 North Brick&CMU	1,134	LinFt	\$170.10	\$0.00	1,134.000	40' 0"	57' 0"	1	Opn	Odd	Rect

Sample Reports
Quantity/Bid Price Report

WIR Continued

Wall

						Height	Length	Qty	Opn	Odd	Adj	Shape
Quantity	Extended	Lay-Cost	Amount									
Mat. Cost												
C Col 23 F.5 to N 3 story Classr	5,799 LinFt	\$869.85	\$0.00	5,799.000	40' 0"	290' 2"	1	Opn	Odd			Rect
B 8" CMUf @ roof Col 10.1&10.9	892 LinFt	\$133.75	\$0.00	891.667	7' 4"	161' 4"	1		Odd			Rect
B 8" CMU Fill in @ roof	5 LinFt	\$0.75	\$0.00	5.000	4' 8"	1' 8"	1		Odd			Rect
B N Wall Top of Main ent.	897 LinFt	\$134.48	\$0.00	896.541	22' 8"	69' 8"	1	Opn	Odd			Rect
B Below barrel parapet	181 LinFt	\$27.20	\$0.00	181.333	10' 8"	41' 4"	1		Odd			Rect
A (8 CMU) Top Radius	166 LinFt	\$24.90	\$0.00	166.000	5' 1"	50' 4"	1	Opn				Rect
Material [HDL9GA08"] Totals	9,729 LinFt	\$1,459.41	\$0.00	9,729.392	Mat. Lay Rate	0.0 LinFt/Day						

HDL9GA10" Hot-Dipp./Ladder 9ga--10"												
Lay	0.0	LinFt/Day	\$0.180/ LinFt	LinFt	Show as LinFt							
A Ext Col A	618	LinFt	\$111.32	\$0.00	618.451	16' 8"	279' 3"	1	Opn	Odd		Rect
CA#1 Alt#1 Returns 1-2" E.5	5	LinFt	\$0.84	\$0.00	4.667	8' 8"	1' 2"	2		Odd		Gable
CA#1 Alt#1 Cor Ent ReturnsCol E.5	13	LinFt	\$2.40	\$0.00	13.333	8' 8"	6' 8"	1		Odd		Rect
C Cor Ent ReturnsCol E.5	13	LinFt	\$2.40	\$0.00	13.333	8' 8"	6' 8"	1		Odd		Rect
C Returns 1-2" E.5	5	LinFt	\$0.84	\$0.00	4.667	8' 8"	1' 2"	2		Odd		Gable
B Alt2(out)Cor Ent ReturnsCol #3	13	LinFt	\$2.28	\$0.00	12.667	8' 8"	6' 4"	1		Odd		Rect
B Alt2 (out) Returns 1-2" Col #3	5	LinFt	\$0.84	\$0.00	4.667	8' 8"	1' 2"	2		Odd		Gable
A Returns 1-2"	5	LinFt	\$0.84	\$0.00	4.667	8' 8"	1' 2"	2		Odd		Gable
A Corr Ent Returns	13	LinFt	\$2.40	\$0.00	13.333	8' 8"	6' 8"	1		Odd		Rect
Material [HDL9GA10"] Totals	690	LinFt	\$124.16	\$0.00	689.784	Mat. Lay Rate	0.0 LinFt/Day					

HDL9GA12" Hot-Dipp./Ladder 9ga--12"												
Lay	0.0	LinFt/Day	\$0.210/ LinFt	LinFt	Show as LinFt							
B E6 between 12.3 & 17 South Wal	520	LinFt	\$109.20	\$0.00	520.000	26' 0"	94' 0"	1	Opn	Odd		Rect
B W Wall (12 CMU) Band B127	315	LinFt	\$66.15	\$0.00	315.000	20' 0"	57' 0"	1	Opn	Odd		Rect
B2 (12 CMU) IDF D226	65	LinFt	\$13.65	\$0.00	65.000	15' 0"	12' 0"	1		Odd		Rect
B Alt#2 (part out)22-8 N Band Rm	457	LinFt	\$95.90	\$0.00	456.667	22' 8"	82' 4"	1	Opn	Odd		Rect
B E Wall (12 CMU) Band B127	190	LinFt	\$39.90	\$0.00	190.000	22' 8"	35' 0"	1		Odd		Rect
A N Wall (12 CMU) Serving #119	245	LinFt	\$51.45	\$0.00	245.000	22' 8"	45' 0"	1	Opn	Odd		Rect
A 18" Ext @ Cafetorium	630	LinFt	\$132.30	\$0.00	630.000	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect
A Alt2 12CMU Col 4.3 @ C&D (Out)	318	LinFt	\$66.78	\$0.00	318.000	33' 8"	48' 0"	1	Opn	Odd		Rect
B H7 between 6 & 6.8 N Ext Wall	278	LinFt	\$58.45	\$0.00	278.333	16' 0"	50' 8"	1	Opn	Odd		Rect
B West Wall Vest B123 with Insul	48	LinFt	\$10.15	\$0.00	48.333	28' 8"	9' 8"	1	Opn	Odd		Rect
A (12 CMU) Projection RM Radi	221	LinFt	\$46.48	\$0.00	221.333	24' 10"	50' 4"	1	Opn	Odd	Adj	Rect
B North wall of Cafetorium	437	LinFt	\$91.70	\$0.00	436.667	26' 0"	79' 4"	1	Opn	Odd	Adj	Rect
B West Wall Vest B123 NO Insul	140	LinFt	\$29.40	\$0.00	140.000	28' 8"	26' 0"	1	Opn	Odd		Rect
B East Wall Vest B123 NO Insul	143	LinFt	\$30.10	\$0.00	143.333	13' 4"	26' 8"	1	Opn	Odd		Rect
B N Wall Top of Main ent.	230	LinFt	\$48.31	\$0.00	230.043	22' 8"	69' 8"	1	Opn	Odd		Rect
B N Wall Top of Main ent.	123	LinFt	\$25.76	\$0.00	122.667	18' 8"	55' 4"	1	Opn	Odd		Rect
B N Wall Office B13 & 140	130	LinFt	\$27.30	\$0.00	130.000	13' 4"	24' 0"	1	Opn	Odd		Rect
B N Wall Confere B138 with Insul	273	LinFt	\$57.40	\$0.00	273.333	13' 4"	49' 8"	1	Opn	Odd		Rect
B H10 between 6.9 & 9	97	LinFt	\$20.30	\$0.00	96.667	19' 0"	18' 4"	1	Opn	Odd		Rect
B East Wall Vest B123 with Insul	68	LinFt	\$14.35	\$0.00	68.333	13' 4"	12' 8"	1	Opn	Odd		Rect
B E6 between 12???????????	215	LinFt	\$45.15	\$0.00	215.000	28' 8"	39' 0"	1	Opn	Odd		Rect
B E&W Walls Office B136 & 140	136	LinFt	\$28.46	\$0.00	135.519	10' 0"	25' 1"	1				Rect
B Below barrel parapet	136	LinFt	\$28.56	\$0.00	136.000	10' 8"	41' 4"	1		Odd		Rect
A (12 CMU) So Gym A108 "no" SGT	656	LinFt	\$137.76	\$0.00	656.000	33' 8"	99' 4"	1	Opn	Odd		Rect
A (12 CMU) No Gym A108 "no" SGT	650	LinFt	\$136.50	\$0.00	650.000	33' 8"	98' 4"	1	Opn	Odd		Rect
A (12 CMU) Gym A108 SGT	1,242	LinFt	\$260.82	\$0.00	1,242.000	33' 8"	125' 0"	1	Opn	Odd		Rect
Material [HDL9GA12"] Totals	7,963	LinFt	\$1,672.28	\$0.00	7,963.228	Mat. Lay Rate	0.0 LinFt/Day					

HDL9GA14" Hot-Dipp./Ladder 9ga--14"												
Lay	0.0	LinFt/Day	\$0.240/ LinFt	LinFt	Show as LinFt							
A Ext Col A	3,000	LinFt	\$719.96	\$0.00	2,999.820	16' 8"	279' 3"	1	Opn	Odd		Rect

Sample Reports
Quantity/Bid Price Report

WIR Continued

Wall

						Height	Length	Qty	Opn	Odd	Adj	Shape
Quantity	Extended	Lay-Cost	Amount									
Mat. Cost												
CA#1 Alt#1 42-8 N & S Full Brick	1,015 LinFt	\$243.55	\$0.00	1,014.811	42' 8"	36' 0"	1	Opn	Odd	Adj	Rect	
B Arch on Piers @ Ent for Mark?	36 LinFt	\$8.64	\$0.00	36.000	3' 0"	17' 0"	1	Opn			Rect	
B Arch on Piers @ Ent for Mark?	59 LinFt	\$14.15	\$0.00	58.945	4' 4"	20' 0"	1	Opn	Odd		Rect	
C 42-8 N & S Full Brick	1,021 LinFt	\$245.13	\$0.00	1,021.388	42' 8"	36' 0"	1	Opn	Odd		Rect	
CA#1 Alt#1 Cor Ent ReturnsCol E.5	27 LinFt	\$6.40	\$0.00	26.667	8' 8"	6' 8"	1		Odd		Rect	
C Cor Ent ReturnsCol E.5	27 LinFt	\$6.40	\$0.00	26.667	8' 8"	6' 8"	1		Odd		Rect	
C Col 17 between E.5 & H.9	2,644 LinFt	\$634.60	\$0.00	2,644.153	40' 0"	85' 7"	1	Opn	Odd		Rect	
B Alcove B127a N Band Rm	875 LinFt	\$210.08	\$0.00	875.315	19' 8"	58' 4"	1	Opn	Odd		Rect	
B N Mech Rm 33-8	2,356 LinFt	\$565.35	\$0.00	2,355.620	20' 4"	149' 8"	1	Opn	Odd		Rect	
B Alt#2 (part out)33-8 N Band Rm	1,417 LinFt	\$340.07	\$0.00	1,416.945	33' 8"	54' 3"	1	Opn	Odd		Rect	
Dumpster Privacy Wall	156 LinFt	\$37.40	\$0.00	155.833	8' 0"	28' 2"	1		Odd		Rect	
Dumpster Privacy Wall Ends	60 LinFt	\$14.40	\$0.00	60.000	8' 0"	6' 0"	2				Pier	
B Alcove B127a N Band Rm @26-0	317 LinFt	\$76.16	\$0.00	317.333	10' 8"	41' 4"	1		Odd		Rect	
B Alt2(out)Cor Ent ReturnsCol #3	25 LinFt	\$6.08	\$0.00	25.333	8' 8"	6' 4"	1		Odd		Rect	
A Corr Ent Returns	27 LinFt	\$6.40	\$0.00	26.667	8' 8"	6' 8"	1		Odd		Rect	
B Top of Piers @ Ent	183 LinFt	\$44.01	\$0.00	183.377	4' 4"	55' 2"	1	Opn	Odd		Rect	
B Piers @ Ent B123 Arch	89 LinFt	\$21.28	\$0.00	88.667	9' 8"	6' 4"	2		Odd		Pier	
B N Wall Top of Main ent.	530 LinFt	\$127.27	\$0.00	530.275	18' 8"	55' 4"	1	Opn	Odd		Rect	
B N Main Ent Splitface Piers	194 LinFt	\$46.59	\$0.00	194.145	10' 0"	25' 9"	1				Rect	
B N Main Ent Brick Piers	383 LinFt	\$91.98	\$0.00	383.236	10' 0"	49' 9"	1				Rect	
B Face of Pier veneer	65 LinFt	\$15.68	\$0.00	65.333	9' 8"	9' 4"	1		Odd		Rect	
B 2x1-2 Pier @ 6.8 & 8	56 LinFt	\$13.44	\$0.00	56.000	9' 8"	4' 0"	2		Odd		Pier	
B 2x1-2 Pier @ 6.8 & 8	89 LinFt	\$21.28	\$0.00	88.667	9' 8"	6' 4"	2		Odd		Pier	
Material [HDL9GA14"] Totals	14,651 LinFt	\$3,516.29	\$0.00	14,651.197	Mat. Lay Rate	0.0 LinFt/Day						
HDL9GA18" Hot-Dipp./Ladder 9ga--18"	Lay	0.0 LinFt/Day	\$0.280/ LinFt	LinFt	Show as LinFt							
A West wall Gym	2,276 LinFt	\$637.27	\$0.00	2,275.961	33' 8"	89' 8"	1	Opn	Odd		Rect	
CA#1 Alt#1 North Brick&CMU	756 LinFt	\$211.68	\$0.00	756.000	40' 0"	57' 0"	1	Opn	Odd		Rect	
C Col 23 F.5 to N 3 story Classr	3,369 LinFt	\$943.21	\$0.00	3,368.594	40' 0"	290' 2"	1	Opn	Odd		Rect	
B E6 between 12.3 & 17 South Wall	1,306 LinFt	\$365.57	\$0.00	1,305.608	26' 0"	94' 0"	1	Opn	Odd		Rect	
B W Wall (12 CMU) Band B127	570 LinFt	\$159.59	\$0.00	569.972	20' 0"	57' 0"	1	Opn	Odd		Rect	
B2 (12 CMU) IDF D226	78 LinFt	\$21.84	\$0.00	78.000	15' 0"	12' 0"	1		Odd		Rect	
B Alt#2 (part out)22-8 N Band Rm	1,086 LinFt	\$303.96	\$0.00	1,085.559	22' 8"	82' 4"	1	Opn	Odd		Rect	
B E Wall (12 CMU) Band B127	456 LinFt	\$127.68	\$0.00	456.000	22' 8"	35' 0"	1		Odd		Rect	
A N Wall (12 CMU) Serving #119	505 LinFt	\$141.40	\$0.00	504.988	22' 8"	45' 0"	1	Opn	Odd		Rect	
A 18" Ext @ Cafetorium	1,381 LinFt	\$386.66	\$0.00	1,380.929	22' 8"	114' 0"	1	Opn	Odd	Adj	Rect	
B H7 between 6 & 6.8 N Ext Wall	344 LinFt	\$96.19	\$0.00	343.522	16' 0"	50' 8"	1	Opn	Odd		Rect	
B West Wall Vest B123 with Insul	149 LinFt	\$41.74	\$0.00	149.085	28' 8"	9' 8"	1	Opn	Odd		Rect	
B North wall of Cafetorium	1,194 LinFt	\$334.23	\$0.00	1,193.687	26' 0"	79' 4"	1	Opn	Odd	Adj	Rect	
B West Wall Vest B123 NO Insul	436 LinFt	\$122.07	\$0.00	435.979	28' 8"	26' 0"	1	Opn	Odd		Rect	
B East Wall Vest B123 NO Insul	107 LinFt	\$29.88	\$0.00	106.712	13' 4"	26' 8"	1	Opn	Odd		Rect	
B N Wall Office B13 & 140	107 LinFt	\$29.93	\$0.00	106.889	13' 4"	24' 0"	1	Opn	Odd		Rect	
B N Wall Confere B138 with Insul	221 LinFt	\$61.74	\$0.00	220.501	13' 4"	49' 8"	1	Opn	Odd		Rect	
B H10 between 6.9 & 9	158 LinFt	\$44.30	\$0.00	158.225	19' 0"	18' 4"	1	Opn	Odd		Rect	
B East Wall Vest B123 with Insul	63 LinFt	\$17.52	\$0.00	62.579	13' 4"	12' 8"	1	Opn	Odd		Rect	
B E6 between 12????????	591 LinFt	\$165.38	\$0.00	590.632	28' 8"	39' 0"	1	Opn	Odd		Rect	
B E&W Walls Office B136 & 140	54 LinFt	\$15.18	\$0.00	54.207	10' 0"	25' 1"	1				Rect	
Material [HDL9GA18"] Totals	15,204 LinFt	\$4,257.02	\$0.00	15,203.630	Mat. Lay Rate	0.0 LinFt/Day						
MGL9GA04" Mill-Gal./Ladder 9ga-- 4"	Lay	0.0 LinFt/Day	\$0.070/ LinFt	LinFt	Show as LinFt							
C3 6 4"CMU 13-0 Reg Wall	555 LinFt	\$38.85	\$0.00	555.000	13' 0"	55' 8"	1		Odd		Rect	
C2 6 4"CMU 13-0 Reg Wall	555 LinFt	\$38.85	\$0.00	555.000	13' 0"	55' 8"	1		Odd		Rect	

Sample Reports
Quantity/Bid Price Report

WIR Continued

Wall

						Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
C1	6	4"CMU 13-0	Reg Wall	555	LinFt	\$38.85	\$0.00	555.000	13' 0"	55' 8"	1			Odd		Rect
B2	4"	CMU 12-8	FireSafe 2nd Floor	693	LinFt	\$48.51	\$0.00	693.000	12' 8"	70' 0"	1					Rect
B	4"	CMU 13-0	FireSafe Reg Wall	1,392	LinFt	\$97.44	\$0.00	1,392.000	13' 0"	139' 8"	1			Odd		Rect
A	4"	CMU	Front of Stage A110	105	LinFt	\$7.33	\$0.00	104.667	2' 11"	47' 4"	1			Odd		Rect
A	4"	CMU	Pipe Chase A103	59	LinFt	\$4.11	\$0.00	58.667	15' 4"	5' 4"	1					Rect
A#3C	Alt3	out (4 CMU)	Serving #119	92	LinFt	\$6.42	\$0.00	91.667	15' 4"	8' 4"	1					Rect
Material [MGL9GA04"] Totals				4,005	LinFt	\$280.35	\$0.00	4,005.000	Mat. Lay Rate		0.0 LinFt/Day					
MGL9GA08" Mill-Gal./Ladder 9ga-- 8"				Lay	0.0 LinFt/Day	\$0.120/ LinFt		LinFt	Show as LinFt							
A	(8	CMU)	Corr A106 SGT	277	LinFt	\$33.19	\$0.00	276.610	21' 4"	22' 4"	1	Opn	Odd	Adj		Rect
CA#1	Copy	Reg	CMU Stair #133	111	LinFt	\$13.32	\$0.00	111.000	13' 4"	11' 4"	1					Rect
CA#1	2Copy	Stair	C133 SGT	129	LinFt	\$15.48	\$0.00	129.000	13' 4"	13' 4"	1			Odd	Adj	Rect
CA#1	3rdStair	C133	SGT	129	LinFt	\$15.48	\$0.00	129.000	13' 4"	13' 4"	1			Odd	Adj	Rect
C3	3	Copy	5 8" CMU Corr 2side SGT	47	LinFt	\$5.63	\$0.00	46.920	13' 4"	8' 0"	1	Opn	Odd			Rect
CA#1	3rd	Fl	8" CMU Corr 2side SGT	47	LinFt	\$5.63	\$0.00	46.920	13' 4"	8' 0"	1	Opn	Odd			Rect
CA#1	Copy	5 8"	CMU Corr 2side SGT	47	LinFt	\$5.63	\$0.00	46.920	13' 4"	8' 0"	1	Opn	Odd			Rect
CA#1	2	Copy	Reg CMU Stair #133	165	LinFt	\$19.80	\$0.00	165.000	13' 4"	17' 4"	1					Rect
CA#1	2	Copy	Reg CMU Stair #133	165	LinFt	\$19.80	\$0.00	165.000	13' 4"	17' 4"	1					Rect
C2	Reg	CMU	Stair #100	111	LinFt	\$13.32	\$0.00	111.000	13' 4"	11' 4"	1					Rect
C3	2Copy	Stair	C100 SGT	225	LinFt	\$27.00	\$0.00	225.000	13' 4"	23' 0"	1			Odd		Rect
C3	2	Copy	Reg CMU Stair #133	165	LinFt	\$19.80	\$0.00	165.000	13' 4"	17' 4"	1					Rect
C2	3	Copy	5 8" CMU Corr 2side SGT	47	LinFt	\$5.63	\$0.00	46.920	13' 4"	8' 0"	1	Opn	Odd			Rect
C2	2	Copy	Reg CMU Stair #133	165	LinFt	\$19.80	\$0.00	165.000	13' 4"	17' 4"	1					Rect
CA#1	Alt#1	Reg	CMU Stair #133	333	LinFt	\$39.96	\$0.00	333.000	13' 4"	34' 0"	1					Rect
C2	2Copy	Stair	C100 SGT	225	LinFt	\$27.00	\$0.00	225.000	13' 4"	23' 0"	1			Odd		Rect
CA#1	Alt#1	C133	Stair	374	LinFt	\$44.83	\$0.00	373.617	13' 4"	41' 4"	1	Opn	Odd			Rect
C1	Stair	C100	8" CMU Reg Wall	339	LinFt	\$40.68	\$0.00	339.000	13' 4"	34' 8"	1					Rect
C1	4	8"CMU	13-0 Reg Wall	992	LinFt	\$118.99	\$0.00	991.551	13' 0"	103' 4"	1	Opn	Odd			Rect
C1	Stair	C100	SGT	377	LinFt	\$45.20	\$0.00	376.641	13' 4"	41' 8"	1	Opn	Odd			Rect
C2	1	8"	CMU Corr Bearing no SGT	5,524	LinFt	\$662.82	\$0.00	5,523.534	13' 4"	587' 8"	1	Opn	Odd			Rect
C1	3	8"CMU	Corr SGT13-0 FireS	2,436	LinFt	\$292.37	\$0.00	2,436.449	13' 0"	264' 8"	1	Opn	Odd			Rect
C3	5	8"	CMU Corr 2side SGT	91	LinFt	\$10.92	\$0.00	91.008	13' 0"	13' 0"	1	Opn	Odd			Rect
C3	4	8"CMU	13-0 Reg Wall	992	LinFt	\$118.99	\$0.00	991.551	13' 0"	103' 4"	1	Opn	Odd			Rect
C3	3	8"CMU	Corr SGT13-0 FireS	2,436	LinFt	\$292.37	\$0.00	2,436.449	13' 0"	264' 8"	1	Opn	Odd			Rect
C2	3	8"CMU	Corr SGT13-0 FireS	2,436	LinFt	\$292.37	\$0.00	2,436.449	13' 0"	264' 8"	1	Opn	Odd			Rect
C3	1	8"	CMU Corr Bearing no SGT	5,524	LinFt	\$662.82	\$0.00	5,523.534	13' 4"	587' 8"	1	Opn	Odd			Rect
C2	5	8"	CMU Corr 2side SGT	91	LinFt	\$10.92	\$0.00	91.008	13' 0"	13' 0"	1	Opn	Odd			Rect
C2	4	8"CMU	13-0 Reg Wall	992	LinFt	\$118.99	\$0.00	991.551	13' 0"	103' 4"	1	Opn	Odd			Rect
C2	3	8"CMU	Corr SGT13-0 FireS	2,436	LinFt	\$292.37	\$0.00	2,436.449	13' 0"	264' 8"	1	Opn	Odd			Rect
C1	5	8"	CMU Corr 2side SGT	91	LinFt	\$10.92	\$0.00	91.008	13' 0"	13' 0"	1	Opn	Odd			Rect
C1	1	8"	CMU Corr Bearing no SGT	5,524	LinFt	\$662.82	\$0.00	5,523.534	13' 4"	587' 8"	1	Opn	Odd			Rect
B	8"	CMU	Corr with SGT base	4,530	LinFt	\$543.58	\$0.00	4,529.874	13' 4"	497' 4"	1	Opn	Odd			Rect
B2	8"	CMU	Corr with SGT base2nd F	1,939	LinFt	\$232.73	\$0.00	1,939.378	12' 0"	242' 0"	1	Opn	Odd			Rect
B	8"	CMU	Corr Bearing no SGT	555	LinFt	\$66.62	\$0.00	555.158	13' 4"	55' 8"	1			Odd		Rect
B2	8"	CMU	Corr with BB No SGT 2 f	349	LinFt	\$41.92	\$0.00	349.333	12' 0"	39' 8"	1			Odd		Rect
B2	8"	CMU	CorSGTnoBB 2nd F	184	LinFt	\$22.05	\$0.00	183.714	12' 0"	39' 4"	1	Opn	Odd			Rect
B2	8"	CMU	2nd Fl no base	2,931	LinFt	\$351.69	\$0.00	2,930.710	12' 8"	303' 4"	1	Opn				Rect
B2	8"	CMU	CorSGTnoBB 12-8	1,405	LinFt	\$168.55	\$0.00	1,404.619	12' 8"	154' 4"	1	Opn	Odd			Rect
B2	8"	CMU	@ Learn Cent @ Door	90	LinFt	\$10.80	\$0.00	90.000	7' 4"	17' 0"	1					Rect
B2	8"	CMU	CorSGTnoBB12-8"	90	LinFt	\$10.80	\$0.00	90.000	12' 8"	10' 0"	1			Odd		Rect
B	8"	CMU	Band rm B127	95	LinFt	\$11.40	\$0.00	95.000	8' 0"	18' 0"	1			Odd		Rect
B	8"	CMU	13-0 FireSafe Reg Wall	6,687	LinFt	\$802.38	\$0.00	6,686.531	13' 0"	690' 7"	1	Opn	Odd			Rect

Sample Reports
Quantity/Bid Price Report

WIR Continued

Wall

		Quantity	Extended Mat. Cost	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
B	8"CMU Corr SGT13-0 FireS	739 LinFt	\$88.68	\$0.00	738.978	13' 0"	83' 7"	1	Opn	Odd		Rect
B	8" CMU Corr SGT base DisplayCa	299 LinFt	\$35.93	\$0.00	299.441	13' 4"	59' 0"	1	Opn	Odd		Rect
B	8" CMU Corr 2side SGT	196 LinFt	\$23.54	\$0.00	196.200	13' 0"	33' 4"	1	Opn	Odd		Rect
A	(8 CMU) Corr A104 SGT	301 LinFt	\$36.08	\$0.00	300.700	15' 4"	29' 4"	1	Opn	Odd		Rect
A	8" CMU A 101, 102, 103, 117&8	1,112 LinFt	\$133.39	\$0.00	1,111.597	15' 4"	96' 4"	1	Opn			Rect
A	8" CMU Projection Rm Walls	280 LinFt	\$33.60	\$0.00	280.000	14' 2"	26' 0"	1				Rect
A	8" CMU Slope Hand Rail	126 LinFt	\$15.12	\$0.00	126.000	4' 0"	57' 0"	1		Odd		Rect
A	8"CMU Slope Hand Rail on Stage	136 LinFt	\$16.28	\$0.00	135.667	6' 0"	34' 8"	1		Odd		BotL
A#3C	Alt3 out (8 CMU) Corr A104 SGT	359 LinFt	\$43.03	\$0.00	358.598	15' 4"	35' 0"	1	Opn	Odd		Rect
A#3C	Alt3 out (8 CMU) Serving #119	501 LinFt	\$60.10	\$0.00	500.810	15' 4"	45' 0"	1	Opn			Rect
Material [MGL9GA08"] Totals		55,943 LinFt	\$6,713.15	\$0.00	55,942.933	Mat. Lay Rate		0.0	LinFt/Day			
MGL9GA10" Mill-Gal./Ladder 9ga--10"		Lay	0.0 LinFt/Day	\$0.080/ LinFt	LinFt							Show as LinFt
B	10" CMU Band Small Rms	1,020 LinFt	\$81.60	\$0.00	1,020.000	21' 4"	62' 0"	1				Rect
MGL9GA12" Mill-Gal./Ladder 9ga--12"		Lay	0.0 LinFt/Day	\$0.020/ LinFt	LinFt							Show as LinFt
A	Alt2 12CMU Col 4.3 @ C&D (Out)	940 LinFt	\$18.79	\$0.00	939.700	33' 8"	48' 0"	1	Opn	Odd		Rect
A	(12 CMU) Projection RM Radi	701 LinFt	\$14.01	\$0.00	700.627	24' 10"	50' 4"	1	Opn	Odd	Adj	Rect
A	(12 CMU) So Gym A108 "no" SGT	2,047 LinFt	\$40.94	\$0.00	2,046.965	33' 8"	99' 4"	1	Opn	Odd		Rect
A	(12 CMU) No Gym A108 "no" SGT	2,008 LinFt	\$40.16	\$0.00	2,008.041	33' 8"	98' 4"	1	Opn	Odd		Rect
A	(12 CMU) Gym A108 SGT	2,111 LinFt	\$42.21	\$0.00	2,110.527	33' 8"	125' 0"	1	Opn	Odd		Rect
A	(12 CMU) Corr A106 SGT	1,735 LinFt	\$34.70	\$0.00	1,735.000	21' 4"	104' 8"	1		Odd		Rect
A	(12 CMU) Around Stage A110	2,482 LinFt	\$49.64	\$0.00	2,482.095	21' 4"	176' 0"	1	Opn			Rect
Material [MGL9GA12"] Totals		12,023 LinFt	\$240.46	\$0.00	12,022.955	Mat. Lay Rate		0.0	LinFt/Day			
MGL9GA14" Mill-Gal./Ladder 9ga--14"		Lay	0.0 LinFt/Day	\$0.220/ LinFt	LinFt							Show as LinFt
B	North wall of Cafetorium SGT	304 LinFt	\$66.79	\$0.00	303.608	26' 0"	22' 0"	1	Opn	Odd		Rect
Class Totals Wire		121,532 LinFt	\$18,411.51	\$0.00	121531.727	Avg. Lay Rate		0.0	LinFt/Day			

Sample Reports
Quantity/Bid Price Report

Crew Section

Ratio of Production Masons to

ID	Description	Production Masons	Prod-Mason Days	Crew Days	Cost Per Day Whole Crew	Cost Per Day Per Prod-Mason	Extended Labor Cost	Ratio of Production Masons to			
								Super	Layout	Saw	Tender/Other
X	2BLF,10L, 2E, 1SM, 1Layout,18BL,2Lull	18.50	1,651.0	89.246	\$14,049.87	\$759.45	\$1,253,888.33	7.20	36.00	18.00	1.45

Totals by Labor ID

ID	Hours	Estimated				Total	Cost / Hour
		Base	Fringe	Burden			
Brick#21	14,279.28	\$436,232.15	\$164,354.57	\$139,594.29	\$740,181.01	\$51.84	
BrickForeman#21	1,427.93	\$49,334.93	\$16,435.46	\$15,787.18	\$81,557.56	\$57.12	
Engineer#150	1,517.17	\$49,821.32	\$33,150.25	\$15,318.63	\$98,290.20	\$64.79	
Laborer	7,362.76	\$216,755.08	\$51,539.29	\$65,565.18	\$333,859.55	\$45.34	
	24,587.14	\$752,143.48	\$265,479.57	\$236,265.27	\$1,253,888.33	\$51.00	

Totals by Equipment ID

ID	Description	Cost	Days	Cost / Day
Lull 644	Lull 644	\$20,526.47	178.491	\$115.00

Sample Reports

Quantity/Bid Price Report

		Costs & Taxes	Overhead	Profit	OH + Profit	Totals	% of Bid
Material Costs		\$509,883.65					
Misc. Taxable Costs		\$0.00					
Taxable Sub-Total		\$509,883.65					
	Tax 0.000%	\$0.00	5.00%	0.00%			
Material + Misc. Taxable Costs + Tax		\$509,883.65	\$25,494.18	\$0.00	\$25,494.18	\$535,377.83	26.1%
Base	59.985%	\$752,143.48					
Fringe	21.173%	\$265,479.57					
Burden	18.843%	\$236,265.27	5.00%	5.00%			
Crew Labor Cost		\$1,253,888.33	\$62,694.42	\$65,829.14	\$128,523.55	\$1,382,411.88	67.4%
Subbed Out			0.00%	0.00%			
Cleaning Cost		\$16,777.87	\$0.00	\$0.00	\$0.00	\$16,777.87	0.8%
Equipment		\$20,526.47	\$1,026.32	\$0.00	\$1,026.32	\$21,552.80	1.1%
Mobilization		\$2,800.00					
Bond 1 1/2%		\$0.00					
Misc. & Rebar/G		\$24,000.00					
Clean-Up		\$5,000.00					
Dumpsters 40		\$12,000.00					
Winter Protect		\$50,000.00	0.00%	0.00%			
Misc. Sub-Total		\$93,800.00	\$0.00	\$0.00	\$0.00	\$93,800.00	4.6%

	Percent of Cost	4.71%	3.47%	8.18%	Bid Price
Grand Totals	\$1,894,876.32	\$89,214.92	\$65,829.14	\$155,044.06	\$2,049,920.38

	Without Misc. or OH&P	With Misc. and OH&P	Total Square Feet
Average Cost Per Square Foot	\$11.80	\$13.42	152,696.50

- Project Notes:**
1. Adding in \$20,000.00 for misc. grout, rods & Steel Angles anchored to masonry for Exp Jts.
 2. No steel supports at top of CMU walls.
 3. Mason cont shall provide engineered bracing to laterally support masonry walls durning const & until roof deck is installed.