

Wall

Quantity	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
----------	----------	--------	--------	--------	-----	-----	-----	-----	-------

Classification **BOL**

**ANCHOR BOLTS**

<b>BOLTS8-IN</b>	100 CNT BOXES OF 8" BOLTS	Lay	1,200.0	Each/Day	\$0.400 / Each	Each	Show as Each						
12" Exterior-Vert Rebar			79	Each	\$36.02	79.000		14' 0"	316' 0"	1	Opn	Odd	Rect
Piers			8	Each	\$3.65	8.000		14' 0"	8' 0"	4	Odd		Pier
Material [BOLTS8-IN] Totals			87	Each	\$39.67	87.000		Mat. Lay Rate	1,200.0	Each/Day			

Classification **BRI**

**BRICKS**

<b>M</b>	Modular Brick	Lay	450.0	Pieces/Day	\$0.300 / Piece	SqFt	6.750	Pieces per SqFt					
12" Exterior-Vert Rebar			14,364	Pieces	\$17,465.67	2,127.995		14' 0"	316' 0"	1	Opn	Odd	Rect
Piers			1,440	Pieces	\$1,750.95	213.333		14' 0"	8' 0"	4	Odd		Pier
Wall Between Piers			559	Pieces	\$679.46	82.784		3' 4"	16' 8"	1	Opn		Rect
Material [M] Totals			16,363	Pieces	\$19,896.08	2,424.112		Mat. Lay Rate	450.0	Pieces/Day			
<b>MS</b>	Modular Brick Soldier	Lay	300.0	Pieces/Day	\$0.300 / Piece	SqFt	6.752	Pieces per SqFt					
12" Exterior-Vert Rebar			3,919	Pieces	\$7,147.83	580.443		14' 0"	316' 0"	1	Opn	Odd	Rect
Piers			396	Pieces	\$722.45	58.667		14' 0"	8' 0"	4	Odd		Pier
Wall Between Piers			41	Pieces	\$74.22	6.027		3' 4"	16' 8"	1	Opn		Rect
Material [MS] Totals			4,356	Pieces	\$7,944.50	645.137		Mat. Lay Rate	300.0	Pieces/Day			
Class Totals BRICKS			20,719	Pieces	\$27,840.58	3,069.249		Avg. Lay Rate	407.2	Pieces/Day			

Classification **CMU**

**C.M.U.**

<b>MW04</b>	4" Mediumweight CMU	Lay	185.0	Pieces/Day	\$0.360 / Piece	SqFt	1.125	Pieces per SqFt					
4" Interior CMU			3,992	Pieces	\$11,806.17	3,548.172		12' 2"	360' 6"	1	Opn	Odd	Rect
<b>MW042RIP</b>	4" Med 2" Rip CMU	Lay	175.0	Pieces/Day	\$0.120 / Piece	SqFt	4.500	Pieces per SqFt					
4" Interior CMU			268	Pieces	\$839.06	59.634		12' 2"	360' 6"	1	Opn	Odd	Rect
<b>MW04B</b>	4" Mediumweight CMU-Bull	Lay	175.0	Pieces/Day	\$0.460 / Piece	SqFt	1.125	Pieces per SqFt					
4" Interior CMU			150	Pieces	\$468.84	133.287		12' 2"	360' 6"	1	Opn	Odd	Rect
<b>MW04BB</b>	4" Mediumweight CMU-B.B.	Lay	165.0	Pieces/Day	\$0.460 / Piece	SqFt	1.125	Pieces per SqFt					
4" Interior CMU			66	Pieces	\$217.58	58.321		12' 2"	360' 6"	1	Opn	Odd	Rect
<b>MW04BH</b>	4" Med CMU-Bull Half	Lay	175.0	Pieces/Day	\$0.460 / Piece	SqFt	2.250	Pieces per SqFt					
4" Interior CMU			154	Pieces	\$482.26	68.551		12' 2"	360' 6"	1	Opn	Odd	Rect
<b>MW06</b>	6" Mediumweight CMU	Lay	175.0	Pieces/Day	\$0.480 / Piece	SqFt	1.125	Pieces per SqFt					
12" Exterior-Vert Rebar			3,813	Pieces	\$11,920.52	3,388.889		14' 0"	316' 0"	1	Opn	Odd	Rect
6" Interior CMU			1,516	Pieces	\$4,738.57	1,347.128		12' 2"	134' 0"	1	Opn	Odd	Rect
Piers			120	Pieces	\$375.20	106.667		14' 0"	8' 0"	4	Odd		Pier
Material [MW06] Totals			5,448	Pieces	\$17,034.29	4,842.683		Mat. Lay Rate	175.0	Pieces/Day			
<b>MW062RIP</b>	6" Med 2" Rip CMU	Lay	175.0	Pieces/Day	\$0.120 / Piece	SqFt	4.500	Pieces per SqFt					
6" Interior CMU			101	Pieces	\$314.23	22.333		12' 2"	134' 0"	1	Opn	Odd	Rect

Wall

CMU Continued

		Quantity	Unit	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
<b>MW06B</b>	6" Mediumweight CMU-Bull	Lay	165.0 Pieces/Day	\$0.580 / Piece	SqFt		1.125	Pieces per SqFt				
	12" Exterior-Vert Rebar		115 Pieces	\$381.36	102.222	14' 0"	316' 0"	1	Opn	Odd		Rect
	6" Interior CMU		58 Pieces	\$191.04	51.208	12' 2"	134' 0"	1	Opn	Odd		Rect
Material [MW06B] Totals			173 Pieces	\$572.41	153.431	Mat. Lay Rate	165.0	Pieces/Day				
<b>MW06BB</b>	6" Mediumweight CMU-B.B.	Lay	155.0 Pieces/Day	\$0.580 / Piece	SqFt		1.125	Pieces per SqFt				
	12" Exterior-Vert Rebar		308 Pieces	\$1,085.52	273.333	14' 0"	316' 0"	1	Opn	Odd		Rect
	6" Interior CMU		21 Pieces	\$73.91	18.611	12' 2"	134' 0"	1	Opn	Odd		Rect
	Piers		6 Pieces	\$21.18	5.333	14' 0"	8' 0"	4	Odd			Pier
Material [MW06BB] Totals			334 Pieces	\$1,180.61	297.277	Mat. Lay Rate	155.0	Pieces/Day				
<b>MW06BH</b>	6"Lt Wt CMU-1/2 Bullnose	Lay	170.0 Pieces/Day	\$0.570 / Piece	SqFt		2.250	Pieces per SqFt				
	12" Exterior-Vert Rebar		183 Pieces	\$587.40	81.111	14' 0"	316' 0"	1	Opn	Odd		Rect
	6" Interior CMU		59 Pieces	\$191.09	26.386	12' 2"	134' 0"	1	Opn	Odd		Rect
Material [MW06BH] Totals			242 Pieces	\$778.49	107.498	Mat. Lay Rate	170.0	Pieces/Day				
Class Totals C.M.U.			10,927 Pieces	\$33,693.95	9,291.187	Avg. Lay Rate	177.5	Pieces/Day				

Classification **DRI**

Drip Edging

<b>COPPERDRI</b>	Copper Drip Edge	Lay	2,000.0 LinFt/Day	\$1.200 / LinFt	LinFt			Show as LinFt				
	12" Exterior-Vert Rebar		276 LinFt	\$75.60	276.333	14' 0"	316' 0"	1	Opn	Odd		Rect
	Piers		19 LinFt	\$5.11	18.667	14' 0"	8' 0"	4	Odd			Pier
Material [COPPERDRI] Totals			295 LinFt	\$80.71	295.000	Mat. Lay Rate	2,000.0	LinFt/Day				

Classification **FLA**

Flashing

<b>IPCO18"</b>	IPCO 18" Flashing	Lay	3,000.0 LinFt/Day	\$1.120 / LinFt	LinFt			Show as LinFt				
	12" Exterior-Vert Rebar		276 LinFt	\$50.40	276.333	14' 0"	316' 0"	1	Opn	Odd		Rect
	Piers		19 LinFt	\$3.40	18.667	14' 0"	8' 0"	4	Odd			Pier
Material [IPCO18"] Totals			295 LinFt	\$53.81	295.000	Mat. Lay Rate	3,000.0	LinFt/Day				

Classification **GRO**

Grout

<b>2500PSI</b>	2500 PSI Grout in Cu.Ft.	Lay	175.0 CbcFt/Day	\$2.750 / CbcFt	CbcFt			Show as CbcFt				
	12" Exterior-Vert Rebar		177 CbcFt	\$552.62	176.743	14' 0"	316' 0"	1	Opn	Odd		Rect
	4" Interior CMU		6 CbcFt	\$18.52	5.924	12' 2"	360' 6"	1	Opn	Odd		Rect
	6" Interior CMU		4 CbcFt	\$13.19	4.219	12' 2"	134' 0"	1	Opn	Odd		Rect
	Piers		1 CbcFt	\$4.02	1.285	14' 0"	8' 0"	4	Odd			Pier
Material [2500PSI] Totals			188 CbcFt	\$588.35	188.170	Mat. Lay Rate	175.0	CbcFt/Day				

Classification **INR**

Rigid Insul.

<b>BLUE2"</b>	Blue 2" Rigid Insulation	Lay	1,500.0 SqFt/Day	\$0.590 / SqFt	SqFt			Show as SqFt				
	12" Exterior-Vert Rebar		3,883 SqFt	\$1,416.40	3,882.889	14' 0"	316' 0"	1	Opn	Odd		Rect
	Piers		261 SqFt	\$95.33	261.333	14' 0"	8' 0"	4	Odd			Pier

Wall

INR Continued

	Quantity	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape	
Material [BLUE2"] Totals	4,144 SqFt	\$1,511.73	4,144.222	Mat. Lay Rate	1,500.0	SqFt/Day					
Classification	<b>LIC</b>		<b>Limestone</b>								
<b>COPING CF</b>	Limestone Coping in Cu Ft	Lay	12.5 CbcFt/Day	\$24.000 / CbcFt	CbcFt	Show as CbcFt					
12" Exterior-Vert Rebar	195 CbcFt			\$8,535.88	195.000	14' 0"	316' 0"	1	Opn	Odd	Rect
<b>PIER CAP</b>	Limestone Cap	Lay	5.5 Pieces/Day	\$72.000 / Piece	CbcFt	2.722 CbcFt per Piece					
Piers	4 Pieces			\$397.21	10.889	14' 0"	8' 0"	4	Odd	Pier	
Class Totals Limestone				\$8,933.08	205.889						

Classification	<b>LIL</b>		<b>Limestone</b>								
<b>2X5SILL</b>	2-1/4 x 5 Sills L.F.	Lay	280.0 LinFt/Day	\$2.750 / LinFt	LinFt	Show as LinFt					
12" Exterior-Vert Rebar	45 LinFt			\$87.94	45.000	14' 0"	316' 0"	1	Opn	Odd	Rect
<b>COP ENT</b>	Limestone Coping - LF	Lay	50.0 LinFt/Day	\$12.350 / LinFt	LinFt	Show as LinFt					
Wall Between Piers	17 LinFt			\$182.39	16.667	3' 4"	16' 8"	1	Opn	Rect	
Class Totals Limestone	62 LinFt			\$270.33	61.667	Avg. Lay Rate	124.8	LinFt/Day			

Classification	<b>LIS</b>		<b>Limestone</b>								
<b>8" BAND</b>	Limestone Band	Lay	8.0 Pieces/Day	\$2.500 / Piece	SqFt	2.667 SqFt per Piece					
12" Exterior-Vert Rebar	134 Pieces			\$9,199.30	358.666	14' 0"	316' 0"	1	Opn	Odd	Rect
Piers	15 Pieces			\$1,003.15	39.111	14' 0"	8' 0"	4	Odd	Pier	
Material [8" BAND] Totals	149 Pieces			\$10,202.45	397.777	Mat. Lay Rate	8.0	Pieces/Day			
<b>ASHLER SF</b>	Limestone in Sq Ft	Lay	8.0 Pieces/Day	\$5.000 / Piece	SqFt	5.333 SqFt per Piece					
12" Exterior-Vert Rebar	135 Pieces			\$9,244.90	720.887	14' 0"	316' 0"	1	Opn	Odd	Rect
Piers	15 Pieces			\$1,003.15	78.222	14' 0"	8' 0"	4	Odd	Pier	
Material [ASHLER SF] Totals	150 Pieces			\$10,248.05	799.109	Mat. Lay Rate	8.0	Pieces/Day			
<b>QUOIN1</b>	Limestone Quoin 1st	Lay	8.0 Pieces/Day	\$0.833 / Piece	SqFt	1.125 Pieces per SqFt					
12" Exterior-Vert Rebar	77 Pieces			\$5,266.71	68.447	14' 0"	316' 0"	1	Opn	Odd	Rect
<b>QUOIN2</b>	Limestone Quoin 2nd	Lay	8.0 Pieces/Day	\$0.625 / Piece	SqFt	1.500 Pieces per SqFt					
12" Exterior-Vert Rebar	67 Pieces			\$4,559.99	44.447	14' 0"	316' 0"	1	Opn	Odd	Rect
Class Totals Limestone	443 Pieces			\$30,277.20	1,309.780	Avg. Lay Rate	8.0	Pieces/Day			

Classification	<b>MOR</b>		<b>Mortar (CuFt)</b>								
<b>Mortar[A]</b>	[A] Type N Port/Lime	1:1:6 Mix		\$2.02 / CbcFt	CbcFt	Show as CbcFt					
12" Exterior-Vert Rebar	794 CbcFt			\$0.00	793.929	14' 0"	316' 0"	1	Opn	Odd	Rect
4" Interior CMU	175 CbcFt			\$0.00	175.483	12' 2"	360' 6"	1	Opn	Odd	Rect
6" Interior CMU	77 CbcFt			\$0.00	76.684	12' 2"	134' 0"	1	Opn	Odd	Rect
Piers	57 CbcFt			\$0.00	57.391	14' 0"	8' 0"	4	Odd	Pier	
Wall Between Piers	17 CbcFt			\$0.00	17.082	3' 4"	16' 8"	1	Opn	Rect	

Wall

MOR Continued

	Quantity	Lay-Cost	Amount	Height	Length	Qty	Opn	Odd	Adj	Shape
Mortar [A] Totals	1,121 CbcFt	\$0.00	1,120.569							

Classification **REB**

Rebar

#	Description	Lay	LinFt/Day	Cost / LinFt	LinFt	Height	Length	Qty	Opn	Odd	Adj	Shape
<b>#4</b>	#4 Rebar / Give Vert. Ht	1,800.0	LinFt/Day	\$0.240 / LinFt	LinFt							Show as LinFt
	12" Exterior-Vert Rebar	1,062	LinFt	\$322.83	1,062.000	14' 0"	316' 0"	1	Opn	Odd		Rect
<b>#4BB REBA</b>	#4 Bond Beam Rebar - 240"	1,800.0	LinFt/Day	\$0.240 / LinFt	LinFt							Show as LinFt
	12" Exterior-Vert Rebar	852	LinFt	\$258.99	852.000	14' 0"	316' 0"	1	Opn	Odd		Rect
	4" Interior CMU	176	LinFt	\$53.42	175.739	12' 2"	360' 6"	1	Opn	Odd		Rect
	6" Interior CMU	56	LinFt	\$16.97	55.832	12' 2"	134' 0"	1	Opn	Odd		Rect
	Piers	32	LinFt	\$9.73	32.000	14' 0"	8' 0"	4		Odd		Pier
Material [#4BB REBA] Totals		1,116	LinFt	\$339.12	1,115.570	Mat. Lay Rate 1,800.0 LinFt/Day						
Class Totals Rebar		2,178	LinFt	\$661.95	2,177.570	Avg. Lay Rate 1,800.0 LinFt/Day						

Classification **WEE**

Plastic Weeps

#	Description	Lay	Each/Day	Cost / Each	Each	Height	Length	Qty	Opn	Odd	Adj	Shape
<b>WEEPPLAS</b>	Plastic Weep Holes	3,000.0	Each/Day	\$0.110 / Each	Each							Show as Each
	12" Exterior-Vert Rebar	138	Each	\$25.17	138.000	14' 0"	316' 0"	1	Opn	Odd		Rect
	Piers	8	Each	\$1.46	8.000	14' 0"	8' 0"	4		Odd		Pier
Material [WEEPPLAS] Totals		146	Each	\$26.63	146.000	Mat. Lay Rate 3,000.0 Each/Day						

Classification **WIR**

Wire

#	Description	Lay	LinFt/Day	Cost / LinFt	LinFt	Height	Length	Qty	Opn	Odd	Adj	Shape
<b>HDT9GA12"</b>	Hot-Dipp./Truss 9ga--12"	0.0	LinFt/Day	\$0.230 / LinFt	LinFt							Show as LinFt
	12" Exterior-Vert Rebar	3,027	LinFt	\$0.00	3,027.333	14' 0"	316' 0"	1	Opn	Odd		Rect
	Piers	160	LinFt	\$0.00	160.000	14' 0"	8' 0"	4		Odd		Pier
	Wall Between Piers	28	LinFt	\$0.00	28.394	3' 4"	16' 8"	1	Opn			Rect
Material [HDT9GA12"] Totals		3,216	LinFt	\$0.00	3,215.728	Mat. Lay Rate 0.0 LinFt/Day						
<b>MGT9GA04"</b>	Mill-Gal./Truss 9ga-- 4"	0.0	LinFt/Day	\$0.100 / LinFt	LinFt							Show as LinFt
	4" Interior CMU	3,071	LinFt	\$0.00	3,071.254	12' 2"	360' 6"	1	Opn	Odd		Rect
<b>MGT9GA06"</b>	Mill-Gal./Truss 9ga-- 6"	0.0	LinFt/Day	\$0.100 / LinFt	LinFt							Show as LinFt
	6" Interior CMU	1,176	LinFt	\$0.00	1,175.500	12' 2"	134' 0"	1	Opn	Odd		Rect
Class Totals Wire		7,462	LinFt	\$0.00	7,462.482	Avg. Lay Rate 0.0 LinFt/Day						