

## Show Demo Project

Mortar Translation Report

### Mortar

<b>A</b>	<b>Type N Port/Lime 1:1:6 Mix</b>	
<b>Quantity</b>	<b>Description</b>	<b>Cost Code</b>

1,033.45	ft <sup>3</sup>	<b>52.89</b>	<b>Short Tons</b>
38.28	yd <sup>3</sup>	47.22	Long Tons
29.26	m <sup>3</sup>	47.98	Metric Tons

19.54	ft <sup>3</sup> /Short Ton
21.88	ft <sup>3</sup> /Long Ton
0.60992	m <sup>3</sup> /Metric Ton

- 172.24228 Bags Portland Cement
- 172.24228 Bags Lime
- 38.27606 Cubic Yard(s) Sand

### Mortar

<b>U</b>	<b>Silo Mix-Type M Port/Lim1:1/4:3 Mix</b>	
<b>Quantity</b>	<b>Description</b>	<b>Cost Code</b>

87.12	ft <sup>3</sup>	<b>5.00</b>	<b>Short Tons</b>
3.23	yd <sup>3</sup>	4.46	Long Tons
2.47	m <sup>3</sup>	4.53	Metric Tons

17.44	ft <sup>3</sup> /Short Ton
19.53	ft <sup>3</sup> /Long Ton
0.54437	m <sup>3</sup> /Metric Ton

- 29.03842 Bags Portland Cement
- 7.25961 Bags Lime
- 3.22649 Cubic Yard(s) Sand
- 3.22649 Rental On Silo Unit